WATER DISTRIBUTION SYSTEM

BASIS OF DESIGN REPORT

FOR

Cadre 4151 N. Craftsman Ct. COTTSDALE, ARIZONA

Disclaimer: If approved; the approval is granted under the condition that the final construction documents submitted for city review will match the information herein. Any subsequent changes in the water or sewer design that materially impact design criteria or standards will require re-analysis, re-submittal, and approval of a revised basis of design report prior to the plan review submission.; this approval is not a guarantee of construction document acceptance. For questions or clarifications contact the Water Resources Planning and Engineering Department at 480-312-5685.

FINAL Basis of Design

APPROVED AS NOTED

REVISE AND RESUBMIT

BY Idillon

Report

APPROVED

DATE 8/22/2018

TTY OF

SCOTTSDALE

9379 E San Salvador D Scottsdale, AZ 85258



May 10, 2018 Revised: August 20, 2018

PREPARED BY:

JACOBS WALLACE, LLC

2233 W. Bethany Home Rd. Phoenix, AZ 85015 602.757.5964

TABLE OF CONTENTS

INTRODUCTION	1
EXISTING CONDITIONS	1
PROPOSED CONDITIONS	1
SUMMARY	2

Appendix:

Vicinity Map Calculations City of Scottsdale Quarter Section Map Preliminary Design Plan

INTRODUCTION

The proposed project consists of a multi-story mixed use building. The bottom floor will be commercial/retail use along with a parking garage. The upper floors will be residential condominiums. The existing conditions include 2 buildings with associated site improvements sitting on 2 lots. The lots would be combined into one with the proposed project. The 0.24-acre site is located at the northeast corner of 3rd Street and Craftsman Ct. The site is bordered to the north by existing commercial development, to the west by Craftsman Ct., to the south by 3rd Street, and to the east by a public alleyway. The site lies within the Southwest Quarter of Section 22, Township 2 North, Range 4 East of Gila and Salt River Base and Meridian. See the Appendix for a vicinity map.

EXISTING CONDITIONS

There is an existing 8" DIP water main within the alley to the east. There are no services from this main to the existing lot. There is also a 8" DIP in Craftsman Ct. There are existing services from this main to the site.

PROPOSED CONDITIONS

The proposed project will install a new 6" fire line service to the proposed building. There will also be 2 new domestic services and master meters to the building as well. The new services will connect to the existing 8" main in the alley. One will be utilized for the residential portion and the other for the commercial portion. The existing service on Craftsman will be utilized for a landscape service.

All water line construction and design will conform to M.A.G. standards and specifications and the latest revision of the <u>City of Scottsdale Design Standards and Policies Manual</u>. All water demands are based on Figure 4.1-3, Average Day Water Demand per Dwelling Unit of the <u>City of Scottsdale Design Standards and Policies Manual</u>.

WATER ANALYSIS

Mixed Use: Retail: 4,097 sf Residential: 6 units (2-bedroom assumed)

Average Daily Flow:

Retail:	4,907sf * 0.8gpd/sf = 3925.6 gpd
Residential:	6 units * 185.3gpd/unit = 1111.8gpd
TOTAL=	5,037.4 GPD=3.5GPM

Maximum Daily Demand: Average Daily Demand x 2

5037gpd*2=10,074gpd = 7.0 gpm

Peak Demand: Maximum Daily Demand x 3.5

10074gpd*3.5 = 35,259gpd = **24.5gpm**

Fire Flow Demand: (Per City of Scottsdale DSPM Section 6-1.501)

1,500 gpm @ 30 psi (For commercial, industrial, and multi-family) Max Daily Demand + Fire Flow = 1,507 gpm @ 30 psi (COS requirement)

JACOBS WALLACE, LLC

ENGINEERING PLANNING MANAGEMENT

WATER MODEL RESULTS

A water model will not be completed for this project. There are no new fire hydrants being installed. A fire flow test was completed on the existing hydrant located near the southeast corner of the site to ensure adequate supply and fire protection for the site. The results:

EXISTING PRESSURE & FLOW

test taken 7-06-18 by EJ (See Attached)

Raw Data:

Static Pressure: 105 psi

Residual Pressure: 78 psi

Flow: 2,572 gpm

20psi Flow: 4,777 gpm

Data with required 33psi safety Factor:

Static Pressure: 72 psi

Residual Pressure: 45 psi

Flow: 2,572 gpm

20psi Flow: 3,664 gpm

CONCLUSION

Based on the information provided and the flow test results, the city system should be able to handle the proposed project demands. The proposed water usage is minimal and similar to what is being used currently in the existing state. The flow test shows that there is more than adequate flow and pressure for proper fire protection.

It is important to note that the actual available flow can be affected by varying seasonal and diurnal water demands, growth within the City, and system operations. This report solely describes the flow available at a design maximum day condition based on current flow tests.

APPENDIX



Flow Test Summary

Project Name: Project Address: Date of Flow Test: Time of Flow Test: Data Reliable Until: Conducted By: Witnessed By: City Forces Contacted: Permit Number:

EJE 18150 4100 N Craftsman Ct, Scottsdale, AZ 85251 2018-07-06 7:30 AM 2019-01-06 Tayler Lynch & Cesar Reyna (EJ Flow Tests) 602.999.7637 Brian Dick (602.228.2187) City of Scottsdale (602.228.2187) C55773

Note

Scottsdale requires a max static pressure of 72 psi for safety factor

Raw Flow Test Data

Static Pressure:	105.0 PSI
Residual Pressure:	78.0 PSI
Flowing GPM:	2,572
GPM @ 20 PSI:	4,777

Hydrant F₁

Pitot Pressure (1): 52 PSI Coefficient of Discharge (1): 0.9 Hydrant Orifice Diameter (1): 4 inches Additional Coefficient 0.83 on orifice #1

Data with a 33 PSI Safety Factor

Static Pressure:	72.0 PSI
Residual Pressure:	45.0 PSI
Flowing GPM:	2,572
GPM @ 20 PSI:	3,664



Static-Residual Hydrant

Flow Hydrant

Distance Between F1 and R 504 ft (measured linearly)

Static-Residual Elevation 1269 ft (above sea level)

Flow Hydrant (F1) Elevation 1267 ft (above sea level)

Elevation & distance values are approximate

EJ Flow Tests, LLC

21505 North 78th Ave. | Suite 130 | Peoria, Arizona 85382 | (602) 999-7637 | www.ejengineering.com John J. Echeverri I NICET Level IV 078493 SME LC-16 FP Contractor BOC 271705 A7 I NEPA CEPS 1915



Static-Residual Hydrant



Approximate Project Site

Flow Hydrant (only hydrant F1 shown for clarity)





Water Supply Curve N^{1.85} Graph



EJ Flow Tests, LLC 21505 North 78th Ave. | Suite 130 | Peoria, Arizona 85382 | (602) 999-7637 | www.ejengineering.com John L. Echeverri I NICET Level IV 078493 SME LC-16 EP Contractor ROC 271705 A7 I NEPA CEPS 1915

Vicinity Map



VICINITY MAP NOT TO SCALE

City Map





· · · ·

.