Engineering

Drainage Reports

Abbreveated Water & Sewer Need Reports

Water Study

Wastewater Study

Stormwater Waiver Application



# PRELIMINARY DRAINAGE REPORT WINFIELD HOTEL AND RESIDENCES

NEC Scottsdale Rd. & 3<sup>rd</sup> Ave. Scottsdale, AZ 85251

**Prepared For:** 

Plan #	
Accepted Corrections M. Rahman 6/6/18 Reviewed By Date	

**DESCO** 

P.O. Box 546 Okoboji, IA 51355

Prepared by:



#### **Sustainability Engineering Group**

8280 E. Gelding Drive, Suite 101 Scottsdale, AZ 85260 480.588.7226 www.azSEG.com

Project Number: 170144

Submittal Date: April 25, 2017 Resubmittal Date: October 6, 2017 Resubmittal Date: December 14, 2017 (Zoning) Resubmittal Date: May 7, 2018 (DRB)



EXPIRES 12-31-18

Case No.: 993-PA-2016; 7-ZN-2017; 1-II-2017

Plan Check No.: TBD



#### TABLE OF CONTENTS:

T/	BLE	OF CONTENTS:	
TA	BLE C	SHEET  OF CONTENTS  RODUCTION  ALI SAMIH FAKIH	1 2 4
2.	LOCA	ATION AND PROJECT DESCRIPTION	
	2.1.	LOCATION:	4
	2.2.	EXISTING AND PROPOSED DEVELOPMENTS SURROUNDING THE SITE: EXPIRES 12-31-18	4
	2.3.	EXISTING SITE DESCRIPTION:	4
	2.4.	PROPOSED SITE DEVELOPMENT:	5
	2.5.	FLOOD HAZARD ZONE:	5
3.	EXIS	TING DRAINAGE CONDITIONS	
	3.1.	OFF-SITE DRAINAGE:	5
	3.2.	ON-SITE DRAINAGE:	5
	3.3.	EXISTING STORM SEWER SYSTEMS:	6
4.	PRO	POSED STORM WATER MANAGEMENT	
	4.1.	DESIGN INTENT:	6
	4.2.	DESIGN STORM REQUIREMENTS:	6
	4.3.	CHARACTERISTICS OF BASINS:	6
	4.4.	OFF-SITE FLOW:	7
	4.5.	STORMWATER RETENTION:	7
	4.6.	ADEQ WATER QUALITY REQUIREMENTS	8
5.	<b>FLO</b> (5.1	OD SAFETY FOR DWELLING UNITS FINISHED FLOOR ELEVATIONS:	8
6.	CON	CLUSIONS	
	6.1	OVERALL PROJECT:	8
	6.2	PROJECT PHASING:	9
7.	WAF	RNING AND DISCLAIMER OF LIABILITY	
8.	REF	ERENCES	



#### LIST OF FIGURES:

FIGURE 1 - Vicinity Map

FIGURE 2 - Aerial FIGURE 3 - FIRM

FIGURE 4 - ALTA / Topographic Survey

#### APPENDIX:

APPENIDX I - Rainfall Data
APPENIDIX II - Calculations

APPENDIX III - Preliminary Grading Exhibit

APPENDIX IV - Request for Stormwater Retention Waiver-Approved



#### 1. INTRODUCTION

This report represents the storm water analysis for the proposed development consisting a 9-floor hotel/condominium project in downtown Scottsdale. The building will contain 230 hotel rooms, 16 condo units, a 5,017 SF restaurant and 3 subgrade parking garage levels. The purpose of this report is to provide the hydrologic and hydraulic analyses, required by the City of Scottsdale, to support the proposed site plan for said development. This report includes discussions and calculations defining the storm water management concepts for collection, conveyance, and detention systems necessary to comply with the drainage requirements of the City of Scottsdale and Maricopa County. Preparation of this report has been done in accordance with the requirements of the City of Scottsdale Design Standards & Policies Manual (DS&PM) 2018 <sup>1</sup>, and the Drainage Design Manuals for Maricopa County, Arizona, Volumes I<sup>2</sup> and Volume II<sup>3</sup>.

#### 2. LOCATION AND PROJECT DESCRIPTION

#### 2.1 LOCATION:

The project property consists of a parcel of land located on the north-east corner of Scottsdale Road and 3<sup>rd</sup> Avenue. It is further bound by developed commercial property followed by 4<sup>th</sup> Avenue to the north and Winfield Scott Plaza to the east. It is located in a portion of Section 23, Township 2 North, Range 4 East of the Gila and Salt River Base and Meridian, Maricopa County,

- Arizona Parcel ID numbers APN: 173-51-005, 173-51-006, 173-51-007, 173-51-012, 173-51-013, 173-51-014, 173-51-015, 173-51-016, 173-51-017, 173-51-018, 173-51-019, 173-51-020
- Street address is 4221 N Scottsdale Rd., Scottsdale, AZ 85251
- The legal description is:

Lots 5 through 7, lots 12-20 of Winfield Scott Plaza book 66, page 03, Maricopa County Records being a portion of the southwest quarter section 23, township 2 north, range 4 east, of the Gila and Salt River Base and Meridian, Maricopa County, Arizona.

Refer to FIGURE 1 - Vicinity Map for the project's location with respect to major cross streets.

#### 2.2 EXISTING AND PROPOSED DEVELOPMENTS SURROUNDING THE SITE:

Existing site context related to surrounding developments is as follows:

- North: To the north there are 3 lots total consisting of offices and restaurants zoned C-2 DO.
- West: The west side is bound by Scottsdale Road and directly across are offices and restaurants zoned D/DC-1 DO.
- South: The south is bound by 3<sup>rd</sup> Avenue and directly across is a Wells Fargo Bank zoned D/OR-2 PBD DO.
- East: The east is bound by Winfield Scott Plaza and directly across are offices zoned C-2/P-3 DO.

#### 2.3 EXISTING SITE DESCRIPTION:

Land ownership, as defined by ALTA/NSPS Land Title Survey by AW Land Surveying, LLC dated 07/27/17 includes approximately 52,122 sq. ft. (1.196 Ac.) gross or 31,069 sq. ft. (0.71+/- acres) net of commercially developed land. Note that Lots 5-7 and 12-20 are separated by a 16' public alley that is to be abandoned. City of Scottsdale zoning map designates this parcel as C-2.



This site is fully developed as multiple shopping buildings and office buildings. The topography generally slopes from the northwest to the southeast corner at approximately 0.80% with a change in elevation of approximately two and one-half (2.5) feet. The site is almost completely an impervious area with a few desert landscape areas around the existing parking lot. Refer to **FIGURE 2** for an aerial of the overall project existing conditions.

#### 2.4 PROPOSED SITE DEVELOPMENT:

The project is proposed to be re-developed from 12 commercial parcels into one property. This property will have 230 hotel rooms, 16 condo units, and a 5,017 SF restaurant. The 16' public alley between Scottsdale Road and Winfield Scott Plaza is to be incorporated into the project boundaries and included as part of the development. Refer to **FIGURE 5** for proposed site layout.

#### 2.5 FLOOD HAZARD ZONE:

As defined by the Flood Insurance Rate Map (FIRM) for Maricopa County, Arizona, and incorporated areas, Community number 045012, Panel number 2235 of 4425, as shown on Map Number 04013C2235L dated October 16, 2013 this site is designated as **Zone "X.** As such, it is defined as areas outside of the 0.2% annual chance of flooding. Refer to **FIGURE 3** for the FIRM.

#### 3. EXISTING DRAINGE CONDITIONS

#### 3.1 OFF-SITE DRAINAGE:

This site is bound as follows:

- By Winfield Scott Plaza to the east. This road has curb and gutter conveying runoff to the south.
- By developed commercial properties to the north. The alley between the east and west parcels
  carries the runoff from the roof drains and flows to the south, joining with the 3<sup>rd</sup> Avenue flows.
- By Scottsdale Road to the west. Runoff is conveyed in curb and gutter towards the south.
- By 3<sup>rd</sup> Avenue to the south. Runoff is conveyed in curb and gutter towards the east.
- Flows from 4<sup>th</sup> Avenue flow is conveyed in curb and gutter towards the east, around the site.

#### 3.2 ON-SITE DRAINAGE:

This site is fully developed as multiple shopping buildings and office buildings. The topography generally slopes from the northwest to the southeast corner at approximately 0.80% with a change in elevation of approximately two and one-half (2.5) feet. The site is a large impervious area with a few desert landscape areas around the existing parking lot. Runoff from the alleyway flows south into 3<sup>rd</sup> Avenue and east towards Winfield Scott Plaza. Refer to **FIGURE 2** for an aerial of the overall project existing conditions.

Based upon topographic survey information and on-site inspections, there is existing stormwater retention provided on this parcel. The covered parking lot contains a drywell structure with rim elevation 1263.07. This basin will fill up to a pavement grade break elevation of 1263.73 at the southeast end of the parking area and overflow through the drive entrance into 3<sup>rd</sup> Avenue. Using



1263.73 as the high-water elevation, the volume provided by this existing basin is 830 CF. Refer to **Exhibit "A"** in Appendix II.

#### 3.3 EXISTING STORM SEWER SYSTEMS:

There are no apparent storm sewers existing on the parcel. Runoff is conveyed to the southeast by overland flow and along concrete curbs to the south east.

#### 4. PROPOSED STORM WATER MANAGEMENT

#### 4.1 DESIGN INTENT:

The existing drywell will be demolished and the storage volume in the existing retention basin will be eliminated. Roof runoff will be conveyed via downspouts and allowed to splash on grade and flow to historical patterns. The alley will be graded to keep existing storm runoff traveling overland unaffected.

Refer to Section 5 below for a discussion on proposed finished floor elevations. Refer to **Appendix III** for the Preliminary Grading & Drainage Plan.

#### 4.2 DESIGN STORM REQUIREMENTS:

In accordance with City of Scottsdale requirements, stormwater storage for the 100-year 2-hour storm event based on pre-development versus post development C values and, at a minimum, existing storage volumes are required to be maintained.

#### 4.3 CHARACTERISTICS OF BASINS:

The proposed drainage areas are comprised of mixed use buildings and associated parking areas, drives and landscape areas. Based on Figure 4.1-4 of the DS&PM, runoff coefficients for the 100-year storm event used are as follows:

- C=0.30 for grassed areas
- C=0.45 for desert landscaping
- C=0.95 for impervious areas.

HYDROLOGIC ANALYSIS: The hydrologic analysis is determined using the procedures in the City of Scottsdale Design Standards & Policies Manual and the Drainage Design Manual for Maricopa County, Arizona, Volume I. The Rational Method was utilized to compute the on-site peak discharges. The following established the Rational Method equation and the basic input data required:

Q=CwtIA

Where:  $C_{wt} = The runoff coefficient relating runoff to rainfall$ 

I = Average rainfall intensity in inches/hour, lasting for Tc
 Tc = The time of concentration (minutes) – use 5 minutes

A = The contributing drainage area in acres

#### Cwt CALCULATIONS:

Pre-development (Refer to EXHIBIT "A" in Appendix II)



Landscape area (Desert):

4,793 SF @ C=0.45

Impervious areas (Roof / Pavement): 26,276 SF @ C=0.95

Cwt:

 $31,069 \text{ SF } @ C_{wt} = 0.87$ 

Post-development (Refer to EXHIBIT "B" in Appendix II)

Landscape area (Desert):

629 SF @ C=0.45

Impervious Ares (Roof / Pavement): 30,440 SF @ C=0.95

Cwt: 31,069 SF @ Cwt = 0.94

#### **OVERALL RUNOFF RATE COMPARISON:**

Based on a Tc of 5 mins, pre and post development rates for the 100 yr storm event are calculated as follows:

 $Q_{100}$  PRE = 0.87 \* 7.46 in/hr \* 0.71 ac = **4.61 CFS** 

 $Q_{100}$  POST = 0.94 \* 7.46 in/hr \* 0.71 ac = **4.98 CFS** 

#### **DEVELOPED RUNOFF FLOWS to OFF-SITE**

Ultimately, all site runoff will exit the site at the historical outlets and join with runoff from Winfield Scott Plaza and 3<sup>rd</sup> Avenue at the northwest corner of the intersection.

#### 4.4 OFF-SITE FLOW:

The alley flows south through the proposed property. The proposed development will have a pass through that will allow the flows from the north lots to continue to the historical outlet.

#### 4.5 STORMWATER RETENTION:

Stormwater storage is required to be provided based on the difference between Pre vs Post development conditions or as required by site grading and drainage constraints. On-site inspection and review of current topographic survey provided evidence that there is existing on-site retention.

#### **REQUIRED STORAGE (Pre vs Post):**

Stormwater storage required is calculated In accordance with the COS – DS&PM. Required Retention  $Vreq(Acre-Feet) = (P/12)*A*(C_{post} - C_{pre})$ 

Where: P = 100-Yr. 2-Hr. Precipitation in Inches (Ref: Isopluvial from DS&PM, Appendix 4-1D, pg. 11)

A = Area (Acres)

C = Cpost - Cpre

Vreq = (2.15 in /12)\* (0.71 AC)\* (0.94-0.87)

Vreq = 0.0089 AC-ft or 388 cf

Including the existing retention from Section 3.2 above, the total volume required is:

 $V_{total} = 388 \text{ cf} + 830 \text{ cf} = 1,218 \text{ cf}$ 



#### STORMWATER RETENTION WAIVER:

The proposed development includes an underground parking structure beyond the limits of the property thereby eliminating potential open or underground retention areas. Therefore, a Request for Stormwater Storage Waiver has been requested and approved based on Section 4-1.602, item 2 of the DS&PM. Refer to Appendix IV for the waiver form.

- A. From the above calculations, the equivalent area associated with a required storage volume of 1,218 CF can be calculated as follows: A = 1,218 / (2.15 in/12) \* 0.94 = 7,232 sq. ft (0.166 ac).
- B. The increase is runoff can then be calculated, using a  $T_c$  of 5 minutes for the 100-yr storm as: Q = CIA = 0.94 \* 7.46 in/hr \* 0.166 ac = 1.16 cfs.
- C. Overall drainage basin area to the west gutter line along N. Winfield Scott is approximately 0.544 acres. Q = 0.95 \* 7.46 in/hr \* 0.544 ac = 3.86 cfs
- D. The existing vertical curb near the southwest corner of the site slopes southerly at approximately 0.34%. The calculated depth of flow is as follows:
  - Normal depth flowing at 3.86 cfs = 0.23'
  - Normal depth flowing at (3.86 + 1.16) 5.02 cfs = 0.25'
  - The net effect is 0.25 0.23 = 0.02' or 0.24-inch increase.

Refer to Appendix II for FlowMaster calculations. This minor increase in water depth related to the street capacity has a negligible impact as the water surface is only ½ of the curb height capacity.

#### 4.6 ADEQ WATER QUALITY REQUIREMENTS

An NOI will be submitted to ADEQ and an approved NOI Certification from ADEQ with an AZCON number will be provided to the City during Improvement Plans submittal.

#### 5. FLOOD SAFETY FOR DWELLINGS

#### 5.1 FINISHED FLOOR ELEVATIONS

The ultimate outfall for this project is located at the southeast corner of the parcel at an elevation of approximately 1262.93. The lowest conceptual finished floor elevation is 1265. All building finished floor elevations will be set a minimum of 14 inches above ultimate outfalls and a minimum of 12 inches above the 100-year high-water elevation of any adjacent streets and drainage paths. This will ensure that each building will be well above the 100-year water level.

#### 6. CONCLUSIONS

#### 6.1 OVERALL PROJECT:

Off-site storm water does not impact this project



- The finish floor elevations will be designed a minimum of 12 inches above the 100-year water surface in adjacent streets and drainage paths and a minimum of 14 inches above the low top of curb of the lot.
- 3. Required stormwater storage can safely be conveyed offsite. Due to the lack of potential retention areas on site, a Request for Stormwater Retention Waiver is justified.

#### 6.2 PROJECT PHASING:

This development is anticipated to be constructed in a single phase.

#### 7. WARNING AND DISCLAIMER OF LIABILITY

RE: following page.

#### 8. REFERENCES

- 1. Design Standards & Policies Manual, City of Scottsdale -2018
- Drainage Design Manual for Maricopa County, Arizona, Volume I, Hydrology, Flood Control District of Maricopa County, Fourth Edition, August 15, 2013
- Drainage Design Manual for Maricopa County, Arizona, Volume II, Hydraulics, Flood Control District of Maricopa County, August 15, 2013



#### Appendix 4-1C

### WARNING & DISCLAIMER OF LIABILITY

The Drainage and Floodplain Regulations and Ordinances of the City of Scottsdale are intended to "minimize the occurrence of losses, hazards and conditions adversely affecting the public health, safety and general welfare which might result from flooding caused by the surface runoff of rainfall" (Scottsdale Revised Code §37-16).


As defined in S.R.C. §37-17, a flood plain or "Special flood hazard area means an area having flood and/or flood related erosion hazards as shown on a FHBM or FIRM as zone A, AO, A1-30, AE, A99, AH, or E, and those areas identified as such by the floodplain administrator, delineated in accordance with subsection 37-18(b) and adopted by the floodplain board." It is possible that a property could be inundated by greater frequency flood events or by a flood greater in magnitude than a 100-year flood. Additionally, much of the Scottsdale area is a dynamic flood area; that is, the floodplains may shift from one location to another, over time, due to natural processes.

#### WARNING AND DISCLAIMER OF LIABILITY PURSUANT TO S.R.C §37-22

"The degree of flood protection provided by the requirements in this article is considered reasonable for regulatory purposes and is based on scientific and engineering considerations. Floods larger than the base flood can and will occur on rare occasions. Floodwater heights may be increased by manmade or natural causes. This article (Chapter 37, Article II) shall not create liability on the part of the city, any officer or employee thereof, or the federal government for any flood damages that result from reliance on this article or any administrative decision lawfully made thereunder."

Compliance with Drainage and Floodplain Regulations and Ordinances does not insure complete protection from flooding. The Floodplain Regulations and Ordinances meet established local and federal standards for floodplain management, but neither this review nor the Regulations and Ordinances take into account such flood related problems as natural erosion, streambed meander or man-made obstructions and diversions, all of which may have an adverse affect in the event of a flood. You are advised to consult your own engineer or other expert regarding these considerations.

I have read and und and explained this of		m an agent for a	n owner I have made the owner aware of
Plan Check No.	Owner or Agent	Date	



DESERT LSCP =

4,793 SF (0.11 AC)

26,276 SF (0.60 AC)

31,069 SF (0.71 AC)

@ Cwt=0.45

@ Cwt=0.95

@ Cwt=0.87




SEG




AN OIL 170144



# APPENDIX II Calculations




Phoenix 1 Mesa GILA H





Large scale aerial


#### PF graphical

PDS-based depth-duration-frequency (DDF) curves Latitude: 33.4973°, Longitude: -111.9256°









NOAA Atlas 14, Volume 1, Version 5

Created (GMT): Fri Feb 17 20:34:19 2017

Back to Top

Maps & aerials

Small scale terrain



NOAA Atlas 14, Volume 1, Version 5 Location name: Scottsdale, Arizona, USA\* Latitude: 33.4973°, Longitude: -111.9256° Elevation: 1262.91 ft\*\*



\* source: ESRI Maps \*\* source: USGS

#### POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

PF tabular | PF graphical | Maps & aerials

#### PF tabular


PDS	S-based p	oint preci	pitation fr	requency	estimates	with 90%	confiden	ce interva	als (in incl	nes) <sup>1</sup>
Duration				Averaç	ge recurrenc	e interval (y	rears)			
Duradion	1	2	5	10	25	50	100	200	500	1000
5-min	<b>0.184</b> (0.154-0.224)	<b>0.240</b> (0.202-0.293)	<b>0.327</b> (0.273-0.397)	<b>0.393</b> (0.326-0.475)	<b>0.482</b> (0.394-0.580)	<b>0.552</b> (0.445-0.660)	0.622 (0.492-0.742)	<b>0.694</b> (0.540-0.827)	<b>0.790</b> (0.598-0.943)	<b>0.864</b> (0.641-1.03
10-min	0.280 (0.234-0.341)	<b>0.366</b> (0.308-0.446)	<b>0.497</b> (0.415-0.604)	<b>0.598</b> (0.496-0.722)	0.734 (0.599-0.883)	<b>0.839</b> (0.677-1.00)	<b>0.947</b> (0.749-1.13)	1.06 (0.821-1.26)	<b>1.20</b> (0.911-1.44)	1.31 (0.976-1.57
15-min	0.347 (0.290-0.423)	0.453 (0.382-0.553)	0.616 (0.515-0.748)	<b>0.741</b> (0.615-0.895)	<b>0.910</b> (0.743-1.09)	1.04 (0.839-1.25)	1.17 (0.928-1.40)	<b>1.31</b> (1.02-1.56)	<b>1.49</b> (1.13-1.78)	<b>1.63</b> (1.21-1.95)
30-min	0.467 (0.391-0.569)	0.610 (0.514-0.744)	0.829 (0.693-1.01)	0.998 (0.828-1.21)	1.23 (1.00-1.47)	1.40 (1.13-1.68)	1.58 (1.25-1.89)	1.76 (1.37-2.10)	2.01 (1.52-2.40)	<b>2.19</b> (1.63-2.63)
60-min	0.578 (0.484-0.704)	0.755 (0.636-0.921)	1.03 (0.858-1.25)	<b>1.24</b> (1.02-1.49)	1.52 (1.24-1.82)	1.73 (1.40-2.08)	1.96 (1.55-2.33)	2.18 (1.70-2.60)	2.48 (1.88-2.97)	<b>2.72</b> (2.02-3.25)
2-hr	<b>0.670</b> (0.571-0.800)	<b>0.867</b> (0.739-1.04)	<b>1.16</b> (0.984-1.38)	<b>1.38</b> (1.16-1.65)	1.69 (1.40-2.00)	1.92 (1.58-2.27)	<b>2.17</b> (1.75-2.55)	<b>2.41</b> (1.91-2.84)	<b>2.74</b> (2.12-3.23)	3.00 (2.27-3.55)
3-hr	<b>0.730</b> (0.618-0.880)	<b>0.937</b> (0.797-1.13)	<b>1.23</b> (1.04-1.48)	<b>1.46</b> (1.23-1.75)	1.79 (1.48-2.13)	2.05 (1.67-2.43)	<b>2.32</b> (1.86-2.75)	2.60 (2.05-3.08)	2.99 (2.29-3.55)	3.31 (2.46-3.93)
6-hr	0.879 (0.760-1.03)	<b>1.11</b> (0.967-1.31)	<b>1.43</b> (1.23-1.68)	<b>1.68</b> (1.44-1.96)	2.02 (1.71-2.34)	<b>2.29</b> (1.90-2.65)	<b>2.57</b> (2.10-2.97)	2.85 (2.29-3.30)	<b>3.24</b> (2.54-3.76)	3.55 (2.71-4.13)
12-hr	<b>0.982</b> (0.859-1.14)	<b>1.24</b> (1.08-1.44)	<b>1.57</b> (1.37-1.82)	1.83 (1.58-2.12)	2.18 (1.87-2.52)	<b>2.45</b> (2.07-2.82)	2.73 (2.27-3.14)	3.01 (2.47-3.47)	3.39 (2.71-3.92)	3.68 (2.90-4.29
24-hr	1.17 (1.04-1.32)	1.49 (1.32-1.69)	1.93 (1.71-2.18)	<b>2.28</b> (2.02-2.57)	2.76 (2.43-3.11)	3.14 (2.74-3.53)	3.54 (3.07-3.98)	3.95 (3.40-4.45)	<b>4.52</b> (3.85-5.09)	<b>4.97</b> (4.19-5.61)
2-day	1.26 (1.13-1.43)	1.62 (1.44-1.83)	2.12 (1.89-2.40)	<b>2.53</b> (2.24-2.85)	3.09 (2.73-3.48)	3.54 (3.10-3.99)	<b>4.02</b> (3.50-4.53)	<b>4.51</b> (3.90-5.09)	<b>5.20</b> (4.44-5.88)	<b>5.76</b> (4.87-6.53)
3-day	<b>1.34</b> (1.19-1.51)	1.71 (1.52-1.94)	<b>2.25</b> (2.00-2.54)	<b>2.69</b> (2.38-3.03)	3.30 (2.90-3.72)	3.79 (3.32-4.27)	<b>4.32</b> (3.75-4.86)	<b>4.87</b> (4.19-5.48)	<b>5.64</b> (4.80-6.36)	<b>6.27</b> (5.28-7.08)
4-day	<b>1.41</b> (1.25-1.60)	1.81 (1.60-2.04)	<b>2.38</b> (2.11-2.69)	2.85 (2.52-3.21)	3.51 (3.08-3.95)	<b>4.05</b> (3.53-4.55)	<b>4.62</b> (4.00-5.19)	<b>5.22</b> (4.48-5.88)	<b>6.08</b> (5.15-6.84)	<b>6.78</b> (5.68-7.64)
7-day	<b>1.57</b> (1.39-1.78)	<b>2.00</b> (1.78-2.27)	2.65 (2.35-2.99)	3.17 (2.80-3.58)	3.91 (3.43-4.40)	<b>4.50</b> (3.93-5.06)	<b>5.13</b> (4.44-5.78)	5.80 (4.98-6.54)	<b>6.75</b> (5.72-7.61)	<b>7.51</b> (6.30-8.49)
10-day	1.70 (1.51-1.93)	<b>2.18</b> (1.94-2.46)	2.88 (2.55-3.24)	<b>3.44</b> (3.04-3.87)	<b>4.23</b> (3.71-4.74)	<b>4.86</b> (4.24-5.44)	<b>5.53</b> (4.80-6.20)	<b>6.24</b> (5.37-7.00)	<b>7.22</b> (6.14-8.11)	<b>8.02</b> (6.75-9.02)
20-day	2.10 (1.87-2.35)	2.69 (2.40-3.02)	3.56 (3.17-3.98)	<b>4.21</b> (3.74-4.71)	<b>5.09</b> (4.50-5.69)	<b>5.77</b> (5.08-6.45)	<b>6.46</b> (5.66-7.23)	<b>7.16</b> (6.24-8.02)	<b>8.10</b> (7.00-9.10)	8.83 (7.57-9.92
30-day	<b>2.45</b> (2.17-2.75)	3.15 (2.80-3.53)	<b>4.15</b> (3.69-4.65)	<b>4.91</b> (4.35-5.49)	<b>5.93</b> (5.23-6.63)	<b>6.72</b> (5.90-7.50)	<b>7.53</b> (6.58-8.39)	<b>8.35</b> (7.25-9.31)	<b>9.45</b> (8.15-10.6)	<b>10.3</b> (8.82-11.5
45-day	2.83 (2.53-3.17)	3.65 (3.26-4.09)	<b>4.81</b> (4.29-5.38)	<b>5.67</b> (5.04-6.34)	<b>6.80</b> (6.03-7.60)	<b>7.65</b> (6.76-8.55)	<b>8.51</b> (7.49-9.52)	9.37 (8.21-10.5)	<b>10.5</b> (9.14-11.8)	<b>11.4</b> (9.82-12.8
60-day	3.13 (2.81-3,50)	<b>4.05</b> (3.62-4.51)	<b>5.32</b> (4.76-5.93)	<b>6.25</b> (5.58-6.97)	<b>7.46</b> (6.64-8.31)	<b>8.35</b> (7.41-9.31)	<b>9.25</b> (8.17-10.3)	<b>10.1</b> (8.91-11.3)	<b>11.3</b> (9.87-12.6)	<b>12.1</b> (10.6-13.6


<sup>&</sup>lt;sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).


Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top










Large scale aerial


#### PF graphical

PDS-based intensity-duration-frequency (IDF) curves Latitude: 33.4973°, Longitude: -111.9256°









NOAA Atlas 14, Volume 1, Version 5

Created (GMT): Fri Feb 17 20:35:07 2017

Back to Top

Maps & aerials

Small scale terrain



#### NOAA Atlas 14, Volume 1, Version 5 Location name: Scottsdale, Arizona, USA\* Latitude: 33.4973°, Longitude: -111.9256° Elevation: 1262.91 ft\*\*



\* source: ESRI Maps \*\* source: USGS

#### POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

PF tabular | PF graphical | Maps & aerials

#### PF tabular

PDS-k	DS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour) <sup>1</sup>									
Duration				Avera	ge recurren	ce interval (	years)			
Duration	1	2	5	10	25	50	100	200	500	1000
5-min	<b>2.21</b> (1.85-2.69)	2.88 (2.42-3.52)	3.92 (3.28-4.76)	<b>4.72</b> (3.91-5.70)	<b>5.78</b> (4.73-6.96)	<b>6.62</b> (5.34-7.92)	<b>7.46</b> (5.90-8.90)	<b>8.33</b> (6.48-9.92)	<b>9.48</b> (7.18-11.3)	<b>10.4</b> (7.69-12.4)
10-min	1.68 (1.40-2.05)	2.20 (1.85-2.68)	2.98 (2.49-3.62)	3.59 (2.98-4.33)	<b>4.40</b> (3.59-5.30)	<b>5.03</b> (4.06-6.02)	<b>5.68</b> (4.49-6.78)	<b>6.34</b> (4.93-7.55)	<b>7.22</b> (5.47-8.62)	<b>7.89</b> (5.86-9.43)
15-min	<b>1.39</b> (1.16-1.69)	1.81 (1.53-2.21)	2.46 (2.06-2.99)	2.96 (2.46-3.58)	3.64 (2.97-4.38)	<b>4.16</b> (3.36-4.98)	<b>4.70</b> (3.71-5.60)	<b>5.24</b> (4.07-6.24)	<b>5.96</b> (4.52-7.12)	<b>6.52</b> (4.84-7.80)
30-min	0.934 (0.782-1.14)	<b>1.22</b> (1.03-1.49)	1.66 (1.39-2.01)	2.00 (1.66-2.41)	<b>2.45</b> (2.00-2.95)	2.80 (2.26-3.35)	3.16 (2.50-3.77)	3.53 (2.74-4.20)	<b>4.02</b> (3.04-4.79)	<b>4.39</b> (3.26-5.25)
60-min	<b>0.578</b> (0.484-0.704)	<b>0.755</b> (0.636-0.921)	1.03 (0.858-1.25)	<b>1.24</b> (1.02-1.49)	<b>1.52</b> (1.24-1.82)	1.73 (1.40-2.08)	1.96 (1.55-2.33)	<b>2.18</b> (1.70-2.60)	2.48 (1.88-2.97)	<b>2.72</b> (2.02-3.25)
2-hr	<b>0.335</b> (0.286-0.400)	0.434 (0.370-0.520)	<b>0.580</b> (0.492-0.691)	0.692 (0.580-0.823)	<b>0.845</b> (0.701-0.998)	<b>0.962</b> (0.788-1.13)	1.08 (0.874-1.28)	<b>1.21</b> (0.954-1.42)	<b>1.37</b> (1.06-1.61)	1.50 (1.13-1.78)
3-hr	0.243 (0.206-0.293)	<b>0.312</b> (0.265-0.377)	<b>0.410</b> (0.347-0.494)	<b>0.487</b> (0.409-0.584)	<b>0.596</b> (0.492-0.709)	<b>0.682</b> (0.556-0.810)	<b>0.773</b> (0.618-0.917)	<b>0.867</b> (0.682-1.03)	<b>0.997</b> (0.761-1.18)	<b>1.10</b> (0.821-1.31)
6-hr	<b>0.147</b> (0.127-0.173)	<b>0.186</b> (0.161-0.219)	<b>0.238</b> (0.206-0.280)	0.280 (0.240-0.327)	<b>0.337</b> (0.285-0.391)	<b>0.382</b> (0.318-0.442)	<b>0.429</b> (0.351-0.496)	0.476 (0.382-0.552)	0.541 (0.424-0.628)	<b>0.593</b> (0.453-0.690
12-hr	0.082 (0.071-0.095)	0.103 (0.090-0.120)	<b>0.130</b> (0.113-0.151)	<b>0.152</b> (0.131-0.176)	<b>0.181</b> (0.155-0.209)	<b>0.204</b> (0.172-0.234)	<b>0.227</b> (0.189-0.261)	<b>0.250</b> (0.205-0.288)	0.281 (0.225-0.326)	0.306 (0.240-0.356
24-hr	0.049 (0.043-0.055)	0.062 (0.055-0.070)	0.080 (0.071-0.091)	0.095 (0.084-0.107)	<b>0.115</b> (0.101-0.130)	<b>0.131</b> (0.114-0.147)	<b>0.148</b> (0.128-0.166)	<b>0.165</b> (0.142-0.185)	0.188 (0.160-0.212)	<b>0.207</b> (0.175-0.234
2-day	0.026 (0.023-0.030)	0.034 (0.030-0.038)	0.044 (0.039-0.050)	0.053 (0.047-0.059)	0.064 (0.057-0.073)	0.074 (0.065-0.083)	0.084 (0.073-0.094)	0.094 (0.081-0.106)	0.108 (0.093-0.123)	<b>0.120</b> (0.101-0.136
3-day	0.019 (0.017-0.021)	0.024 (0.021-0.027)	0.031 (0.028-0.035)	0.037 (0.033-0.042)	0.046 (0.040-0.052)	0.053 (0.046-0.059)	0.060 (0.052-0.067)	0.068 (0.058-0.076)	0.078 (0.067-0.088)	0.087 (0.073-0.098
4-day	0.015 (0.013-0.017)	0.019 (0.017-0.021)	0.025 (0.022-0.028)	0.030 (0.026-0.033)	0.037 (0.032-0.041)	0.042 (0.037-0.047)	0.048 (0.042-0.054)	0.054 (0.047-0.061)	0.063 (0.054-0.071)	0.071 (0.059-0.080
7-day	0.009 (0.008-0.011)	0.012 (0.011-0.014)	<b>0.016</b> (0.014-0.018)	0.019 (0.017-0.021)	0.023 (0.020-0.026)	0.027 (0.023-0.030)	0.031 (0.026-0.034)	0.035 (0.030-0.039)	0.040 (0.034-0.045)	0.045 (0.038-0.051
10-day	0.007 (0.006-0.008)	0.009 (0.008-0.010)	<b>0.012</b> (0.011-0.014)	0.014 (0.013-0.016)	0.018 (0.015-0.020)	0.020 (0.018-0.023)	0.023 (0.020-0.026)	0.026 (0.022-0.029)	0.030 (0.026-0.034)	0.033 (0.028-0.038
20-day	0.004 (0.004-0.005)	0.006 (0.005-0.006)	0.007 (0.007-0.008)	0.009 (0.008-0.010)	<b>0.011</b> (0.009-0.012)	<b>0.012</b> (0.011-0.013)	<b>0.013</b> (0.012-0.015)	<b>0.015</b> (0.013-0.017)	<b>0.017</b> (0.015-0.019)	<b>0.018</b> (0.016-0.021
30-day	0.003 (0.003-0.004)	0.004 (0.004-0.005)	0.006 (0.005-0.006)	0.007 (0.006-0.008)	0.008 (0.007-0.009)	0.009 (0.008-0.010)	0.010 (0.009-0.012)	0.012 (0.010-0.013)	0.013 (0.011-0.015)	0.014 (0.012-0.016
45-day	0.003 (0.002-0.003)	0.003 (0.003-0.004)	0.004 (0.004-0.005)	0.005 (0.005-0.006)	0.006 (0.006-0.007)	0.007 (0.006-0.008)	0.008 (0.007-0.009)	0.009 (0.008-0.010)	0.010 (0.008-0.011)	0.011 (0.009-0.012
60-day	0.002 (0.002-0.002)	0.003 (0.003-0.003)	0.004 (0.003-0.004)	0.004 (0.004-0.005)	0.005 (0.005-0.006)	0.006 (0.005-0.006)	0.006 (0.006-0.007)	0.007 (0.006-0.008)	0.008 (0.007-0.009)	0.008 (0.007-0.009

<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).


Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top



# Appendix 4-1D ISOPLUVIALS






# APPENDIX I Rainfall Data







### ALTA/NSPS LAND TITLE SURVEY

LOTS 5 THROUGH 7. LOTS 12 THROUGH 20 WINFIELD SCOTT PLAZA BOOK 66, PAGE 03, MARICOPA COUNTY RECORDS

BEING A PORTION OF THE SOUTHWEST QUARTER OF SECTION 23, TOWNSHIP 2 NORTH, RANGE 4 EAST, OF THE GILA AND SALT RIVER BASE AND MERIDIAN. MARICOPA COUNTY, ARIZONA.

#### SCHEDULE "B" ITEMS

- 1) Property taxes, which are a lien not yet due and payable, including any assessments collected with taxes to be levied for the year 2017.
- INTENTIONALLY OMITTED
- Any outstanding flabilities and obligations, including unpaid assessments, imposed upon said Land by reason of: (a) inclusion thereof within the boundaries of the Salt River Project Agricultural Improvement and Power District; (b) membership of the owner thereof in the Salt River Valley Water Users' Association, an Arizona corporation and (c) the terms of any Water Right Application made under the reclamation laws of the United States for the purposes of obtaining water rights for said
- Easements, covenants, conditions and restrictions as set forth on the plat recorded in Book 66 of
- Easement(s) for the purpose(s) shown below and rights incidental thereto as set forth in a document: Purpose: Road or Highway and Public utility lines Recording No: Docket 13358, page 864 (as to Lots 14 through 20, inclusive
- Easement(s) for the purpose(s) shown below and rights incidental thereto as set forth in a document: Purpose: Communication facilities Recording No: 88-022256
- Reservations contained in the Patent

From: The United States of America Recording Date: February 07, 1891 Recording No: Book 25 of Deeds, page 588

Which among other things recites as follows

Subject to any vested and accrued water rights for mining, agricultural, manufacturing, or other purposes and rights to ditches and reservoirs used in connection with such water rights, as may be recognized and acknowledged by local customs, laws and decisions of the courts; and also subject to the right of the proprietor of a vein or lode to extract and remove his one therefrom should the same be found to penetrate or intersect the premises hereby granted, as provided by law.

- Water rights, claims or title to water, whether or not disclosed by the public records.
- Any rights of the parties in possession of a portion of, or all of, said Land, which rights are not osed by the public records.
- Matters which may be disclosed by an inspection and/or by a correct ALTA/ACSM Land Title Survey of said Land that is satisfactory to the Company, and/or by inquiry of the parties in possession thereof.
- PLOTTABLE SCHEDULE "B" ITEM, SHOWN ON THIS SURVEY (PAGE 2)
- O SCHEDULE "B" ITEM CANNOT BE PLOTTED BUT DO AFFECT SUBJECT PROPERTIES.

#### NOTES: (Table "A" Items")

- SET A 1/2" REBAR W/CAP "AWLS 45377" AT PROPERTY CORNERS AS SHOWN HEREON UNLESS OTHERWISE
- LOTS 5 & 6: 4221 N SCOTTSDALE ROAD, SCOTTSDALE, ARIZONA LOT 7: 4223 N SCOTTSDALE ROAD, SCOTTSDALE, ARIZONA LOTS 12-13: 4234 N WINFIELD SCOTT PLAZA, SCOTTSDALE, ARIZONA LOTS 14-20: 4216 N WINFIELD SCOTT PLAZA, SCOTTSDALE, ARIZONA PER MARICOPA COUNTY ASSESSOR WEBSITE.
- THIS SURVEY REFLECTS ABOVE GROUND INDICATIONS OF UTILITIES. THE SURVEYOR DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED, ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCUMATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES. ADDITIONALLY, AS PER THE 2016 ALTANSPS STANDARDS: WITH REGARD TO TABLE A, ITEM 11, SOURCE INFORMATION FROM PLANS AND MARKINGS WILL BE COMBINED WITH OBSERVED EVIDENCE OF UTILITIES TO DEVELOP A VIEW OF THOSE UNDERGROUND UTILITIES. HOWEVER, LACKING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY. COMPLETELY AND RELIABLY DEPICTED, WHERE ADDITIONAL OR MORE DETAILED INFORMATION IS REQUIRED, THE CLIENT IS ADVISED THAT EXCAVATION MAY BE NECESSARY.
- 4. ADJOINER INFORMATION IS PER MARICOPA COUNTY ASSESSOR WEBSITE.
- THE BUILDING LINES AND DIMENSIONS SHOWN HEREON DEPICT THE EXTERIOR BUILDING FOOTPRINT AT GROUND LEVEL BASED ON FIELD MEASUREMENTS, THIS MAY OR MAY NOT BE THE EXACT DIMENSIONS OF THE BUILDING FOUNDATION. THE BUILDING AREA IN SQUARE FEET IS CALCULATED FROM THESE MEASUREMENTS AND IS NOT INTENDED TO REPRESENT INTERIOR LEASEABLE AREA.
- 6. SUBJECT PROPERTIES ARE ZONED C-2 DO (CENTRAL BUSINESS WITH DOWNTOWN OVERLAY) PER CITY



#### GENERAL NOTES

- 1. ALL TITLE INFORMATION IS BASED ON A COMMITMENT FOR TITLE INSURANCE PREPARED BY LAWYERS TITLE OF ARIZONA, INC., REPRESENTING COMMONWEALTH LAND TITLE INSURANCE COMPANY, ORDER NO. 01864517-003-R64, WITH AN EFFECTIVE DATE OF JUNE 22, 2017 AND AN AMENDMENT DATE OF JUNE 27, 2017.
- 2. A.R.S. 32-151 STATES THAT THE USE OF THE WORD "CERTIFY" OR "CERTIFICATION" BY A PERSON OR FIRM THAT IS REGISTERED OR CERTIFIED BY THE BOARD IS AN EXPRESSION OF PROFESSIONAL OPINION REGARDING THE FACTS OR FINDINGS THAT ARE SUBJECT TO THE CERTIFICATION AND DOES NOT CONSTITUTE A WARRANTY OR GUARANTEE
- 3. SURVEY FIELD WORK WAS COMPLETED ON FEBRUARY 7, 2017.
- 4. THIS SURVEYOR HAS MADE NO INVESTIGATION OR INDEPENDENT SEARCH FOR EASEMENTS OF RECORD, ENCUMBRANCES, RESTRICTIVE COVENANTS, OWNERSHIP TITLE EVIDENCE OR ANY OTHER FACTS THAT AN ACCURATE AND CURRENT TITLE

#### BASIS OF BEARING

THE BASIS OF BEARING AND ALL MONUMENTATION SHOWN HEREON IS BASED ON THE WEST LINE OF THE SOUTHWEST QUARTER OF SECTION 23, USING A BEARING OF NORTH 00'00'00' EAST AS SHOWN ON THE FINAL PLAT OF WINFIELD SCOTT PLAZA, RECORDED IN BOOK 68, PAGE 3, MCR.

#### BENCHMARK

BENCHMARK IS A MARICOPA CITY OF SCOTTSDALE BRASS CAP IN HANDHOLE LOCATED AT THE INTERSECTION OF SCOTTSDALE ROAD AND INDIAN SCHOOL ROAD.

ELEVATION = 1260.37' NAVD 88

#### CERTIFICATION

4221 - Associates, AZ, LLC, an Arizona limited liability company, as to Parcel 1 and Heldi H. Ream, a widow as to an undivided 50% interest and R. Gregory Hougham and Ann Hougham, husband and wife as to an undivided 50% interest as joint tenants with right of

Central State Bank

LAWYERS TITLE OF ARIZONA, INC. REPRESENTING COMMONWEALTH LAND TITLE INSURANCE COMPANY

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2016 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTANNSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 6(a), 6(b), 7(a), 7(b)(1), 8, 9, 11, AND 13 OF TABLE A THEREOF. THE FIELDWORK WAS COMPLETED ON FEBUARY 08, 2017.

FIGURE 4

© AL ROSES RESERVED



ALTA/NSPS LAND TITLE SURVEY SECTION 23 TOWNSHIP 2 NORTH RANGE 4 FAST OF THE G.S.R.B. & M. MARICOPA COUNTY, ARIZONA



DRAWN BY: CHECKED BY: DATE: 07/27/17 JOB NO.: 17-014 SHEET NO. 1 OF 2



AT THE TIME OF THIS SURVEY, SUBJECT PROPERTY IS LOCATED WITHIN ZONE "X" (DOTTED) AS SHOWN ON FEMA FLOOD INSURANCE RATE MAP NO. 04013C2235L, DATED OCTOBER 16, 2013. ZONE "X" IS DEFINED AS AREAS OF 0.2% ANNUAL FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DATANIAGE AREAS LESS THAN 1 SQUARE MILE, AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

FLOOD INSURANCE RATE MAP (FIRM) INFORMATION

GROSS AREA TO INCLUDE 1/2 STREET RIGHTS-OF-WAY:

NET AREA; 31,068.8 SQ. FT. OR 0,712 ACRES MORE OR LESS.

52,122.1 SQ. FT. OR 1.196 ACRES MORE OR LESS.

PARKING SPACES

2 HANDICAP PARKING SPACES (COVERED)

PARCEL DESCRIPTION

Beginning:

Lots 5 through 7, inclusive and Lots 14 through 20, inclusive, WINFIELD SCOTT PLAZA, according to Book 66

Together with a portion of that certain 16 foot alley as shown on the final plat of WINFIELD SCOTT PLAZA,

Commencing at the west quarter corner of said Section 23, a Maricopa County Brass Cap in Handhole, from

which the southwest corner of said Section 23, a City of Scottsdale Brass Cap in Handhole, bears South 00 degrees 00 minutes East (Basis of Bearing) a distance of 2656.21 feet;

Thence along the west line of the Southwest guarter of said Section 23, South 00 degrees 00 minutes 00 nds East a distance of 1572 17 feet to the centerline of 4th avenue a City of Scottsdale brass cap flush:

Thence leaving said west line along the center line South 89 degrees 42 minutes 48 seconds East a distance of

Thence leaving said center line South 00 degrees 00 minutes 01 seconds West a distance of 40.00 feet to the northeast corner of Lot 10 as shown of said final plat;

Thence along the easterly lines of Lots 8, 9 and 10 of said final plat, South 00 degrees 00 minutes 01 seconds

Thence leaving said northeast corner of Lot 7, South 89 degrees 44 minutes 57 seconds East a distance of 16.00 feet to the northwest corner of Lot 14 as shown on said final plat;

ds West a distance of 90.04 feet, to the southwest corner of Lot 16

of 16.00 feet to the southeast corner of Lot 5 as shown on said final plat:

AREA TABLE

LOT Sq. Ft. Acres

Thence along the westerly lines of Lots 14, 15 and 16 a shown on said final plat, South 00 degrees 00 minutes


Thence leaving said southwest corner of said Lot 19, North 89 degrees 46 minutes 48 seconds West a distance

Thence along the easterly lines of Lots 5, 6, and 7, North 00 degrees 00 minutes 01 seconds East a distance of 90.05 feet to the Point of Beginning

Lots 12 and 13, WINFIELD SCOTT PLAZA, according to Book 66 of Maps, page 3, records of Maricopa County,

quarter of Section 23, Township 2 North, Range 4 East of the Gila and Salt River Base and Meridian, Maricopa County, Arizona, more particularly described as follows:

according to Book 66 of Maps, page 3, records of Maricopa County, Arizona, Iving within the Southw



#### Worksheet for Irregular Section - Winfield Scott @ q=3.86 cfs

#### **Project Description**

Friction Method Manning Formula Solve For Normal Depth

#### Input Data

 Channel Slope
 0.00380
 ft/ft

 Discharge
 5.02
 ft³/s

Section Definitions

Station (ft)	Elevation (ft)
0+00	63.22
-0+31	62.88
-0+31	63.88

Roughness Segment Definitions

Start Station	Ending Station	Roughness Coefficien
---------------	----------------	----------------------

(0+00, 63.22)

(-0+31, 63.88)

0.013

#### Options

Current Roughness Weighted Pavlovskii's Method Open Channel Weighting Method Pavlovskii's Method Closed Channel Weighting Method Pavlovskii's Method

Results	TO SHE WELL THE STATE OF THE ST	1100	
Normal Depth		0.25	ft
Elevation Range	62.88 to 63.88 ft		
Flow Area		2.86	ft²
Wetted Perimeter		23.11	ft
Hydraulic Radius		0.12	ft
Top Width		22.86	ft
Normal Depth		0.25	ft
Critical Depth		0.24	ft
Critical Slope		0.00508	ft/ft
Velocity		1.75	ft/s

Bentley Systems, Inc. Haestad Methods SoBdittle & Fider Master V8i (SELECT series 1) [08.11.01.03]

10/4/2017 5:47:55 PM

27 Siemons Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Page 1 of 2

Worksheet	for Irregular Sec	ction - Wint	field Scott @ q=3.86 cfs
Results			
Velocity Head		0.05	ft
Specific Energy		0.30	ft
Froude Number		0.87	
Flow Type	Subcritical		
GVF Input Data			
Downstream Depth		0.00	ft
Length		0.00	ft
Number Of Steps		0	
GVF Output Data			ELLEN STATE
Upstream Depth		0.00	ft
Profile Description			
Profile Headloss		0.00	ft
Downstream Velocity		Infinity	ft/s
Upstream Velocity		Infinity	ft/s
Normal Depth		0.25	ft
Critical Depth		0.24	ft
Channel Slope		0.00380	ft/ft

0.00508 ft/ft

Critical Slope

#### Cross Section for Irregular Section - Winfield Scott 3.86 cfs

#### **Project Description**

Friction Method

Manning Formula

Solve For

Normal Depth

#### Input Data

Channel Slope

0.00380 ft/ft


Normal Depth

0.23 ft

Discharge

3.86 ft<sup>3</sup>/s

#### Cross Section Image



#### Worksheet for Irregular Section - Winfield Scott @ q= 5.02 cfs

#### **Project Description**

Friction Method

Manning Formula

Solve For

Normal Depth

#### Input Data

Channel Slope

0.00380 ft/ft

Discharge

5.02 ft<sup>3</sup>/s

Section Definitions

Station (ft)	Elevation (ft)
0+00	63.22
-0+31	62.88
-0+31	63.88

Roughness Segment Definitions

Start Station	Ending Station	Roughness Coefficient

(0+00, 63.22)

(-0+31, 63.88)

0.013

#### **Options**

Current Roughness Weighted Method

Pavlovskii's Method

Open Channel Weighting Method

Pavlovskii's Method

Closed Channel Weighting Method

Pavlovskii's Method

Results				
Normal Depth		0.25	ft	
Elevation Range	62.88 to 63.88 ft			
Flow Area		2.86	ft²	
Wetted Perimeter		23.11	ft	
Hydraulic Radius		0.12	ft	
Top Width		22.86	ft	
Normal Depth		0.25	ft	
Critical Depth		0.24	ft	
Critical Slope		0.00508	ft/ft	
Velocity		1.75	ft/s	

Bentley Systems, Inc. Haestad Methods Solletidie C Finder Master V8i (SELECT series 1) [08.11.01.03]

10/4/2017 5:44:59 PM

27 Siemons Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Page 1 of 2

Worksheet	for Irregular Sec	ction - Winf	ield Scott @ q	= 5.02 cfs
Results				TENER DE L'AND
Velocity Head		0.05	ft	
Specific Energy		0.30	ft	
Froude Number		0.87		
Flow Type	Subcritical			
GVF Input Data				EPASSION OF
Downstream Depth		0.00	ft	
Length		0.00	ft	
Number Of Steps		0		
GVF Output Data		72 7 7 7 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		MERCHINE.
Upstream Depth		0.00	ft	
Profile Description				
Profile Headloss		0.00	ft	
Downstream Velocity		Infinity	ft/s	
Upstream Velocity		Infinity	ft/s	
Normal Depth		0.25	ft	
Critical Depth		0.24	ft	
Channel Slope		0.00380	ft/ft	

0.00508 ft/ft

Critical Slope

#### **Cross Section for Irregular Section - 1**

#### **Project Description**

Friction Method

Manning Formula

Solve For

Normal Depth

#### Input Data

Channel Slope

0.00380 ft/ft


Normal Depth

0.25 ft

Discharge

5.02 ft<sup>3</sup>/s

#### Cross Section Image





# APPENDIX III Grading Plans



### APPENDIX IV

Request for Stormwater Storage Waiver



## **Request for Stormwater Storage Waiver**

City of Scottsdale Case Numbers	:					
PA 7 - ZN - 2017 UP DR	PP PC#					
The applicant/developer must complete and submit this form to the city for processing and obtain approval of waiver request <b>before submitting improvement plans</b> . Denial of the waiver may require the developer to submit a revised site plan to the Development Review Board.						
Date 10/04/2017 Project Name Winfield Hotel and Residences						
Project Location NEC Scottsdale Road and 3rd Avenue						
The production of the control of the	SEG					
Phone 480.588.7226 Fax E-mail steve@	gazseg.com					
Address 8280 E. Gelding Dr., Suite 101, Scottsdale, AZ 85260	·					
Waiver Criteria  A project must meet at least one of three criteria listed below for the city to consider waiving some or all required stormwater storage. However, regardless of the criteria, a waiver will only be granted if the applicant can demonstrate that the effect of a waiver will not Increase the potential for flooding on any property. Check the applicable box and provide a signed engineering report and supporting engineering analysis that demonstrate the project meets the criteria and that the effect of a waiver will not increase the potential for flooding on any property.  If the runoff for the project has been included in a storage facility at another location, the applicant must demonstrate that the stormwater storage facility was specifically designed to accommodate runoff from the subject property and that the runoff will be conveyed to this location through an adequately designed conveyance facility.						
<ol> <li>The development is adjacent to a conveyance facility that an engineering analysis shows is designed and constructed to handle the additional runoff from the site as a result of development.</li> </ol>						
2. The development is on a parcel less than one-half acre in size.						
3. Stormwater storage requirements conflict with requirements of the Environmentally Sensitive Lands Ordinance (ESLO).						
For a full storage waiver, a conflict with ESLO is limited to:						
<ul> <li>Property located in the hillside landform as defined in the city Zoning Ore</li> <li>Property in the upper desert landform that has a land slope steeper than</li> <li>Property within the ESL zoning overlay district where the only viable located requires blasting</li> </ul>	5% as defined in the city Zoning Ordinance					
This full waiver only applies to those portions of property meeting one of these three requirements.						
This full waiver only applies to those portions of property meeting one of these three requirements.  Partial waivers are available for projects or portions of properties within the Environmentally Sensitive Lands Zoning Overlay District, not meeting any of the three full waiver criteria above, if post-development peak discharge rates do not exceed pre-development conditions, based on the 10- and 100-year storm events.						
By signing below, I certify that the stated project meets the waiver criteria selected ab documentation.	ove as demonstrated by the attached					
Steven R. Counsell	October 4, 2017					
Engineer	Date					

Planning, Neighborhood & Transportation Division

7447 E Indian School Road, Suite 105, Scottsdale, AZ 85251 + Phone; 480-312-2500 + Fax: 480-312-7781



# **Request for Stormwater Storage Waiver**

City of Scottsdale Case Numbers:	
PA7 - ZN - 2017UPDRPP PC#	_
CITY STAFF TO COMPLETE THIS PAGE  Project Name Winfield Hotel and Residences	
Project Name	
Check Appropriate Boxes:	
Meets waiver criteria (specify): ☑ 1 □ 2 □ 3	
Recommend <u>approve</u> waiver.	
Recommend deny waiver:  None of waiver criteria met.	
□ Downstream conditions prohibit waiver of any storage.	
□ Other:	
Explain:	
Return waiver request:  Insufficient data provided.  Other:  Explain:	
Recommended Conditions of Waiver:  All storage requirements waived.  Post-development peak discharge rates do not exceed pre-development conditions.  Other:  Explain:	
Waiver approved per above conditions.	
Waiver denied.	
C. Ashley Couch 10/25/17	
Floodplain Administrator or Designee Date	

Planning, Neighborhood & Transportation Division

7447 E Indian School Road, Suite 105, Scottsdale, AZ 85251 • Phone: 480-312-2500 • Fax: 480-312-7781



# **Request for Stormwater Storage Waiver**

- PA -	7	- ZN - 2017	City of Scottsdal	e Case Numbers:	- PP -	PC#
FA		ZN	0			
		In	-Lieu Fee and In-P	(ind Contributions	S	
levels, base and contribu including co maintenanc storage bas	d on the 1 ite an in-li sts such a e over a 7 in designe	0- and 100-year eu fee based on as land acquisitio 5-year design life ed to mitigate the	ects where post-deversity and extended to the storm events. If the what it would cost the construction, land e. The fee for this construction increase in runoff as eu fee calculations see	city grants a waiver, e city to provide a ste scaping, design, con- est is \$1.87 per cubic ssociated with the 10	the developer is re orage basin, sized struction managen foot of stormwater 0-year/2-hour storm	equired to calculate as described below nent, and storage for a virtua m event. The
serve as pa	nt of or ins public bea	tead of the calcunefit. In-lieu fees	rs in-kind contribution ulated in-lieu fee. In-l s and in-kind contribu	kind contributions mu	ist be stormwater i	elated and must
Project Nam	Winfield	d Hotel and Reside	ences			
The waived	stormwat	er storage volum	e is calculated using	a simplified approac	h as follows:	
$\Delta C = increa$ R = 100-yea	se in weig r/2-hour p	ghted average ru	ed, in cubic feet, noff coefficient over h, in feet (DSPM, Ap e feet			
Furthermore	<b>)</b> ,					
$V_w = V - V_p$ ; $V_w = \text{volume}$ V = volume $V_p = \text{volume}$	waived, required,		$A = V = \frac{1,21}{V_p}$ $V_w = \frac{0}{1,21}$		- - -	
			on the following calcu yer cubic foot = \$2.2		ng documentation:	
☐ An in-ki	nd contrib	ution will be mad	le, as follows:			
				•		
☐ No in-lie	eu fee is re	equired. Reason	1:			
Approved b	y:					
C	. AS	lay Gov	-l		10/20	5/17
Floodplain Ad	ministrato	r or Designee			Date	

Planning, Neighborhood & Transportation Division

7447 E Indian School Road, Suite 105, Scottsdale, AZ 85251 + Phone: 480-312-2500 + Fax: 480-312-7781