



Archaeological Resources
Airport Vicinity Development Checklist
Parking Study
Trip Generation Comparison
Parking Master Plan



SCOTTSDALE AIRPORT VICINITY DEVELOPMENT LONG FORM

For development projects with taxilane access and/or parcels adjacent to airport property

The owner of developments within the Airport Influence Area shall complete forms required by the City and Scottsdale Airport to comply with the Scottsdale Revised Code, Chapter 5 – Aviation and the Airpark Rules and Regulations; and submit the completed forms with final plans to the assigned city project manager.

Project Name:	Pre-App:
Site Address:	
Contact name:	Phone:

1. HEIGHT ANALYSIS, CH. 5, SEC. 5-354. GENERAL REQUIREMENTS

- Applicants must conduct a height analysis for all projects located within 20,000 feet of Scottsdale Airport.
1. Complete a height analysis for all structures, appurtenances or construction equipment through the FAA at: <https://oeaaa.faa.gov/oeaaa/external/portal.jsp>, click on the Notice Criteria Tool (left side). If you do not exceed criteria, submit this FAA response from the website with your packet or you must complete step 2.

IF required by FAA, complete Step 2

2. Submit an FAA form 7460-1 Notice of Proposed Construction or Alteration for review and determination. Please allow about 45 days for this process. A copy of the FAA's response will be required prior to final plan approval.

2. TAXILANE ACCESS REVIEW, AIRPARK RULES AND REGULATIONS

- Submit a full-size site plan** at a 1"= 20' scale and elevation plan for aviation staff review. The plans must depict the following: **Taxilane centerline, proposed based aircraft (if known), hangar space dimensions, staging area dimensions, vehicle access path and gate.**
- A staging area shall be greater than or equal to the size of the largest hangar on the site per *Definitions section*.
 - Also proposed parcel site must include enough hangar space for each proposed aircraft to fit simultaneously inside. Sec. 310.

- The taxilane easement safety area must be a weight-bearing surface. Gravel for ground cover is discouraged, and if requested, must be between 2" -3" diameter. *FAA Advisory Circular Airport Design.*
- The Maximum Recommended Wingspan for aircraft stored in the airpark is 66 feet or less as stated in the *Airpark Rules and Regulations, Sec. 206*
- Vehicular access to hangar/staging area must not traverse taxilane easement and requires a gate. *Sec. 404*

- Existing or proposed fuel facility.** A fuel storage area must be constructed and maintained in accordance with the regulations in *Sec. 511.*
- Proposed architectural barriers** (buildings, walls, bollards, etc.) that will separate auto parking area and taxilane easement safety area.
- Drop-offs, objects** exceeding 3" in height or vegetation in the taxilane safety area (50' from airpark taxilane centerline) are not permitted. *FAA Advisory Circular Airport Design.*
- Exterior lighting locations.** Lighting must be illuminated downward toward taxilane.
- Landscape plan.** Slope gradients should not exceed 5%; storm water retention is prohibited.
- Refuse collection dumpster storage locations.** Locate away from aircraft staging, taxilane access points and airport property fence line.
- Helicopter landing area** (if applicable). Proposed helicopter operations require approval from both the city and FAA and a conditional use permit. A conditional use permit is required by the City of Scottsdale. The FAA requires completion of an FAA 7480-1 Notice of Landing Area Proposal.

3. AIRCRAFT NOISE AND OVERFLIGHT DISCLOSURE, CH. 5, SEC. 5-356 & SECT. 5-357

- Incorporate the Airport Disclosure for Development around Scottsdale Airport language into the CC&Rs or other procedural documents and provide a copy.
- An aviation easement will need to be granted to the city. If not already recorded for property, submit a notarized Aviation Easement form with packet to your project manager.

4. APPLICANT'S SIGNATURE

Signature:



Date: 12/13/19

Aviation Approval:

Date:

Comments:



August 7, 2015

55-DR-2019
12/17/2019



NOTE TO CITY REVIEWER: WE HAVE SUBMITTED TO FAA TO OBTAIN A LETTER IN TIME FOR FINAL REVIEW.

Notice Criteria Tool

Notice Criteria Tool - Desk Reference Guide V_2018.2.0

The requirements for filing with the Federal Aviation Administration for proposed structures vary based on a number of factors: height, proximity to an airport, location, and frequencies emitted from the structure, etc. For more details, please reference CFR Title 14 Part 77.9.

You must file with the FAA at least 45 days prior to construction if:

- your structure will exceed 200ft above ground level
• your structure will be in proximity to an airport and will exceed the slope ratio
• your structure involves construction of a traverseway (i.e. highway, railroad, waterway etc...) and once adjusted upward with the appropriate vertical distance would exceed a standard of 77.9(a) or (b)
• your structure will emit frequencies, and does not meet the conditions of the FAA Co-location Policy
• your structure will be in an instrument approach area and might exceed part 77 Subpart C
• your proposed structure will be in proximity to a navigation facility and may impact the assurance of navigation signal reception
• your structure will be on an airport or heliport
• filing has been requested by the FAA

If you require additional information regarding the filing requirements for your structure, please identify and contact the appropriate FAA representative using the Air Traffic Areas of Responsibility map for Off Airport construction, or contact the FAA Airports Region / District Office for On Airport construction.

The tool below will assist in applying Part 77 Notice Criteria.

Form with input fields for Latitude (33 Deg 37 M 32.26 S N), Longitude (111 Deg 55 M 44 S W), Horizontal Datum (NAD83), Site Elevation (1475), Structure Height (28), Traverseway (No Traverseway), and Is structure on airport (No).


Results

You exceed the following Notice Criteria:


Your proposed structure is in proximity to a navigation facility and may impact the assurance of navigation signal reception. The FAA, in accordance with 77.9, requests that you file.

77.9(b) by 7 ft. The nearest airport is SDL, and the nearest runway is 03/21.

The FAA requests that you file



SCOTTSDALE AIRPORT MASTER PLAN



LEGEND AND TABLE KEY

----- Municipal Boundary

Airport Influence Areas

- AC-1
- AC-2
- AC-3
- AC-P

NP - Not Permitted

P - Permitted with Use Limitations

(1) - Avigation easement required under Sec. 5-357


(2) - Noise attenuation required under Sec. 5-358

Noise Sensitive Uses	AC ¹ -3	AC-2	AC-1
Dwelling unit*	NP	P (1) (2)	P (1)
Manufactured home*	NP	P (1) (2)	P (1)
Elementary and secondary school*	NP	P (1) (2)	P (1)
Hospital*	NP	P (1) (2)	P
Travel accommodation*	NP	P (1) (2)	P
Place of worship	NP	P (1) (2)	P (1)
Cultural, civic, and social organization	NP	P (1) (2)	P (1)


* The terms dwelling unit, manufactured home, elementary and secondary school, hospital and travel accommodation defined in the Basic Zoning Ordinance.

¹ AC - Airport Compatibility District

Scottsdale Airport Vicinity, FAA Notice of Proposed Construction




Area Of Detail



INSTRUCTIONS: Proposed temporary cranes or structures which exceed a height of 100:1 slope (100 ft horizontally for 1 foot vertically) from the nearest point of the runway must provide notice to the FAA via a 7460-1 form. Forms are available at the FAA Flight Standards District Office (480 419-0111) or the Scottsdale Airport Administration Office (480 312-2321).

Scottsdale Airport Traffic Pattern Airspace



Map Date: October 18, 2001

SAMPLE FAIR DISCLOSURE FOR DEVELOPMENT AROUND SCOTTSDALE AIRPORT

NOTICE TO PURCHASERS

OF PROXIMITY TO THE SCOTTSDALE AIRPORT

To include in CC&R's or disclosure notice:

Proximity to Airport.

Each Owner of a Lot in the Airport Influence Area identified in Chapter 5 of the Scottsdale Revised Code acknowledges that, as of the date of this notice:

(a) The Lot is close to the Scottsdale Airport (the "Airport"), located generally between Frank Lloyd Wright Boulevard on the north, Pima Road on the east, Thunderbird Road on the south and Scottsdale Road on the west.

(b) The Airport is operated as a general aviation reliever/commercial service airport for Scottsdale and North Phoenix, and used generally for airplanes, jets and helicopters.

(c) Aircraft using the Airport may fly over the Lot and adjacent properties at altitudes that vary for several reasons, including weather conditions, aircraft type, aircraft performance and pilot proficiency.

(d) The majority of takeoffs and landings occur between 6:00 a.m. and 11:00 p.m., but the Airport is open 24 hours each day, so takeoffs and landings may occur at any time.

(e) The number of takeoffs and landings at the Airport average approximately 400 each day, but that number varies and may increase.

(f) Aircraft using the Airport will generate noise, the volume, pitch, amount and frequency of which will vary for several reasons, including weather conditions, aircraft type, aircraft altitude and aircraft number.

(g) Airport management attempts to minimize aircraft noise and its influence on Lots in the Airport Influence Zone, but there is no guarantee that such attempts will be effective or remain in place.

The Owner accepts and assumes any and all risks, burdens and inconvenience caused by or associated with the Airport and its operations (including noise), and agrees not to assert or make any claim arising out of the Airport and its operations against the City of Scottsdale, its elected and appointed officials, officers, directors, commissioners, representatives, employees, and agents.

Any questions regarding the operation of the Airport can be directed to the Airport Administration office at 480-312-2321.

3.4 Grantor's or others' personal perceptions of Aircraft Effects or sensitivity to Aircraft Effects.

4. Grantor shall not cause or allow the Property to be used to discharge fumes; smoke; dust; or electronic, light, laser or other emissions, which may obstruct visibility or adversely affect or interfere with the operation of aircraft or any navigational facilities. No building, mast, tree, vegetation, or other thing upon the Property shall exceed Federal Aviation Administration approved height restrictions.
5. Grantor has been advised and understands that:
 - 5.1. All or a portion of the Property is located in a noise-influence area.
 - 5.2. Aircraft Effects might be annoying to users of the Property and might interfere with the unrestricted use and enjoyment of the Property.
 - 5.3. Aircraft Effects will likely increase over time.
6. Grantor waives all rights and claims that Grantor may ever have against, and agrees not to sue, Grantee regarding Aircraft Effects. Grantor makes its waivers and agreements for itself, its successors and assigns, in favor of Grantee, and all Grantee's officers, officials, employees, agents, lessees, permittees, invitees, successors and assigns.

Grantor warrants and covenants to Grantee and its successors and assigns that Grantor is lawfully seized and possessed of the Property; that Grantor has a good and lawful right to make the conveyance described herein; and that Grantee shall have title and quiet possession against the claims of all persons.

The person executing this document on behalf of a corporation, trust or other organization warrants his or her authority to do so and that all persons necessary to bind Grantor have joined in this document. This document runs with the land in favor of Grantee's successors and assigns.

DATED this ____ day of _____, 20__.

GRANTOR: _____

for _____

for _____

N/A THERE IS NO FUEL DISPENSING INTALLATION ON SITE



SCOTTSDALE AIRPARK FUEL DISPENSING INSTALLATION APPROVAL FORM

(Required for installation of an airpark aircraft fuel dispensing and storage facility)

PURPOSE: Scottsdale Airpark Rules and Regulations specify requirements relating to fueling, flammable fluids and safety in the airpark. Proposed installation plans for fuel dispensing facilities in the airpark must be reviewed and approved by airport staff to ensure compliance with all applicable laws, ordinances, rules and regulations. Airport approval is required prior to issuance of any other applicable City permits.

INSTRUCTIONS: Please complete Section A below and submit this form with a site plan, project description and system design for review and approval by Scottsdale Airport staff prior to final plans approval or fire department inspection. After project review, Airport staff will complete Section B and return the form to the Applicant at the specified address, fax, or email address.

Section A – To be completed by Applicant. Please “x” the boxes and complete the requested information as it applies to the project.

Applicant Name and Fuel Dispensing location:

Applicant: _____

Installation Address: _____

APN: _____

Authorized Representative: _____ Title: _____

Indicate where approval should be sent: _____

Specify the number of dispensing sites, tanks, capacity of each tank, and type of fuel:

	<u>Tank 1 (Indicate capacity and fuel type below)</u>	<u>Tank 2 (Indicate capacity and fuel type below)</u>	<u>Tank 3 (Indicate capacity and fuel type below)</u>	<u>Tank 4 (Indicate capacity and fuel type below)</u>
<u>Dispensing Site 1</u>				
<u>Dispensing Site 2</u>				
<u>Dispensing Site 3</u>				

I have reviewed and understand the applicable sections of the Airpark Rules and Regulations including, without limitation, Article 500 pertaining to Fueling, Flammable Fluids, and Safety.

I certify that the statements made in this application are true and complete to the best of my knowledge. The undersigned representative certifies he/she is authorized to sign for the applicant.

Authorized Representative’s Signature Date signed

Return this completed form to: Airport Administration, 15000 N. Airport Drive, Suite 200, Scottsdale, AZ 85260

N/A THERE IS NO FUEL DISPENSING INTALLATION ON SITE

******Airport Administration Only******

Section B – To be completed by Airport Staff and returned to Applicant.

Airport staff has reviewed the submitted information pertaining to (AP#)_____, and has determined the proposed project complies with current Airpark Rules and Regulations. Total gallons for the site: _____.

Airport staff cannot approve this project based upon the submitted information. The proposed project must address the following stipulations before airport staff can approve the project:

Stipulations:

Attach copies of applicable documents

Approved Conditional Use Permit

Self-fueling Permit No. _____

Airport Director (or designee)

Date signed

WHEN RECORDED, RETURN TO:

CITY OF SCOTTSDALE
ONE STOP SHOP/RECORDS

(_____)

7447 E. Indian School Road, Suite 100
Scottsdale, AZ 85251

Exempt from Affidavit of Value
under A.R.S. § 11-1134(A)(2, 3)



**CITY OF SCOTTSDALE
AVIGATION EASEMENT**

Project No. 734-PA-2019

Q.S. _____

FOR ONE DOLLAR (\$1.00) and other good and valuable consideration received _____

The Vanderhul Family LMT Partnership (collectively "Grantor") grants to the City of Scottsdale, an Arizona municipal corporation ("Grantee"), a perpetual, non-exclusive easement upon, over and across the parcel of land (the "Property") described on the legal description and the sketch attached hereto as Exhibits "A" and "B". The purpose of the easement is for a right of flight for aircraft in the airspace above the Property.

1. "Aircraft" means any manned or unmanned device that flies.
2. Without limitation, the right of flight includes the right to operate aircraft over and near the Property, and cause any noise, vibration, fumes, light, exhaust, odors, fuel vapor particles, electronic interference, dust, annoyances, nuisances, emissions, and any other effects relating to operating aircraft (collectively "Aircraft Effects").
3. All Aircraft Effects are included within the scope of the easement, including without limitation those that reach or affect the Property or improvements to the Property, interfere with other uses of the Property, annoy users of the Property, and are caused or made worse by any changes in the following:
 - 3.1 The size, number, method of propulsion, weight, noisiness, design, fuel, category, type or other characteristics of aircraft, and in any aircraft practices, laws, rules, policies, circumstances, customs, protocols or procedures.
 - 3.2 The airport size, orientation, configuration, location, runway length, improvements or other characteristics, and in any airport practices, laws, rules, policies, circumstances, customs, protocols or procedures.
 - 3.3 The flight paths, flight frequency, flight timing, airport operations, climbing and descending, altitudes, takeoff and landing, air traffic control, and in any related aircraft and airport practices, laws, rules, policies, circumstances, customs, protocols or procedures.


- 3.4 Grantor's or others' personal perceptions of Aircraft Effects or sensitivity to Aircraft Effects.
4. Grantor shall not cause or allow the Property to be used to discharge fumes; smoke; dust; or electronic, light, laser or other emissions, which may obstruct visibility or adversely affect or interfere with the operation of aircraft or any navigational facilities. No building, mast, tree, vegetation, or other thing upon the Property shall exceed Federal Aviation Administration approved height restrictions.
5. Grantor has been advised and understands that:
- 5.1. All or a portion of the Property is located in a noise-influence area.
- 5.2. Aircraft Effects might be annoying to users of the Property and might interfere with the unrestricted use and enjoyment of the Property.
- 5.3. Aircraft Effects will likely increase over time.
6. Grantor waives all rights and claims that Grantor may ever have against, and agrees not to sue, Grantee regarding Aircraft Effects. Grantor makes its waivers and agreements for itself, its successors and assigns, in favor of Grantee, and all Grantee's officers, officials, employees, agents, lessees, permittees, invitees, successors and assigns.

Grantor warrants and covenants to Grantee and its successors and assigns that Grantor is lawfully seized and possessed of the Property; that Grantor has a good and lawful right to make the conveyance described herein; and that Grantee shall have title and quiet possession against the claims of all persons.

The person executing this document on behalf of a corporation, trust or other organization warrants his or her authority to do so and that all persons necessary to bind Grantor have joined in this document. This document runs with the land in favor of Grantee's successors and assigns.

DATED this 13 day of December, 2019.

GRANTOR:



for The Vanderhwt Family
Limited Partnership

for _____

STATE OF ARIZONA)
) ss.
County of Maricopa)

This document was acknowledged before me this ___ day of _____, 20___, by _____ for and on behalf of _____.

NOTARY PUBLIC

My commission expires:


STATE OF ARIZONA)
) ss.
County of Maricopa)

This document was acknowledged before me this 12th day of December, 2019, by _____ for and on behalf of _____.

Victoria Stewart
NOTARY PUBLIC

My commission expires:

10/26/21



Structural Calculations

Project

Silverking Office Building and Car Storage

Permit Submittal

Scottsdale, AZ



Project No. A19104

03 February 2020

BDA Engineers

Scottsdale


SEE KEY PLAN

CITY OF SCOTTSDALE
ROOF FRAMING DESIGN LOADS

LIVE 20 PSF
DEAD 20 PSF

HIGH ROOF

ROOF JOISTS



MTL DECK
MAX SPAN = 10.75

18 GA N DECK
WR = 42 PSF OK

✓ G SPACES @ 6'-8", G = 10.61'! OK

✓ JOISTS L = 44.0' WD = 215
WL = 215 PLT
WTL = 430


28 LHOB
WR = 305/496 OK
L TL

✓ EDGE BEAMS

R = 4.8D ✓
4.8L ✓

NORTH Lmax = 13' ✓

JOIST CASE




R = 6.5(4.8) = 31 KFT ✓

W8X15 MR = 32 KFT


TW22
W = 22' (200) = 0.44D
20L = 0.44L TW 10.8
D 0.21
L 0.21

SOUTH 3 SPANS



REVISE

Type PLN3™ or HSN3™



ROOF SPAN

Allowable Uniform Loads (psf)

DECK		SPAN (ft.-in.)																	
SPAN	GAGE	CRITERIA	4'-0"	5'-0"	6'-0"	7'-0"	8'-0"	9'-0"	10'-0"	11'-0"	12'-0"	13'-0"	14'-0"	15'-0"	16'-0"	17'-0"	18'-0"	19'-0"	20'-0"
SINGLE	22	Stress	300	282	196	144	110	87	71	58	49	42	36	31	28	24	22	20	18
		L/360	♦♦♦	252	146	92	62	43	32	24	18	14	12	9	8	6	5	5	4
		L/240	♦♦♦	♦♦♦	♦♦♦	138	92	65	47	36	27	22	17	14	12	10	8	7	6
	20	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	87	63	47	37	29	23	19	15	13	11	9	8
		Stress	300	300	251	184	141	112	90	75	63	53	46	40	35	31	28	25	23
		L/360	♦♦♦	♦♦♦	180	113	76	53	39	29	23	18	14	12	10	8	7	6	5
	18	L/240	♦♦♦	♦♦♦	♦♦♦	170	114	80	58	44	34	27	21	17	14	12	10	9	7
		L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	107	78	58	45	35	28	23	19	16	13	11	10
		Stress	300	300	300	274	210	166	134	111	93	79	68	60	52	46	41	37	34
	16	L/360	♦♦♦	♦♦♦	249	157	105	74	54	40	31	24	20	16	13	11	9	8	7
		L/240	♦♦♦	♦♦♦	♦♦♦	235	158	111	81	61	47	37	29	24	20	16	14	12	10
		L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	148	108	81	62	49	39	32	26	22	18	16	13
22	Stress	300	300	300	300	276	218	177	146	123	104	90	78	69	61	55	49	44	
	L/360	♦♦♦	♦♦♦	♦♦♦	200	134	94	69	52	40	31	25	20	17	14	12	10	9	
	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	201	141	103	78	60	47	38	31	25	21	18	15	13	
20	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	269	189	138	103	80	63	50	41	34	28	24	20	17	
	Stress	300	300	225	165	127	100	81	67	56	48	41	36	32	28	25	22	20	
	L/360	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	62	48	38	30	25	20	17	14	12	10
18	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	
	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	
	Stress	300	300	283	208	159	126	102	84	71	60	52	45	40	35	31	28	25	
20	L/360	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	100	75	58	46	37	30	25	20	17	15	13
	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	45	37	31	26	22	19
	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	25
18	Stress	300	300	300	295	226	178	144	119	100	85	74	64	56	50	45	40	36	
	L/360	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	134	101	78	61	49	40	33	27	23	20	17	
	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	73	60	49	41	35	29	25	
16	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	39	34
	Stress	300	300	300	300	291	230	186	154	129	110	95	83	73	64	58	52	47	
	L/360	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	229	167	126	97	76	61	50	41	34	29	24	21	
22	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	91	74	61	51	43	37	31	
	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	57	49	42
	Stress	300	300	281	207	158	125	101	84	70	60	52	45	40	35	31	28	25	
20	L/360	♦♦♦	♦♦♦	♦♦♦	189	126	89	65	49	37	29	24	19	16	13	11	9	8	
	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	59	47	38	32	26	22	19	16
	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦
18	Stress	300	300	300	260	199	157	127	105	88	75	65	57	50	44	39	35	32	
	L/360	♦♦♦	♦♦♦	♦♦♦	229	154	108	79	59	45	36	29	23	19	16	13	11	10	
	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	118	89	68	54	43	35	29	24	20	17	15	
16	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	72	57	47	38	32	27	23	20
	Stress	300	300	300	300	282	223	181	149	125	107	92	80	71	62	56	50	45	
	L/360	♦♦♦	♦♦♦	♦♦♦	♦♦♦	205	144	105	79	61	48	38	31	26	21	18	15	13	
22	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	216	157	118	91	72	57	47	38	32	27	23	20	
	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	122	96	77	62	51	43	36	31	26
	Stress	300	300	300	300	300	288	233	193	162	138	119	104	91	81	72	65	58	
20	L/360	♦♦♦	♦♦♦	♦♦♦	♦♦♦	256	180	131	98	76	60	48	39	32	27	22	19	16	
	L/240	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	269	196	148	114	89	72	58	48	40	34	29	25	
	L/180	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	♦♦♦	151	119	95	78	64	53	45	38	33

See footnotes on page 81.

project name: SILVER KING

page #: 4

design by: _____

project #: A19104

checked by: gb

date: March 2019

HIGH ROOF (CONT)

SHORT JOISTS L=21' 3 SPANS @ 0.83'

SAME INTL DECK
BEAMS AS JOISTS


B3

MID L=21' TW=8.83' D 0.18 L 0.18 W12x16 ✓

B4


END L=21' TW=4.42' D 0.09 L 0.09 W12x14 ✓

EDGE BEAM AT STAIR



B5

NS EDGE BM @ STAIR





RAM SBeam v3.0
 Silver King
 High Roof Short Beams as Joists - Middle
 Licensed to: RAM International

Gravity Beam Design

B3

5

06/08/19 13:13:31

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (21.00,0.00)

Beam Size (User Selected) = W12X16 Fy = 50.0 ksi
 Total Beam Length (ft) = 21.00
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.016	0.000
	21.000	0.016	0.000
2	0.000	0.180	0.180
	21.000	0.180	0.180

SHEAR: Max V (DL+LL) = 3.95 kips fv = 1.50 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Center	Max +	20.7	10.5	0.0	1.00	14.55 33.00	14.55 33.00
Controlling		20.7	10.5	0.0	1.00	14.55 33.00	--- ---

REACTIONS (kips):

	Left	Right
DL reaction	2.06	2.06
Max +LL reaction	1.89	1.89
Max +total reaction	3.95	3.95

DEFLECTIONS:

Dead load (in)	at	10.50 ft =	-0.287	L/D =	878
Live load (in)	at	10.50 ft =	-0.264	L/D =	956
Net Total load (in)	at	10.50 ft =	-0.551	L/D =	457



RAM SBeam v3.0
 Silver King
 High Roof Short Beams as Joists - End
 Licensed to: RAM International

Gravity Beam Design

6

BT

06/08/19 13:15:10

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (21.00,0.00)

Beam Size (User Selected) = W12X14 Fy = 50.0 ksi
 Total Beam Length (ft) = 21.00
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.014	0.000
	21.000	0.014	0.000
2	0.000	0.100	0.100
	21.000	0.100	0.100

SHEAR: Max V (DL+LL) = 2.25 kips fv = 0.98 ksi Fv = 18.76 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Center	Max +	11.8	10.5	0.0	1.00	9.51 33.00	9.51 33.00
Controlling		11.8	10.5	0.0	1.00	9.51 33.00	--- ---

REACTIONS (kips):

	Left	Right
DL reaction	1.20	1.20
Max +LL reaction	1.05	1.05
Max +total reaction	2.25	2.25

DEFLECTIONS:

Dead load (in)	at	10.50 ft =	-0.194	L/D =	1296
Live load (in)	at	10.50 ft =	-0.170	L/D =	1480
Net Total load (in)	at	10.50 ft =	-0.365	L/D =	691



RAM SBeam v3.0
 Silver King
 Hi Roof - NS Edge Beam at Stair B21
 Licensed to: RAM International

Gravity Beam Design

B21

GB

02/01/20 09:44:17

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W24X55 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
21.000	1.70	2.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.055	0.000
	44.000	0.055	0.000
2	0.000	0.110	0.110
	44.000	0.110	0.110
3	0.000	0.100	0.100
	44.000	0.100	0.100

SHEAR: Max V (DL+LL) = 12.39 kips fv = 1.39 ksi Fv = 18.78 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Center	Max +	155.4	21.0	0.0	1.00	16.22 33.00	16.22 33.00
Controlling		155.4	21.0	0.0	1.00	16.22 33.00	--- ---

REACTIONS (kips):

	Left	Right
DL reaction	6.73	6.65
Max +LL reaction	5.67	5.57
Max +total reaction	12.39	12.23

DEFLECTIONS: (Camber = 1/2)

Dead load (in)	at	22.00 ft =	-0.699	L/D =	755
Live load (in)	at	22.00 ft =	-0.604	L/D =	874
Net Total load (in)	at	22.00 ft =	-0.803	L/D =	657

ROOF (CONT)

WEST EDGE @ STAIR

B5 L=32'-0" TW=12.07'
 $\frac{12.07}{2} = 6.04'$ D 0.13
 L 0.13


W18x35 (C=1/2")
 R=3.60
 3.05

B6 WEST BM @ S1

B15
 10D
 BL
 L=44'-0" TW=6.34 + $\frac{10.61}{2} = 11.65'$ D 0.24
 L 0.24



REV'D B2




B2 LEFT

W18x50
 CAMBER
 UP 1/4"

R 27k


SOUTH EDGE BEAM



B2 CENTER

W16x26

11k 9k




B2 RIGHT

W24x62
 C=1/4"

9k 20 24

B7

CANT BM SUPPORTING B2 RIGHT





W18x40 W18x50


Roof CON


STAIR AREA

B8 START RINGS $L_{max} = 9.5$ $TW = 8.75'$ $D = 0.175$
 $L = 0.175$
 $K = (0.175)^2 (9.5)^2 / 8 = 4$ KFT
 $\sqrt{6 \times 9} \text{ o/c}$ PER. ST W8X10


B9 EDGE BM ON GL ②

 $TW = 4.5'$ $D = 0.09$
 $L = 0.09$ W12X19
 $R1$ $2.42 D$
 $2.14 L$

B10 BM ON GL ③

 $D = 0.64$ $B = 0.64$ $L = 0.5$
 17.67 9.5 $TW = 11'$
 $R2$ $2.6 D$
 $2.3 L$ W16X31

B11 
 $TW = 4.5'$ $D = 0.1$
 $L = 0.1$ W12X19
 $R2$ $2.6 D$
 $2.3 L$

B12 
 $D = 0.09$ $L = 0.09$ $B = 0.64$ $L = 0.5$
 9.5 $TW = 4.5'$ $R2$ $2.42 D$
 $2.20 L$ W16X31

B13 SAME AS B12
 $D = 0.1$ $L = 0.1$ $R2$ $2.42 D$
 $2.20 L$

B15 
 12.7 11.5 $TW = 11'$
 $R2$ $0.04 D$
 $0.04 L$ W18X55



Gravity Beam Design

B5

9

11/16/19 08:10:51

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (39.00,0.00)

Beam Size (User Selected) = W18X35 Fy = 50.0 ksi
 Total Beam Length (ft) = 39.00
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.035	0.000
	39.000	0.035	0.000
2	0.000	0.150	0.150
	39.000	0.150	0.150

SHEAR: Max V (DL+LL) = 6.53 kips fv = 1.29 ksi Fv = 19.13 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Center	Max +	63.7	19.5	0.0	1.00	13.27 33.00	13.27 33.00
Controlling		63.7	19.5	0.0	1.00	13.27 33.00	--- ---

REACTIONS (kips):

	Left	Right
DL reaction	3.61	3.61
Max +LL reaction	2.92	2.92
Max +total reaction	6.53	6.53

DEFLECTIONS: (Camber = 1/2)

Dead load (in)	at	19.50 ft =	-0.651	L/D =	719
Live load (in)	at	19.50 ft =	-0.528	L/D =	887
Net Total load (in)	at	19.50 ft =	-0.679	L/D =	689



RAM SBeam v3.0
 Silver King
 Hi Roof - West Beam at S1 - B6
 Licensed to: RAM International

Gravity Beam Design

10

B6

11/16/19 08:20:23

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W18X71 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
6.000	10.00	8.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.071	0.000
	44.000	0.071	0.000
2	0.000	0.240	0.240
	44.000	0.240	0.240

SHEAR: Max V (DL+LL) = 27.66 kips fv = 3.02 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	192.8	17.5	0.0	1.00	18.21	33.00	18.21	33.00
Controlling		192.8	17.5	0.0	1.00	18.21	33.00	---	---

REACTIONS (kips):

	Left	Right
DL reaction	15.47	8.20
Max +LL reaction	12.19	6.37
Max +total reaction	27.66	14.57

DEFLECTIONS: (Camber = 3/4)

Dead load (in)	at	21.12 ft =	-1.135	L/D =	465
Live load (in)	at	21.12 ft =	-0.887	L/D =	595
Net Total load (in)	at	21.12 ft =	-1.272	L/D =	415



RAM SBeam v3.0
 Silver King
 Hi Roof - South Edge Beams - Left B2 Left
 Licensed to: RAM International

Gravity Beam Design

1)

09/26/19 15:18:33

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (40.67,0.00)

Beam Size (User Selected) = W18X55 Fy = 50.0 ksi
 Total Beam Length (ft) = 40.67
 Cantilever on left (ft) = 12.67
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
0.000	4.20	3.80	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.055	0.000
	12.670	0.055	0.000
2	12.670	0.055	0.000
	40.670	0.055	0.000
3	12.670	0.440	0.440
	40.670	0.440	0.440
4	0.000	0.040	0.040
	12.670	0.040	0.040

SHEAR: Max V (DL+LL) = 17.10 kips fv = 2.42 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Left	Max -	-112.2	12.7	12.7	1.00	13.70	30.00	13.70	23.52
	Center	Max +	63.7	29.0	0.0	7.78	33.00	7.78	33.00
	Max -	-112.2	12.7	28.0	1.75	13.70	30.00	13.70	16.38
Controlling		-112.2	12.7	28.0	1.75	---	---	13.70	16.38

REACTIONS (kips):

	Left	Right
DL reaction	14.51	4.76
Max +LL reaction	12.30	6.16
Max -LL reaction	0.00	-1.83
Max +total reaction	26.81	10.92

DEFLECTIONS:

Left cantilever:

Dead load (in)	= -0.309	L/D = 985
Pos Live load (in)	= -0.588	L/D = 517
Neg Live load (in)	= 0.341	L/D = 891
Pos Total load (in)	= -0.896	L/D = 339
Neg Total load (in)	= 0.033	L/D = 9316



RAM SBeam v3.0
Silver King
Hi Roof - South Edge Beams - Left B2 Left
Licensed to: RAM International

Gravity Beam Design

09/26/19 15:18:33

Center span:

Dead load (in)	at	27.79 ft =	-0.070	L/D =	4785
Live load (in)	at	27.79 ft =	-0.234	L/D =	1436
Net Total load (in)	at	27.79 ft =	-0.304	L/D =	1105



RAM SBeam v3.0
 Silver King
 Hi Roof - South Edge Beams - B2 Center
 Licensed to: RAM International

Gravity Beam Design

13

09/26/19 15:21:06

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (18.00,0.00)

Beam Size (User Selected) = W16X26 Fy = 50.0 ksi
 Total Beam Length (ft) = 18.00
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.026	0.000
	18.000	0.026	0.000
2	0.000	0.440	0.440
	18.000	0.440	0.440

SHEAR: Max V (DL+LL) = 8.16 kips fv = 2.17 ksi Fv = 17.89 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Center	Max +	36.7	9.0	0.0	1.00	11.47 33.00	11.47 33.00
Controlling		36.7	9.0	0.0	1.00	11.47 33.00	--- ---

REACTIONS (kips):

	Left	Right
DL reaction	4.20	4.20
Max +LL reaction	3.96	3.96
Max +total reaction	8.16	8.16

DEFLECTIONS:

Dead load (in)	at	9.00 ft =	-0.126	L/D =	1713
Live load (in)	at	9.00 ft =	-0.119	L/D =	1814
Net Total load (in)	at	9.00 ft =	-0.245	L/D =	881



RAM SBeam v3.0
 Silver King
 Hi Roof - South Edge Beams - B2 Right
 Licensed to: RAM International

Gravity Beam Design

14

09/27/19 11:44:01

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (45.00,0.00)

Beam Size (Optimum) = W24X62 Fy = 50.0 ksi
 Total Beam Length (ft) = 45.00
 Cantilever on right (ft) = 9.33
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
19.000	8.70	7.80	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.062	0.000
	35.670	0.062	0.000
2	35.670	0.062	0.000
	45.000	0.062	0.000
3	0.000	0.440	0.440
	19.000	0.440	0.440
4	19.000	0.210	0.210
	35.670	0.210	0.210
5	35.670	0.210	0.210
	44.320	0.210	0.210

SHEAR: Max V (DL+LL) = 22.43 kips fv = 2.20 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	256.1	19.0	0.0	1.00	23.28	33.00	23.28	33.00
	Max -	-18.4	35.7	35.7	1.75	1.67	30.00	1.67	8.60
Right	Max -	-18.4	35.7	9.3	1.00	1.67	30.00	1.67	26.47
Controlling		256.1	19.0	0.0	1.00	23.28	33.00	---	---

REACTIONS (kips):

	Left	Right
DL reaction	11.83	13.35
Max +LL reaction	10.60	11.10
Max -LL reaction	-0.22	0.00
Max +total reaction	22.43	24.45

DEFLECTIONS: (Camber = 1/4)

Center span:

Dead load (in)	at	17.66 ft =	-0.602	L/D =	711
Live load (in)	at	17.83 ft =	-0.551	L/D =	776
Net Total load (in)	at	17.83 ft =	-0.903	L/D =	474



RAM SBeam v3.0
Silver King
Hi Roof - South Edge Beams - B2 Right
Licensed to: RAM International

Gravity Beam Design

09/27/19 11:44:01

Right cantilever:

Dead load (in)	=	0.457	L/D =	490
Pos Live load (in)	=	-0.039	L/D =	5670
Neg Live load (in)	=	0.442	L/D =	507
Neg Total load (in)	=	0.898	L/D =	249



RAM SBeam v3.0
 Silver King
 High Roof Cant Beam Supp B2 Right
 Licensed to: RAM International

Gravity Beam Design

16

B7

09/26/19 15:41:43

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (20.50,0.00)

Beam Size (User Selected) = W18X40 Fy = 50.0 ksi
 Total Beam Length (ft) = 20.50
 Cantilever on left (ft) = 5.50
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
0.000	8.50	7.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.040	0.000
	5.500	0.040	0.000
2	0.000	0.180	0.180
	5.500	0.180	0.180
3	5.500	0.040	0.000
	20.500	0.040	0.000
4	5.500	0.180	0.180
	20.500	0.180	0.180

SHEAR: Max V (DL+LL) = 17.70 kips fv = 3.14 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Left	Max -	-91.3	5.5	5.5	1.00	16.02	30.00	16.02	30.00
Center	Max -	-91.3	5.5	15.0	1.75	16.02	30.00	16.02	20.60
Controlling		-91.3	5.5	15.0	1.75	---	---	16.02	20.60

REACTIONS (kips):

	Left	Right
DL reaction	14.70	-1.69
Max +LL reaction	12.09	1.35
Max -LL reaction	0.00	-2.75
Max +total reaction	26.79	-0.34
Max -total reaction	14.70	-4.44

DEFLECTIONS:

Left cantilever:

Dead load (in)	= -0.166	L/D = 796
Pos Live load (in)	= -0.150	L/D = 879
Neg Live load (in)	= 0.014	L/D = 9738
Pos Total load (in)	= -0.316	L/D = 418

Center span:

Dead load (in)	at 11.72 ft = 0.057	L/D = 3174
Live load (in)	at 11.72 ft = 0.058	L/D = 3108



RAM SBeam v3.0
Silver King
High Roof Cant Beam Supp B2 Right
Licensed to: RAM International

B7

Gravity Beam Design

Center span:

Net Total load (in) at 11.72 ft = 0.115 L/D = 1570



Gravity Beam Design

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (23.50,0.00)

Beam Size (Optimum) = W12X14 Fy = 50.0 ksi
 Total Beam Length (ft) = 23.50
 Cantilever on left (ft) = 9.50
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
0.000	0.10	0.10	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.014	0.000
	9.500	0.014	0.000
2	0.000	0.100	0.100
	9.500	0.100	0.100
3	9.500	0.014	0.000
	23.500	0.014	0.000
4	9.500	0.100	0.100
	23.500	0.100	0.100

SHEAR: Max V (DL+LL) = 2.33 kips fv = 1.02 ksi Fv = 18.76 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Left	Max -	-11.6	9.5	9.5	1.00	9.31	30.00	9.31	12.05
	Max +	2.6	18.5	0.0	1.00	2.13	33.00	2.13	33.00
Center	Max -	-11.6	9.5	14.0	1.75	9.31	30.00	9.31	9.71
	Controlling	-11.6	9.5	14.0	1.75	---	---	9.31	9.71

REACTIONS (kips):

	Left	Right
DL reaction	2.42	0.36
Max +LL reaction	2.14	0.70
Max -LL reaction	0.00	-0.39
Max +total reaction	4.56	1.06
Max -total reaction	2.42	-0.03

DEFLECTIONS:

Left cantilever:

Dead load (in)	= -0.196	L/D = 1164
Pos Live load (in)	= -0.251	L/D = 910
Neg Live load (in)	= 0.073	L/D = 3121
Pos Total load (in)	= -0.446	L/D = 511



RAM SBeam v3.0
Silver King
High Roof Stair Area B9 - GL D
Licensed to: RAM International

Gravity Beam Design

19

09/27/19 10:50:47

Center span:

Dead load (in)	at	14.75 ft =	0.015	L/D =	10840
Live load (in)	at	14.75 ft =	0.046	L/D =	3676
Net Total load (in)	at	14.75 ft =	0.061	L/D =	2745



Gravity Beam Design

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (27.17,0.00)

Beam Size (User Selected) = W16X31 Fy = 50.0 ksi
 Total Beam Length (ft) = 27.17
 Cantilever on right (ft) = 9.50
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
8.840	2.60	2.50	No	No
27.150	2.20	2.10	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.031	0.000
	17.670	0.031	0.000
2	0.000	0.020	0.020
	17.670	0.020	0.020
3	17.670	0.031	0.000
	27.170	0.031	0.000
4	17.670	0.020	0.020
	27.170	0.020	0.020

SHEAR: Max V (DL+LL) = 5.67 kips fv = 1.37 ksi Fv = 19.67 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	13.7	8.8	0.0	1.00	3.49	33.00	3.49	33.00
	Max -	-44.0	17.7	17.7	1.75	11.18	30.00	11.18	15.16
Right	Max -	-44.0	17.7	9.5	1.00	11.18	30.00	11.18	22.67
Controlling		-44.0	17.7	17.7	1.75	---	---	11.18	15.16

REACTIONS (kips):

	Left	Right
DL reaction	0.44	5.75
Max +LL reaction	1.43	4.90
Max -LL reaction	-1.18	0.00
Max +total reaction	1.87	10.64
Max -total reaction	-0.74	5.75

DEFLECTIONS:

Center span:

Dead load (in)	at	11.31 ft =	0.021	L/D = 10298
Live load (in)	at	11.31 ft =	0.065	L/D = 3261
Net Total load (in)	at	11.31 ft =	0.086	L/D = 2477



RAM SBeam v3.0
Silver King
High Roof Stair Area B10 - GL3
Licensed to: RAM International

Gravity Beam Design

Right cantilever:

Dead load (in)	=	-0.219	L/D =	1039
Pos Live load (in)	=	-0.283	L/D =	805
Neg Live load (in)	=	0.081	L/D =	2829
Pos Total load (in)	=	-0.503	L/D =	453



Gravity Beam Design

22

09/27/19 11:02:07

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (27.17,0.00)

Beam Size (User Selected) = W12X19 Fy = 50.0 ksi
 Total Beam Length (ft) = 27.17
 Cantilever on right (ft) = 9.50
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
27.160	0.10	0.10	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.019	0.000
	17.670	0.019	0.000
2	0.000	0.100	0.100
	17.670	0.100	0.100
3	17.670	0.019	0.000
	27.170	0.019	0.000
4	17.670	0.100	0.100
	27.170	0.100	0.100

SHEAR: Max V (DL+LL) = 2.60 kips fv = 0.91 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	5.7	7.2	0.0	1.00	3.20	33.00	3.20	33.00
	Max -	-11.8	17.7	17.7	1.75	6.64	30.00	6.64	11.39
Right	Max -	-11.8	17.7	9.5	1.00	6.64	30.00	6.64	13.28
Controlling		-11.8	17.7	17.7	1.75	---	---	6.64	11.39

REACTIONS (kips):

	Left	Right
DL reaction	0.69	2.64
Max +LL reaction	0.88	2.24
Max -LL reaction	-0.31	0.00
Max +total reaction	1.58	4.88

DEFLECTIONS:

Center span:

Dead load (in)	at	7.95 ft =	-0.014	L/D =	14817
Live load (in)	at	7.95 ft =	-0.057	L/D =	3689
Net Total load (in)	at	7.95 ft =	-0.072	L/D =	2953

Right cantilever:

Dead load (in)	=	-0.112	L/D =	2044
Pos Live load (in)	=	-0.200	L/D =	1141
Neg Live load (in)	=	0.100	L/D =	2278



RAM SBeam v3.0
Silver King
High Roof Stair Area B11 GL 1
Licensed to: RAM International

Gravity Beam Design

Right cantilever:

Pos Total load (in) = -0.311 L/D = 732



Gravity Beam Design

24

09/27/19 11:06:42

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (18.17,0.00)

Beam Size (User Selected) = W16X31 Fy = 50.0 ksi
 Total Beam Length (ft) = 18.17
 Cantilever on right (ft) = 9.50
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
18.160	2.50	2.20	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.031	0.000
	8.670	0.031	0.000
2	0.000	0.050	0.050
	8.670	0.050	0.050
3	8.670	0.031	0.000
	18.170	0.031	0.000
4	8.670	0.050	0.050
	18.170	0.050	0.050

SHEAR: Max V (DL+LL) = 6.39 kips fv = 1.55 ksi Fv = 19.67 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max -	-50.5	8.7	8.7	1.75	12.84	30.00	12.84	30.00
Right	Max -	-50.5	8.7	9.5	1.00	12.84	30.00	12.84	22.67
Controlling		-50.5	8.7	9.5	1.00	---	---	12.84	22.67

REACTIONS (kips):

	Left	Right
DL reaction	-2.81	6.78
Max +LL reaction	0.22	5.56
Max -LL reaction	-2.67	0.00
Max +total reaction	-2.59	12.34
Max -total reaction	-5.48	6.78

DEFLECTIONS:

Center span:

Dead load (in)	at	5.03 ft =	0.020	L/D =	5186
Live load (in)	at	5.03 ft =	0.018	L/D =	5870
Net Total load (in)	at	5.03 ft =	0.038	L/D =	2753

Right cantilever:

Dead load (in)	=	-0.243	L/D =	940
Pos Live load (in)	=	-0.209	L/D =	1092



RAM SBeam v3.0
Silver King
High Roof Stair Area B12 GL 2
Licensed to: RAM International

Gravity Beam Design

25

Right cantilever:

Neg Live load (in)	= 0.002	L/D = 11124
		5
Pos Total load (in)	= -0.451	L/D = 505



RAM SBeam v3.0
 Silver King
 High Roof Stair Area B14
 Licensed to: RAM International

Gravity Beam Design

26

09/27/19 11:40:18

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W24X55 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
20.000	2.50	2.20	No	No
34.000	2.50	2.20	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.055	0.000
	44.000	0.055	0.000
2	0.000	0.250	0.250
	44.000	0.250	0.250

SHEAR: Max V (DL+LL) = 17.99 kips fv = 2.02 ksi Fv = 18.78 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	205.9	20.1	0.0	1.00	21.49	33.00	21.49	33.00
Controlling		205.9	20.1	0.0	1.00	21.49	33.00	---	---

REACTIONS (kips):

	Left	Right
DL reaction	8.65	9.79
Max +LL reaction	7.20	8.20
Max +total reaction	15.85	17.99

DEFLECTIONS: (Camber = 3/4)

Dead load (in)	at	22.22 ft =	-0.969	L/D =	545
Live load (in)	at	22.22 ft =	-0.812	L/D =	650
Net Total load (in)	at	22.22 ft =	-1.031	L/D =	512

project name: _____

design by: _____


checked by: gb

page #: _____

project #: _____


date: January 2020

REVISE FRAMING @ CANOPIES (BMS LOWER)



B5 UNCHANGED
B15 UNCHANGED
B6 UNCHANGED

B20



AS R/C



project name: OLIVE PLINY


page #: 27

design by: _____

project #: _____

checked by: gb

date: September 2019





STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (24.20,0.00)

Beam Size (User Selected) = W18X55 Fy = 50.0 ksi
 Total Beam Length (ft) = 24.20
 Cantilever on left (ft) = 12.70
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
0.000	3.60	3.00	Yes	Yes

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.055	0.000
	12.700	0.055	0.000
2	0.000	0.040	0.040
	12.700	0.040	0.040
3	12.700	0.055	0.000
	24.200	0.055	0.000
4	12.700	0.040	0.040
	24.200	0.040	0.040

SHEAR: Max V (DL+LL) = 9.01 kips fv = 1.28 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Left	Max -	-94.7	12.7	12.7	1.00	11.56	30.00	11.56	23.47
Center	Max -	-94.7	12.7	11.5	1.75	11.56	30.00	11.56	30.00
Controlling		-94.7	12.7	12.7	1.00	---	---	11.56	23.47

REACTIONS (kips):

	Left	Right
DL reaction	10.00	-4.10
Max +LL reaction	7.33	0.23
Max -LL reaction	0.00	-3.59
Max +total reaction	17.33	-3.87
Max -total reaction	10.00	-7.69

DEFLECTIONS:

Left cantilever:

Dead load (in)	= -0.354	L/D = 861
Pos Live load (in)	= -0.281	L/D = 1086
Neg Live load (in)	= 0.002	L/D = 14142
		1
Pos Total load (in)	= -0.635	L/D = 480



RAM SBeam v3.0
Silver King
Hi Roof - West Edge Canopy Beam B15
Licensed to: RAM International

Gravity Beam Design

11/16/19 08:15:52

Center span:

Dead load (in)	at	17.53 ft =	0.029	L/D =	4772
Live load (in)	at	17.53 ft =	0.023	L/D =	5879
Net Total load (in)	at	17.53 ft =	0.052	L/D =	2634

project name: SILVER KIVA

page #: 30

design by: _____

project #: A19104

checked by: gb

date: May 2019

FLOOR FRAMING

3/4" STUDB

3" NWC/3" MILDK. DL=55

DL TOT = 80
LL = 100 PSF C = 60 PSF

TYP FLOOR BEAM

7 SPACES @ $64.5 = 9.22'$


D 2.4
L 2.4

FR PROP

D 0.74 C 0.86
L 0.92


MID

FB1



W18x60 (26) ✓
(C=3/8) ✓

FB2/B



W21x62 (28) ✓
O/C

MID W/DUCT PEN


14" x 20"

~~12" x 26"~~

MID


~~POINT~~

FB2



W21x62 (28) ✓

EDGE



D 0.37 C = 0.28
L 0.46

W18x40 (17)
C = 3/8


SHORT BEAMS MIDDLE

L = 21' TW = 8.83'

D 0.71
C 0.35
L 0.88

W12x22 (10)

FB3




SHORT BEAMS END

L = 21' TW = 4.42'

D 0.36
C 0.18
L 0.44


W12x14 (7)

FB4



FLOOR KEY PLAN

31



1 LEVEL 2 FRAMING PLAN

1/8" = 1'-0" A



RAM SBeam v3.0
Silver King
Typical Floor Beam
Licensed to: RAM International

Gravity Beam Design

FBI

32

06/08/19 13:42:18

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W18X60 ✓ Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Cantilever on right (ft) = 9.33
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f'c (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 104.01	Y bar(in) = 18.44	
Seff (in3) = 142.17	Str (in3) = 175.57	
Ieff (in4) = 2129.10	Itr (in4) = 3248.62	
Stud length (in) = 5.00	Stud diam (in) = 0.75	
Stud Capacity (kips) q = 9.4		
# of studs: Max = 68 Partial = 26 Actual = 26 ✓		
Number of Stud Rows = 1 Percent of Full Composite Action = 25.56		
Top flange braced by decking.		

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
43.950	2.40	0.00	2.40	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.060	0.060	0.000	0.000
	34.670	0.060	0.060	0.000	0.000
2	0.000	0.750	0.555	0.930	0.000
	34.670	0.750	0.555	0.930	0.000
3	34.670	0.060	0.060	0.000	0.000
	44.000	0.060	0.060	0.000	0.000
4	34.670	0.750	0.555	0.930	0.000
	44.000	0.750	0.555	0.930	0.000

SHEAR: Max V (DL+LL) = 33.63 kips fv = 4.45 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	79.5	16.1	0.0	1.00	8.83	33.00	8.83	33.00
	PreCmp-	-26.8	34.7	34.7	1.75	2.97	30.00	2.97	14.57
	Max +	233.5	16.4	---	---				



	kip-ft	ft	ft		fb	Fb	fb	Fb
Mmax/Seff					19.70	33.00	---	---
Mconst/Sx+Mpost/Seff					21.83	45.00	---	---
Right Max -	-120.3	34.7	34.7	1.75	13.36	30.00	13.36	14.57
Right PreCmp-	-26.8	34.7	9.3	1.00	2.97	30.00	2.97	30.00
Right Max -	-120.3	34.7	9.3	1.00	13.36	30.00	13.36	30.00
Controlling	-120.3	34.7	34.7	1.75	---	---	13.36	14.57
fc (ksi) =	0.40	Fc =	1.58					

REACTIONS (kips):

	Left	Right
Initial reaction	9.89	17.17
DL reaction	12.38	25.65
Max +LL reaction	16.12	29.01
Max -LL reaction	-1.81	0.00
Max +total reaction	28.50	54.66

DEFLECTIONS: (Camber = 3/8) ✓

Center span:

Initial load (in)	at	16.99 ft =	-0.579	L/D =	718
Live load (in)	at	16.99 ft =	-0.489	L/D =	850
Post Comp load (in)	at	16.99 ft =	-0.528	L/D =	788
Net Total load (in)	at	16.99 ft =	-0.732	L/D =	568

Right cantilever:

Init load (in)	=	0.393	L/D =	569
Pos Live load (in)	=	-0.282	L/D =	795
Neg Live load (in)	=	0.422	L/D =	531
Pos Post Comp load (in)	=	-0.336	L/D =	666
Neg Post Comp load (in)	=	0.367	L/D =	610
Neg Total load (in)	=	0.760	L/D =	295



RAM SBeam v3.0
Silver King
Typical Floor Beam with duct pen FB22
Licensed to: RAM International

Gravity Beam Design

FB2

24

11/16/19 09:10:12

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W21X62 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Cantilever on right (ft) = 9.33
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f'c (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 104.01	Y bar(in) = 20.67	
Seff (in3) = 164.75	Str (in3) = 200.15	
Ieff (in4) = 2786.51	Itr (in4) = 4151.97	
Stud length (in) = 5.00	Stud diam (in) = 0.75	
Stud Capacity (kips) q = 9.4		
# of studs: Max = 68 Partial = 28 Actual = 28		
Number of Stud Rows = 1 Percent of Full Composite Action = 26.63		
Top flange braced by decking.		

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
43.950	2.40	0.00	2.40	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.062	0.062	0.000	0.000
	34.670	0.062	0.062	0.000	0.000
2	0.000	0.750	0.555	0.930	0.000
	34.670	0.750	0.555	0.930	0.000
3	34.670	0.062	0.062	0.000	0.000
	44.000	0.062	0.062	0.000	0.000
4	34.670	0.750	0.555	0.930	0.000
	44.000	0.750	0.555	0.930	0.000

SHEAR: Max V (DL+LL) = 33.67 kips fv = 4.01 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	79.8	16.1	0.0	1.00	7.54	33.00	7.54	33.00
	PreCmp-	-26.9	34.7	34.7	1.75	2.54	30.00	2.54	12.18
	Max +	233.8	16.4	---	---				



	kip-ft	ft	ft		fb	Fb	fb	Fb
Mmax/Seff					17.03	33.00	---	---
Mconst/Sx+Mpost/Seff					18.75	45.00	---	---
Max -	-120.4	34.7	34.7	1.75	11.37	30.00	11.37	12.18
Right PreCmp-	-26.9	34.7	9.3	1.00	2.54	30.00	2.54	28.79
Max -	-120.4	34.7	9.3	1.00	11.37	30.00	11.37	28.79
Controlling	-120.4	34.7	34.7	1.75	---	---	11.37	12.18
fc (ksi) =	0.34	Fc =	1.58					

REACTIONS (kips):

	Left	Right
Initial reaction	9.93	17.23
DL reaction	12.42	25.72
Max +LL reaction	16.12	29.01
Max -LL reaction	-1.81	0.00
Max +total reaction	28.54	54.73

DEFLECTIONS:

Multipliers for effects of Web Openings:

Span	Precomp/Noncomp	Composite
Center Span	1.000	1.000
Right Cantilever	1.000	1.000

Center span:

Initial load (in)	at	16.99 ft =	-0.430	L/D =	967
Live load (in)	at	16.99 ft =	-0.374	L/D =	1113
Post Comp load (in)	at	16.99 ft =	-0.403	L/D =	1032
Net Total load (in)	at	16.99 ft =	-0.834	L/D =	499

Right cantilever:

Init load (in)	=	0.292	L/D =	767
Pos Live load (in)	=	-0.213	L/D =	1051
Neg Live load (in)	=	0.322	L/D =	695
Pos Post Comp load (in)	=	-0.254	L/D =	883
Neg Post Comp load (in)	=	0.282	L/D =	795
Neg Total load (in)	=	0.574	L/D =	390

WEB OPENINGS:

#	Opening			B	Position	Stiffener					
	Dist* ft	Shp	H/Dia in			to in	Width in	Thick in	Length in	Sides	Weld in
1	18.00	Rect	14.00	20.00	Centered	Center	---	---	---	---	---

*Dist is the distance along the beam from the left end.

Opening #1 at 18.000 ft

Minimum corner radii (in): 0.8000 or greater

Min. Slab Reinforcement: 0.0025 Transv. and Longit. within a distance of 1.75 ft of opening

Min. Shear Connectors: 2 studs/ft for a dist. 1.75 ft from opening towards max moment point

Capacity - Noncomposite / Precomposite



Top Tee
 Prt = 0.00 kips mut = 0.00 nut = 5.71 alphavt = 0.33
 Vpt = 40.41 kips Vmt = 13.29 kips

Bottom Tee
 Prb = 0.00 kips mub = 0.00 nub = 5.71 alphavb = 0.33
 Vpb = 40.41 kips Vmb = 13.29 kips

Capacity: Vpbar = 242.49 kips
 Upper Limit Vm = 0.67 Vpbar = 161.66 kips
 Vm = 13.29 + 13.29 = 26.59 kips
 Mm = 511.62 kip-ft

Capacity - Composite

Top Tee
 Pch = 112.50 kips dh = 5.82 in Pcl = 103.13 kips dl = 3.17 in
 Prt = 0.00 kips mut = 2.32 nut = 5.71 alphavt = 0.64
 Vpt = 40.41 kips Vmt(sh) = 51.53 kips Vmt = 25.88 kips

Bottom Tee
 Prb = 0.00 kips mub = 0.00 nub = 5.71 alphavb = 0.33
 Vpb = 40.41 kips Vmb = 13.29 kips

Capacity: Vpbar = 242.49 kips Vcbar = 0.00 kips
 Upper Limit Vm = 0.67 Vpbar + Vcbar = 161.66 kips
 Vm = 25.88 + 13.29 = 39.17 kips
 Mm = 580.75 kip-ft

Precomposite

Vu = 2.02 kips Mu = 133.72 kip-ft at 18.00 ft (1.7DL+1.7LL)
 Interaction: Vu / 1.00 Vm = 0.076
 Mu / 1.00 Mm = 0.261
 M - V Interaction = 0.263

Composite

Vu = 4.80 kips Mu = 393.51 kip-ft at 18.00 ft (1.7DL+1.7LL)
 Interaction: Vu / 1.00 Vm = 0.122
 Mu / 1.00 Mm = 0.678
 M - V Interaction = 0.679

Compression Tee Buckling

Couple arm distance (in) = 19.74 phi = 1.00
 K = 1.0 L (in) = 20.00
 Top: area (in²) = 6.22 rx (in) = 0.79 ry (in) = 2.15

Cond	Mu kip-ft	LoadCombo	Pu kips	phi*Pn kips	Ratio
Precomp M	133.72	1.7DL+1.7LL	81.31	296.68	0.274



RAM SBeam v3.0
Silver King
Typical Floor Beam with duct pen FB2B
Licensed to: RAM International

Gravity Beam Design

379

11/16/19 09:08:32

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W21X62 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Cantilever on right (ft) = 9.33
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f'c (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) =	104.01	Y bar(in) = 20.67
Seff (in3) =	164.75	Str (in3) = 200.15
Ieff (in4) =	2786.51	Itr (in4) = 4151.97
Stud length (in) =	5.00	Stud diam (in) = 0.75
Stud Capacity (kips) q = 9.4		
# of studs: Max = 68	Partial = 28	Actual = 28
Number of Stud Rows = 1	Percent of Full Composite Action = 26.63	
Top flange braced by decking.		

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
43.950	2.40	0.00	2.40	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.062	0.062	0.000	0.000
	34.670	0.062	0.062	0.000	0.000
2	0.000	0.750	0.555	0.930	0.000
	34.670	0.750	0.555	0.930	0.000
3	34.670	0.062	0.062	0.000	0.000
	44.000	0.062	0.062	0.000	0.000
4	34.670	0.750	0.555	0.930	0.000
	44.000	0.750	0.555	0.930	0.000

SHEAR: Max V (DL+LL) = 33.67 kips fv = 4.01 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	79.8	16.1	0.0	1.00	7.54	33.00	7.54	33.00
	PreCmp-	-26.9	34.7	34.7	1.75	2.54	30.00	2.54	12.18
	Max +	233.8	16.4	---	---				



	kip-ft	ft	ft		fb	Fb	fb	Fb
Mmax/Seff					17.03	33.00	---	---
Mconst/Sx+Mpost/Seff					18.75	45.00	---	---
Max -	-120.4	34.7	34.7	1.75	11.37	30.00	11.37	12.18
Right PreComp-	-26.9	34.7	9.3	1.00	2.54	30.00	2.54	28.79
Max -	-120.4	34.7	9.3	1.00	11.37	30.00	11.37	28.79
Controlling	-120.4	34.7	34.7	1.75	---	---	11.37	12.18
fc (ksi) =	0.34	Fc =	1.58					

REACTIONS (kips):

	Left	Right
Initial reaction	9.93	17.23
DL reaction	12.42	25.72
Max +LL reaction	16.12	29.01
Max -LL reaction	-1.81	0.00
Max +total reaction	28.54	54.73

DEFLECTIONS:

Multipliers for effects of Web Openings:

Span	Precomp/Noncomp	Composite
Center Span	1.000	1.000
Right Cantilever	1.000	1.000

Center span:

Initial load (in)	at	16.99 ft =	-0.430	L/D =	967
Live load (in)	at	16.99 ft =	-0.374	L/D =	1113
Post Comp load (in)	at	16.99 ft =	-0.403	L/D =	1032
Net Total load (in)	at	16.99 ft =	-0.834	L/D =	499

Right cantilever:

Init load (in)	=	0.292	L/D =	767
Pos Live load (in)	=	-0.213	L/D =	1051
Neg Live load (in)	=	0.322	L/D =	695
Pos Post Comp load (in)	=	-0.254	L/D =	883
Neg Post Comp load (in)	=	0.282	L/D =	795
Neg Total load (in)	=	0.574	L/D =	390

WEB OPENINGS:

#	Opening			B	Position to	Stiffener				
	Dist* ft	Shp	H/Dia in			Width in	Thick in	Length in	Sides	Weld in
1	12.00	Rect	14.00	24.00	Centered Center	---	---	---		---

*Dist is the distance along the beam from the left end.

Opening #1 at 12.000 ft

Minimum corner radii (in): 0.8000 or greater

Min. Slab Reinforcement: 0.0025 Transv. and Longit. within a distance of 2.00 ft of opening

Min. Shear Connectors: 2 studs/ft for a dist. 2.00 ft from opening towards max moment point

Capacity - Noncomposite / Precomposite



Top Tee

Prt = 0.00 kips mut = 0.00 nut = 6.86 alphavt = 0.29
Vpt = 40.41 kips Vmt = 11.53 kips

Bottom Tee

Prb = 0.00 kips mub = 0.00 nub = 6.86 alphavb = 0.29
Vpb = 40.41 kips Vmb = 11.53 kips

Capacity: Vpbar = 242.49 kips
Upper Limit Vm = 0.67 Vpbar = 161.66 kips
Vm = 11.53 + 11.53 = 23.05 kips
Mm = 511.62 kip-ft

Capacity - Composite

Top Tee

Pch = 93.75 kips dh = 5.85 in Pcl = 75.00 kips dl = 3.12 in
Prt = 0.00 kips mut = 2.22 nut = 6.86 alphavt = 0.54
Vpt = 40.41 kips Vmt(sh) = 51.53 kips Vmt = 21.98 kips

Bottom Tee

Prb = 0.00 kips mub = 0.00 nub = 6.86 alphavb = 0.29
Vpb = 40.41 kips Vmb = 11.53 kips

Capacity: Vpbar = 242.49 kips Vcbar = 0.00 kips
Upper Limit Vm = 0.67 Vpbar + Vcbar = 161.66 kips
Vm = 21.98 + 11.53 = 33.50 kips
Mm = 570.04 kip-ft

Precomposite

Vu = 4.28 kips Mu = 126.93 kip-ft at 12.00 ft (1.7DL+1.7LL)
Interaction: Vu / 1.00 Vm = 0.186
Mu / 1.00 Mm = 0.248
M - V Interaction = 0.279

Composite

Vu = 12.98 kips Mu = 368.97 kip-ft at 12.00 ft (1.7DL+1.7LL)
Interaction: Vu / 1.00 Vm = 0.387
Mu / 1.00 Mm = 0.647
M - V Interaction = 0.691

Compression Tee Buckling

Couple arm distance (in) = 19.74 phi = 1.00
K = 1.0 L (in) = 24.00
Top: area (in²) = 6.22 rx (in) = 0.79 ry (in) = 2.15

Cond	Mu kip-ft	LoadCombo	Pu kips	phi*Pn kips	Ratio
Precomp M	126.93	1.7DL+1.7LL	77.18	290.55	0.266



Gravity Beam Design

FBS

40

06/08/19 13:55:11

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (21.00,0.00)

Beam Size (User Selected) = W12X22 ✓ Fy = 50.0 ksi
 Total Beam Length (ft) = 21.00
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f _c (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) =	63.00	Y bar(in) = 14.49
Seff (in ³) =	39.45	Str (in ³) = 51.52
Ieff (in ⁴) =	474.97	Itr (in ⁴) = 748.98
Stud length (in) =	5.00	Stud diam (in) = 0.75
Stud Capacity (kips) q = 9.4		
# of studs: Max = 21	Partial = 10	Actual = 10 ✓
Number of Stud Rows = 1	Percent of Full Composite Action = 28.93	
Top flange braced by decking.		

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.022	0.022	0.000	0.000
	21.000	0.022	0.022	0.000	0.000
2	0.000	0.710	0.350	0.880	0.000
	21.000	0.710	0.350	0.880	0.000

SHEAR: Max V (DL+LL) = 16.93 kips fv = 5.29 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	20.5	10.5	0.0	1.00	9.69	33.00	9.69	33.00
	Max +	88.9	10.5	---	---				
	Mmax/Seff					27.03	33.00	---	---
	Mconst/Sx+Mpost/Seff					30.48	45.00	---	---
Controlling		88.9	10.5	---	---	27.03	33.00	---	---
fc (ksi) = 0.51		Fc = 1.58							

REACTIONS (kips):

	Left	Right
Initial reaction	3.91	3.91
DL reaction	7.69	7.69
Max +LL reaction	9.24	9.24
Max +total reaction	16.93	16.93



DEFLECTIONS:

Initial load (in)	at	10.50 ft =	-0.360	L/D =	700
Live load (in)	at	10.50 ft =	-0.280	L/D =	901
Post Comp load (in)	at	10.50 ft =	-0.394	L/D =	640
Net Total load (in)	at	10.50 ft =	-0.754	L/D =	334



Gravity Beam Design

FB4

42

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (21.00,0.00)

Beam Size (User Selected) = W12X14 Fy = 50.0 ksi
 Total Beam Length (ft) = 21.00
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f _c (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 63.00	Y bar (in) = 14.82	= 14.82
Seff (in3) = 24.35	Str (in3) = 33.07	= 33.07
Ieff (in4) = 298.27	Itr (in4) = 491.78	= 491.78
Stud length (in) = 5.00	Stud diam (in) = 0.75	= 0.75
Stud Capacity (kips) q = 9.4		
# of studs: Max = 21	Partial = 7	Actual = 7
Number of Stud Rows = 1	Percent of Full Composite Action = 27.04	
Top flange braced by decking.		

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.014	0.014	0.000	0.000
	21.000	0.014	0.014	0.000	0.000
2	0.000	0.360	0.180	0.440	0.000
	21.000	0.360	0.180	0.440	0.000

SHEAR: Max V (DL+LL) = 8.55 kips fv = 3.73 ksi Fv = 18.76 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Center	PreCmp+	10.7	10.5	0.0	1.00	8.62 33.00	8.62 33.00
	Max +	44.9	10.5	---	---		
	Mmax/Seff					22.12 33.00	---
	Mconst/Sx+Mpost/Seff					25.46 45.00	---
Controlling		44.9	10.5	---	---	22.12 33.00	---
fc (ksi) = 0.31 Fc = 1.58							

REACTIONS (kips):

	Left	Right
Initial reaction	2.04	2.04
DL reaction	3.93	3.93
Max +LL reaction	4.62	4.62
Max +total reaction	8.55	8.55

Gravity Beam Design

43

06/08/19 13:57:36



RAM SBeam v3.0
Silver King
Short Beams - End
Licensed to: RAM International

DEFLECTIONS:


Initial load (in)	at	10.50 ft =	-0.331	L/D =	762
Live load (in)	at	10.50 ft =	-0.223	L/D =	1132
Post Comp load (in)	at	10.50 ft =	-0.314	L/D =	803
Net Total load (in)	at	10.50 ft =	-0.644	L/D =	391

FLOOR CONT

SOUTH SPAN


FBS

FBB




EDGE BM @ STAIR


FBS



DOUBLE CANT BEAM



REVERSE W/ ONLY ONE POINT LOAD @ LEFT CANT.



FBS



RAM SBeam v3.0
Silver King
Floor South Edge Beam - Mid FB5
Licensed to: RAM International

Gravity Beam Design

43

10/07/19 18:52:36

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (18.25,0.00)

Beam Size (User Selected) = W21X48 Fy = 50.0 ksi
 Total Beam Length (ft) = 18.25
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f _c (ksi)	3.50	3.50
Decking Orientation	parallel	parallel
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 54.75	Y bar(in) = 19.76	
Seff (in ³) = 120.70	Str (in ³) = 145.01	
Ieff (in ⁴) = 1980.60	Itr (in ⁴) = 2877.04	
Stud length (in) = 5.00	Stud diam (in) = 0.75	
Stud Capacity (kips) q = 12.5		
# of studs per stud segment: Full = 4,26,29		
Partial = 1,7,8		
Actual = 1,7,8		

Number of Stud Rows = 1 Percent of Full Composite Action = 28.37
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
1.000	10.00	0.00	10.00	0.00	No	No
9.380	12.40	10.00	16.20	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.048	0.048	0.000	0.000
	18.250	0.048	0.048	0.000	0.000

SHEAR: Max V (DL+LL) = 33.24 kips fv = 4.81 ksi Fv = 19.05 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	47.6	9.4	18.3	1.00	6.14	30.00	6.14	14.74
	Max +	142.1	9.4	---	---				
	Mmax/Seff					14.13	33.00	---	---
	Mconst/Sx+Mpost/Seff					15.54	45.00	---	---
Controlling		142.1	9.4	---	---	14.13	33.00	---	---
fc (ksi) = 0.33	Fc = 1.58								



46

REACTIONS (kips):

	Left	Right
Initial reaction	5.30	5.58
DL reaction	15.92	7.36
Max +LL reaction	17.33	8.87
Max +total reaction	33.24	16.23

DEFLECTIONS:

Initial load (in)	at	9.13 ft =	-0.083	L/D =	2642
Live load (in)	at	9.13 ft =	-0.068	L/D =	3226
Post Comp load (in)	at	9.13 ft =	-0.083	L/D =	2630
Net Total load (in)	at	9.13 ft =	-0.166	L/D =	1318



STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (21.00,0.00)

Beam Size (User Selected) = W21X73 Fy = 50.0 ksi
 Total Beam Length (ft) = 21.00
 Cantilever on left (ft) = 5.00
 Cantilever on right (ft) = 5.00
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
15.000	8.00	8.00	No	No
0.000	22.30	25.50	No	No
20.990	30.00	36.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.073	0.000
	5.000	0.073	0.000
2	0.000	0.710	0.880
	5.000	0.710	0.880
3	5.000	0.073	0.000
	16.000	0.073	0.000
4	5.000	0.710	0.880
	16.000	0.710	0.880
5	16.000	0.073	0.000
	21.000	0.073	0.000
6	16.000	0.710	0.880
	21.000	0.710	0.880

SHEAR: Max V (DL+LL) = 74.32 kips fv = 7.70 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange fb Fb	Compr Flange fb Fb
Left	Max -	-259.8	5.0	5.0	1.00	20.65 33.00	20.65 33.00
Center	Max -	-350.1	16.0	11.0	1.14	27.82 30.00	27.82 29.92
Right	Max -	-350.1	16.0	5.0	1.00	27.82 33.00	27.82 33.00
Controlling		-350.1	16.0	11.0	1.14	--- ---	27.82 29.92

REACTIONS (kips):

	Left	Right
DL reaction	27.78	48.97
Max +LL reaction	48.06	69.84
Max -LL reaction	-17.33	-12.59
Max +total reaction	75.84	118.81



48

DEFLECTIONS:

Left cantilever:

Dead load (in)	=	-0.163	L/D =	735
Pos Live load (in)	=	-0.202	L/D =	595
Neg Live load (in)	=	0.012	L/D =	10173
Pos Total load (in)	=	-0.365	L/D =	329

Center span:

Dead load (in)	at	10.61 ft =	0.071	L/D =	1851
Live load (in)	at	10.61 ft =	0.093	L/D =	1423
Net Total load (in)	at	10.61 ft =	0.164	L/D =	804

Right cantilever:

Dead load (in)	=	-0.186	L/D =	645
Pos Live load (in)	=	-0.236	L/D =	509
Neg Live load (in)	=	0.014	L/D =	8678
Pos Total load (in)	=	-0.422	L/D =	284

project name: SILVER KING

page #: 49

design by: _____

project #: A19104

checked by: gb

date: July 2019

FLOOR FRAMING - EAST STAIR AREA


#1 TYP STOPT BM SUPPORTING SPACING

$L = 4.75'$ max $TW = 5'$ max

$DL = 20$ psf $LL = 100$ psf

$W = 600$ PLF $M = 0.6(4.75)^2/8 = 1.7$ KFT

W6X9 o/c OR C8X11.5



$TW = 2.5'$
 $D = 0.05$
 $L = 0.25$

NON COMP

$R = 0.74D$
 $2.62L$

C12X20.7

Gravity Beam Design



RAM SBeam v3.0
 Silver King
 Floor Stair Area FB9
 Licensed to: RAM International

50

10/08/19 11:31:55

STEEL CODE, ASD ALL EL.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (21.00,0.00)

Beam Size (User Selected) = C12X20.7 Fy = 50.0 ksi
 Total Beam Length (ft) = 21.00
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.021	0.000
	21.000	0.021	0.000
2	0.000	0.050	0.250
	21.000	0.050	0.250

SHEAR: Max V (DL+LL) = 3.37 kips fv = 1.00 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	17.7	10.5	0.0	1.00	9.87	33.00	9.87	33.00
Controlling		17.7	10.5	0.0	1.00	9.87	33.00	---	---

REACTIONS (kips):

	Left	Right
DL reaction	0.74	0.74
Max +LL reaction	2.62	2.62
Max +total reaction	3.37	3.37

DEFLECTIONS:

Dead load (in)	at	10.50 ft =	-0.083	L/D =	3048
Live load (in)	at	10.50 ft =	-0.292	L/D =	862
Net Total load (in)	at	10.50 ft =	-0.375	L/D =	672



RAM SBeam v3.0
 Silver King
 Floor Framing FB10
 Licensed to: RAM International

Gravity Beam Design

51

10/08/19 12:02:24

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (Optimum) = W24X68 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Cantilever on right (ft) = 9.33
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
f'c (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 104.01	Y bar(in) = 22.60	
Seff (in3) = 196.92	Str (in3) = 237.75	
Ieff (in4) = 3655.24	Itr (in4) = 5391.96	
Stud length (in) = 5.00	Stud diam (in) = 0.75	
Stud Capacity (kips) q = 9.4		
# of studs: Max = 102	Partial = 33	Actual = 33
Number of Stud Rows = 1	Percent of Full Composite Action = 26.15	
Top flange braced by decking.		

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
43.950	2.40	0.00	2.40	0.00	No	No
19.250	6.00	4.60	9.33	0.00	No	No
39.670	0.75	0.00	2.62	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.068	0.068	0.000	0.000
	34.670	0.068	0.068	0.000	0.000
2	0.000	0.750	0.555	0.930	0.000
	34.670	0.750	0.555	0.930	0.000
3	34.670	0.068	0.068	0.000	0.000
	44.000	0.068	0.068	0.000	0.000
4	34.670	0.750	0.555	0.930	0.000
	44.000	0.750	0.555	0.930	0.000

SHEAR: Max V (DL+LL) = 42.79 kips fv = 4.58 ksi Fv = 19.79 ksi

MOMENTS:

Span Cond Moment @ Lb Cb Tension Flange Compr Flange



RAM SBeam v3.0
 Silver King
 Floor Framing FB10
 Licensed to: RAM International

Gravity Beam Design

52

10/08/19 12:02:24

		kip-ft	ft	ft		fb	Fb	fb	Fb
Center	PreCmp+	116.8	19.3	0.0	1.00	9.10	33.00	9.10	33.00
	PreCmp-	-27.1	34.7	34.7	1.75	2.11	30.00	2.11	11.18
	Max +	356.5	19.3	---	---				
	Mmax/Seff					21.73	33.00	---	---
	Mconst/Sx+Mpost/Seff					23.71	45.00	---	---
	Max -	-137.5	34.7	34.7	1.75	10.71	30.00	10.71	11.18
Right	PreCmp-	-27.1	34.7	9.3	1.00	2.11	30.00	2.11	29.39
	Max -	-137.5	34.7	9.3	1.00	10.71	30.00	10.71	29.39
Controlling		-137.5	34.7	34.7	1.75	---	---	10.71	11.18

fc (ksi) = 0.46 Fc = 1.58

REACTIONS (kips):

	Left	Right
Initial reaction	12.07	19.96
DL reaction	15.08	30.08
Max +LL reaction	20.27	37.19
Max -LL reaction	-2.19	0.00
Max +total reaction	35.35	67.27

DEFLECTIONS:

Center span:

Initial load (in)	at	17.34 ft =	-0.443	L/D =	939
Live load (in)	at	17.34 ft =	-0.415	L/D =	1003
Post Comp load (in)	at	17.34 ft =	-0.452	L/D =	921
Net Total load (in)	at	17.34 ft =	-0.895	L/D =	465

Right cantilever:

Init load (in)	=	0.322	L/D =	696
Pos Live load (in)	=	-0.191	L/D =	1171
Neg Live load (in)	=	0.355	L/D =	631
Pos Post Comp load (in)	=	-0.213	L/D =	1050
Neg Post Comp load (in)	=	0.333	L/D =	673
Neg Total load (in)	=	0.655	L/D =	342



RAM SBeam v3.0
 Silver King
 Added Floor Girder GLS5 FB11
 Licensed to: RAM International

Gravity Beam Design

53

10/08/19 12:09:16

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (18.10,0.00)

Beam Size (User Selected) = W18X55 Fy = 50.0 ksi
 Total Beam Length (ft) = 18.10
 Distance to Adjacent Beam on Left (ft) = 9.3
 Distance to Adjacent Edge on Right (ft) = 0.5

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
fc (ksi)	3.50	3.50
Decking Orientation	parallel	parallel
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 33.15	Y bar(in) = 15.75	= 15.75
Seff (in ³) = 127.82	Str (in ³) = 145.31	= 145.31
Ieff (in ⁴) = 1775.88	Itr (in ⁴) = 2300.74	= 2300.74
Stud length (in) = 5.00	Stud diam (in) = 0.75	= 0.75
Stud Capacity (kips) q = 12.5		
# of studs per stud segment: Full = 18,18	= 18,18	
Partial = 7,7	= 7,7	
Actual = 7,7	= 7,7	
Number of Stud Rows = 1	Percent of Full Composite Action = 39.43	
Top flange braced by decking.		

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
9.220	30.00	20.00	38.00	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.055	0.055	0.000	0.000
	18.100	0.055	0.055	0.000	0.000
2	0.000	0.400	0.000	0.500	0.000
	18.100	0.400	0.000	0.500	0.000

SHEAR: Max V (DL+LL) = 43.28 kips fv = 6.13 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	92.7	9.2	18.1	1.00	11.32	30.00	11.32	14.48
	Max +	346.7	9.2	---	---				
	Mmax/Seff					32.55	33.00	---	---
	Mconst/Sx+Mpost/Seff					35.16	45.00	---	---
Controlling		346.7	9.2	---	---	32.55	33.00	---	---
fc (ksi) = 1.34	Fc = 1.58								



RAM SBeam v3.0
Silver King
Added Floor Girder GLS5 FB11
Licensed to: RAM International

Gravity Beam Design

10/08/19 12:09:16

REACTIONS (kips):

	Left	Right
Initial reaction	10.31	10.69
DL reaction	18.84	19.40
Max +LL reaction	23.17	23.88
Max +total reaction	42.01	43.28

DEFLECTIONS:

Initial load (in)	at	9.14 ft =	-0.170	L/D =	1274
Live load (in)	at	9.14 ft =	-0.181	L/D =	1201
Post Comp load (in)	at	9.14 ft =	-0.241	L/D =	901
Net Total load (in)	at	9.14 ft =	-0.412	L/D =	528

project name: Silver Fire

page #: 96


design by: _____

project #: A19104



checked by: gb

date: July 2019



ADD **FB11**
NEW FLOOR GIRDER - GLSS TO CHU



WEST STAIR AREA



FB13
CANT BMS





RAM SBeam v3.0
 Silver King
 Floor West Stair Aea FB12L
 Licensed to: RAM International

Gravity Beam Design

97

10/08/19 12:34:12

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (15.33,0.00)

Beam Size (Optimum) = C12X20.7 Fy = 50.0 ksi
 Total Beam Length (ft) = 15.33
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.021	0.000
	15.330	0.021	0.000
2	0.000	0.400	0.500
	15.330	0.400	0.500
3	0.000	0.010	0.500
	15.330	0.010	0.500

SHEAR: Max V (DL+LL) = 10.97 kips fv = 3.24 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	42.0	7.7	0.0	1.00	23.46	33.00	23.46	33.00
Controlling		42.0	7.7	0.0	1.00	23.46	33.00	---	---

REACTIONS (kips):

	Left	Right
DL reaction	3.30	3.30
Max +LL reaction	7.66	7.66
Max +total reaction	10.97	10.97

DEFLECTIONS:

Dead load (in)	at	7.66 ft =	-0.143	L/D =	1286
Live load (in)	at	7.66 ft =	-0.332	L/D =	554
Net Total load (in)	at	7.66 ft =	-0.475	L/D =	387



RAM SBeam v3.0
 Silver King
 Floor West Stair Aea FB12R
 Licensed to: RAM International

Gravity Beam Design

CSB

10/08/19 12:35:41

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (13.00,0.00)

Beam Size (User Selected) = C12X20.7 Fy = 50.0 ksi
 Total Beam Length (ft) = 13.00
 Top flange braced by decking.

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.021	0.000
	13.000	0.021	0.000
2	0.000	0.400	0.500
	13.000	0.400	0.500
3	0.000	0.400	0.500
	13.000	0.400	0.500

SHEAR: Max V (DL+LL) = 11.83 kips fv = 3.50 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	38.5	6.5	0.0	1.00	21.47	33.00	21.47	33.00
Controlling		38.5	6.5	0.0	1.00	21.47	33.00	---	---

REACTIONS (kips):

	Left	Right
DL reaction	5.33	5.33
Max +LL reaction	6.50	6.50
Max +total reaction	11.83	11.83

DEFLECTIONS:

Dead load (in)	at	6.50 ft =	-0.141	L/D =	1107
Live load (in)	at	6.50 ft =	-0.172	L/D =	908
Net Total load (in)	at	6.50 ft =	-0.313	L/D =	499



RAM SBeam v3.0
 Silver King
 Floor West Stair Aea FB13
 Licensed to: RAM International

Gravity Beam Design

31

10/08/19 12:41:46

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (17.75,0.00)

Beam Size (User Selected) = W18X55 Fy = 50.0 ksi
 Total Beam Length (ft) = 17.75
 Cantilever on left (ft) = 8.75
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
0.000	8.60	14.20	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.055	0.000
	8.750	0.055	0.000
2	0.000	0.160	0.200
	8.750	0.160	0.200
3	8.750	0.055	0.000
	17.750	0.055	0.000
4	8.750	0.160	0.200
	17.750	0.160	0.200

SHEAR: Max V (DL+LL) = 26.43 kips fv = 3.74 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Left	Max -	-215.4	8.8	8.8	1.00	26.29	30.00	26.29	29.95
Center	Max -	-215.4	8.8	9.0	1.75	26.29	30.00	26.29	30.00
Controlling		-215.4	8.8	8.8	1.00	---	---	26.29	29.95

REACTIONS (kips):

	Left	Right
DL reaction	20.73	-8.31
Max +LL reaction	31.51	0.90
Max -LL reaction	0.00	-14.66
Max +total reaction	52.23	-7.41
Max -total reaction	20.73	-22.96

DEFLECTIONS:

Left cantilever:

Dead load (in)	= -0.282	L/D = 745
Pos Live load (in)	= -0.454	L/D = 463
Neg Live load (in)	= 0.004	L/D = 59008
Pos Total load (in)	= -0.736	L/D = 285

Center span:

Dead load (in)	at 12.53 ft =	0.028	L/D = 3878
Live load (in)	at 12.53 ft =	0.046	L/D = 2354



RAM SBeam v3.0
Silver King
Floor West Stair Aea FB13
Licensed to: RAM International

Gravity Beam Design

60

10/08/19 12:41:46

Center span:

Net Total load (in)

at

12.53 ft =

0.074

L/D =

1465



RAM SBeam v3.0
Silver King
West Stair Area FB14
Licensed to: RAM International

Gravity Beam Design

61

11/16/19 08:25:53

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (44.00,0.00)

Beam Size (User Selected) = W30X108 Fy = 50.0 ksi
 Total Beam Length (ft) = 44.00
 Cantilever on right (ft) = 9.33
 Distance to Adjacent Edge on Left (ft) = 0.5
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left		Right
Concrete thickness (in)	3.00		3.00
Unit weight concrete (pcf)	150.00		150.00
f _c (ksi)	3.50		3.50
Decking Orientation	perpendicular		perpendicular
Decking type	VERCO W3 Formlok		VERCO W3 Formlok
beff (in) = 58.00	Y bar(in)	=	22.74
Seff (in ³) = 353.46	Str (in ³)	=	407.15
Ieff (in ⁴) = 6907.32	Itr (in ⁴)	=	9310.60
Stud length (in) = 5.00	Stud diam (in)	=	0.75
Stud Capacity (kips) q = 9.4			
# of studs per stud segment: Full	=	27,20,10	
Partial	=	7,6,3	
Actual	=	7,5,3	

Number of Stud Rows = 1 Percent of Full Composite Action = 25.35
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
15.330	21.00	0.00	32.00	0.00	No	No
28.330	21.00	0.00	32.00	0.00	No	No
43.950	15.00	0.00	13.00	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.108	0.108	0.000	0.000
	34.670	0.108	0.108	0.000	0.000
2	0.000	0.370	0.280	0.460	0.000
	34.670	0.370	0.280	0.460	0.000
3	34.670	0.108	0.108	0.000	0.000
	44.000	0.108	0.108	0.000	0.000
4	34.670	0.370	0.280	0.460	0.000
	44.000	0.370	0.280	0.460	0.000
5	0.000	0.100	0.000	0.500	0.000
	15.330	0.100	0.000	0.500	0.000
6	15.330	0.040	0.000	0.500	0.000
	28.330	0.040	0.000	0.500	0.000



Gravity Beam Design

62

SHEAR: Max V (DL+LL) = 98.13 kips fv = 6.04 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	50.1	16.1	0.0	1.00	2.01	33.00	2.01	33.00
	PreCmp-	-16.9	34.7	34.7	1.75	0.68	30.00	0.68	13.52
	Max +	749.3	15.3	---	---				
	Mmax/Seff					25.44	33.00	---	---
	Mconst/Sx+Mpost/Seff					25.75	45.00	---	---
Right	Max -	-300.7	34.7	34.7	1.75	12.07	30.00	12.07	13.52
	PreCmp-	-16.9	34.7	9.3	1.00	0.68	30.00	0.68	28.70
	Max -	-300.7	34.7	9.3	1.00	12.07	30.00	12.07	28.70
Controlling		-300.7	34.7	34.7	1.75	---	---	12.07	13.52

fc (ksi) = 1.43 Fc = 1.58

REACTIONS (kips):

	Left	Right
Initial reaction	6.24	10.83
DL reaction	20.61	59.47
Max +LL reaction	40.05	75.41
Max -LL reaction	-4.06	0.00
Max +total reaction	60.66	134.88

DEFLECTIONS:

Center span:

Initial load (in)	at	17.16 ft =	-0.080	L/D =	5174
Live load (in)	at	17.16 ft =	-0.510	L/D =	816
Post Comp load (in)	at	17.16 ft =	-0.679	L/D =	613
Net Total load (in)	at	17.16 ft =	-0.759	L/D =	548

Right cantilever:

Init load (in)	=	0.055	L/D =	4101
Pos Live load (in)	=	-0.183	L/D =	1222
Neg Live load (in)	=	0.450	L/D =	498
Pos Post Comp load (in)	=	-0.138	L/D =	1620
Neg Post Comp load (in)	=	0.495	L/D =	452
Pos Total load (in)	=	-0.084	L/D =	2677
Neg Total load (in)	=	0.550	L/D =	407

project name: Silver/City

page #: 62 B


design by: _____

project #: M9104

checked by: gb

date: January 2020

REVISE FB14 - TOO DEEP



COL 77K 90K

HAS 5x5 x 3/8 HAS 5x5 x 3/8

FT 8'0" x 8'0" FT 8'0" x 8'0"



RAM SBeam v3.0
Silver King
West Stair Area FB14 Right Beam
Licensed to: RAM International

Gravity Beam Design

620

02/01/20 08:54:08

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (18.33,0.00)

Beam Size (Optimum) = W21X62 Fy = 50.0 ksi
 Total Beam Length (ft) = 18.33
 Cantilever on right (ft) = 9.33
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	LL	Flange Bracing	
			Top	Bottom
2.670	21.00	32.00	No	No
18.310	15.00	13.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	LL
1	0.000	0.062	0.000
	9.000	0.062	0.000
2	0.000	0.370	0.460
	9.000	0.370	0.460
3	9.000	0.062	0.000
	18.330	0.062	0.000
4	9.000	0.370	0.460
	18.330	0.370	0.460
5	0.000	0.040	0.500
	2.670	0.040	0.500

SHEAR: Max V (DL+LL) = 53.23 kips fv = 6.34 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	Max +	61.4	2.7	0.0	1.00	5.80	33.00	5.80	33.00
	Max -	-299.5	9.0	9.0	1.75	28.30	30.00	28.30	30.00
Right	PreCmp-	-16.9	9.0	0.0	0.00	1.60	0.00	1.60	0.00
	Max -	-299.5	9.0	9.3	1.00	28.30	30.00	28.30	28.79
Controlling		-299.5	9.0	9.3	1.00	---	---	28.30	28.79

REACTIONS (kips):

	Left	Right
DL reaction	-0.80	44.83
Max +LL reaction	25.71	44.73
Max -LL reaction	-15.67	0.00
Max +total reaction	24.91	89.56
Max -total reaction	-16.47	44.83

DEFLECTIONS:

Center span:

Dead load (in) at 5.45 ft = 0.025 L/D = 4313
 Live load (in) at 5.45 ft = 0.033 L/D = 3301



RAM SBeam v3.0
Silver King
West Stair Area FB14 Right Beam
Licensed to: RAM International

Gravity Beam Design

620

02/01/20 08:54:08

Center span:

Net Total load (in) at 5.45 ft = 0.058 L/D = 1870

Right cantilever:

Dead load (in)	= -0.361	L/D =	621
Pos Live load (in)	= -0.354	L/D =	633
Neg Live load (in)	= 0.056	L/D =	4015
Pos Total load (in)	= -0.714	L/D =	313



RAM SBeam v3.0
Silver King
West Stair Area FB14 Left Beam
Licensed to: RAM International

Gravity Beam Design

625

02/01/20 08:56:24

STEEL CODE: ASD 9th Ed.

SPAN INFORMATION (ft): I-End (0.00,0.00) J-End (25.67,0.00)

Beam Size (User Selected) = W21X83 Fy = 50.0 ksi
 Total Beam Length (ft) = 25.67
 Distance to Adjacent Edge on Left (ft) = 0.5
 Distance to Adjacent Beam on Right (ft) = 9.3

COMPOSITE PROPERTIES (Not Shored):

	Left	Right
Concrete thickness (in)	3.00	3.00
Unit weight concrete (pcf)	150.00	150.00
fc (ksi)	3.50	3.50
Decking Orientation	perpendicular	perpendicular
Decking type	VERCO W3 Formlok	VERCO W3 Formlok
beff (in) = 44.50	Y bar(in) = 16.85	
Seff (in3) = 209.17	Str (in3) = 242.72	
Ieff (in4) = 3045.47	Itr (in4) = 4113.90	
Stud length (in) = 5.00	Stud diam (in) = 0.75	
Stud Capacity (kips) q = 9.4		
# of studs per stud segment: Full	= 21,20	
Partial	= 6,6	
Actual	= 6,6	

Number of Stud Rows = 1 Percent of Full Composite Action = 28.32
 Top flange braced by decking.

POINT LOADS (kips):

Dist (ft)	DL	CDL	LL	CLL	Flange Bracing	
					Top	Bottom
15.330	21.00	0.00	32.00	0.00	No	No

LINE LOADS (k/ft):

Load	Dist (ft)	DL	CDL	LL	CLL
1	0.000	0.083	0.083	0.000	0.000
	25.670	0.083	0.083	0.000	0.000
2	0.000	0.370	0.280	0.460	0.000
	25.670	0.370	0.280	0.460	0.000
3	0.000	0.100	0.000	0.500	0.000
	15.330	0.100	0.000	0.500	0.000
4	15.330	0.040	0.000	0.500	0.000
	25.670	0.040	0.000	0.500	0.000

SHEAR: Max V (DL+LL) = 50.57 kips fv = 4.59 ksi Fv = 20.00 ksi

MOMENTS:

Span	Cond	Moment kip-ft	@ ft	Lb ft	Cb	Tension Flange		Compr Flange	
						fb	Fb	fb	Fb
Center	PreCmp+	29.9	12.8	0.0	1.00	2.10	33.00	2.10	33.00
	Max +	445.2	15.3	---	---				



RAM SBeam v3.0
 Silver King
 West Stair Area FB14 Left Beam
 Licensed to: RAM International

Gravity Beam Design

02/01/20 08:56:24

	kip-ft	ft	ft		fb	Fb	fb	Fb
Mmax/Seff					25.54	33.00	---	---
Mconst/Sx+Mpost/Seff					25.93	45.00	---	---
Controlling	445.2	15.3	---	---	25.54	33.00	---	---
fc (ksi) =	1.56	Fc =	1.58					

REACTIONS (kips):

	Left	Right
Initial reaction	4.66	4.66
DL reaction	15.43	19.14
Max +LL reaction	25.21	31.43
Max +total reaction	40.64	50.57

DEFLECTIONS:

Initial load (in)	at	13.35 ft =	-0.067	L/D =	4622
Live load (in)	at	13.35 ft =	-0.316	L/D =	976
Post Comp load (in)	at	13.35 ft =	-0.472	L/D =	653
Net Total load (in)	at	13.35 ft =	-0.539	L/D =	572



project name: silver pine

page #: 63

design by:

project #: A19104

checked by: gb

date: July 2019

COLS / FTG $Q_s = 1500 \text{ PPF}$
 COLUMNS UP TO ROOF $P_{max} = 49K (S1/4)(B1/4)$
 $HSS4 \times 4 \times 1/4$ $PP = 60K (N=11')$

COLS DOWN TO FTG

COL GRADE	LOAD	COL/PIER	FTG
B1/4	$P = 65K + 46K = 111K$	MP2 Wall Pier	9'0" x 9'0" F
B.5/4	$P = 46 * 3/4 = 80K$	"	8'10" x 8'0"
C/4	$P = 17 + 68 = 85K$	"	"
B-1/2	$P = 100K + 35K$	HSS 5 x 5 x 1/2 PP = 151K	10'0" x 10'0" 9'0" x 9'0"
TYP/2	$P = 65K$	HSS 4 x 4 x 3/8 PP = 74K	7'10" x 7'0"
C1/3 FB2	$P = 76$ 118	HSS 5 x 5 x 3/8	8'0" x 8'0" 9'0" x 9'0"

GARAGE AREA

WALL FTG LOAD BEARING

$$W = \frac{74}{2}(\text{roof}) + 65(24) = 3040 \text{ FT} \quad \text{FTG } 2'0" \text{ WIDE}$$

LATE

$$V_{\text{wind}} = 0.19 \left(\frac{108 + 249 + 133}{2} \right) = 47 \text{ K}$$

no DRIVING CONTROLS

$$V_{\text{wind COPY AREA}} = 30 \text{ K} \left\{ \begin{array}{l} \text{ROOF } 6 \text{ K} \\ \text{FLOOR } 24 \text{ K} \end{array} \right.$$

$$V_{\text{inlet copy}} = 17 \text{ K}$$

2 sto.


ROOF → FLOOR

$$V_{R1} \quad V = 2040 \#$$

RESISTED BY (3) COLS
DOWN TO CIMU WALL

$$V_{\text{COL}} = 900 \#$$

N/S CONTROLS



$$V_{\text{max}} = V_{R1}$$

$$V = 1305 + 1856 = 3.2 \text{ K}$$

$$P = 33 \text{ K}$$

$$M = Vh = 3.2(4) = 12.8 \text{ KFT}$$

$$\text{Interaction } \frac{P}{P_R} + \frac{M}{M_R} < 1.33$$

$$M_R = 0.6(F_y)S \\ = 0.6(46)4.11 = 113 \text{ KFT}$$

$$\text{OK } \frac{33}{55 \text{ K}} + \frac{12.8}{113} = 0.7 \text{ OK}$$

project name: SILVER KIDNEY

page #: 66

design by:

project #: A19104

checked by: gb

date: September 2019

VAT(3)

ROOF → FLOOR CON

V_{P2}

$$V = 2400^{\#} + 1900^{\#} = 4300^{\#}$$

RESISTED BY CMU @ ELEV.

(2) 9'± walls w/ #5 @ 32" oc

$$A_e = 60 \text{ in}^2/\text{ft}$$

$$f_v = \frac{V}{A_e} = \frac{4300}{60(2)9} = 4 \text{ psi} \ll f_v = 30 \text{ psi} \text{ OK}$$

V_{P5} . LESS FORCE THAN V_{P2} OK!

FLOOR → GROUND

SEE KEY

V_{F1} V_{max} = 16K

RESISTED BY CMU @ ELEV.

AS ABOVE f_v = 15 psi OK

V_{F2} V_{max} = 16 + 8.5 = 24.5K

RES. BY 8" CMU SHEAR WALL

$$L = 18' + 29' = 47'$$

$$f_v = \frac{24500}{60(47)} = 9 \text{ psi OK}$$

project name: CAIVER K109page #: 69

design by: _____

project #: A19104

checked by: gb

date: October 2019

LAT④

$$\sqrt{F3/4} \quad V_{max} = 12 + 8.5 = 20.5 + 4 \text{ PILES} = 25K$$

DES. BY 6" CMU L_{min} 5 PILES @ 4' = 20'


$$F_v = \frac{25K}{5 \text{ PILES}} = 21 \text{ PSI OK.}$$

$$60(4)$$

6" CMU STEPPED WALLS ADEQUATE

ROOF LEVEL
LAT. FORCES

$V = 6000 \#$
 $\downarrow N = 6000 / 10 \# = 50 \text{ PLF}$
 $\leftarrow N = 6000 / 44 = 126 \text{ PLF}$



VP5

VP4

VP3

