

- RESIDENTS PLACE TRASH & RECYCLABLES IN PROVDED WASTE CONTAINERS OUTSIDE OF THEIR INDIVIDUAL DWELLING UNITS AT DESIGNATED DAILY COLLECTION TIMES.
- VALET SERVICE COLLECTS ALL RESIDENT TRASH AND RECYCLABLES FROM DWELLING UNITS. STORAGE OF TRANSPORTING BINS ARE LOCATED ON THE 1ST FLOOR REFUSE ROOM.
- REFUSE IS TRANSPORTED TO COMPACTOR AND RECYCLING DUMPSTER LOCATION VIA 2 YD ROLLING DUMPSTERS.
- REFUSE IS COMPACTED AND REMOVED BY PRIVATE REFUSE CONTRACTOR.

## **COMPACTOR SPECIFICATIONS:**

SUPPLY AND INSTALL ONE (1) MARATHON RJ-250 SC, 34 YARD SELF-CONTAINED TRASH COMPACTOR TO BE CONNECTED TO A THREE PHASE (208V) POWER SUPPLY. COMPACTOR SHALL INCLUDE THE DOGHOUSE HOPPER WITH CHUTE AND SIDE DOOR WITH INTERLOCK. MULTI-CYCLE TIMER, AUTO START WIRED TO EXTERIOR DOOR SAFETY INTERLOCK. EXTERIOR DOOR WITH SAFETY INTERLOCK BUILT FROM ALUMINUM. E-STOP ON 35FT LEADS TO BE MOUNTED ON OUTSIDE OF ENCLOSURE NEAR THE DOOR. PRESSURE GAUGE ON 35FT HOSE TO BE MOUNTED OUTSIDE OF ENCLOSURE. PROVIDE A SET OF STOPS AND CONTAINER GUIDES.

RECYCLING DUMPSTER REMOVED BY PRIVATE REFUSE CONTRACTOR. RECYCLING DUMPSTER TO BE A 6YD BINS.

## REFUSE CAPACITY REQUIRED / PROVIDED:

REQUIRED CAPACITY: 1.5 CY x 155 DU TRASH

1.5 CY x 155 DU TRASH = 232 CY TRASH PER MONTH TRASH COMPACTION RATIO OF 3:1 = ±77 CY TRASH 0.5 CY x 155 DU RECYCLE = 78 CY RECYCLE PER MONTH

PROVIDED SERVICE:
(1) 34 YD COMPACTED TRASH BINS x 1 SERVICES PER WEEK = ±147 CY COMPACTED TRASH SERVICED PER MONTH
(1) 6 YD RECYCLE BINS X 3 SERVICES PER WEEK = ±78 CY
COMPACTED RECYCLE SERVICED PER MONTH

ы NO. 20-2006-02

## GREYSTAR ACTIVE INDEPENDENT LIVING

Scottsdale, AZ





ARCHITECTURE. PLANNING. LANDSCAPE ARCHITECTURE.

4019 N. 44TH ST. / PHOENIX, AZ 85018 602-952-8280 / TODDASSOC.COM Copyright 2020 Todd & Associates, Inc.


10-09-20

REZONING SUBMITTAL

Proj Mgr.
Dwn By:

## **VICINITY MAP**





REFUSE PLAN