

WASTEWATER

PRELIMINARY BASIS OF DESIGN REPORT

Headwaters Scottsdale Scottsdale, Arizona

PRELIMINARY Basis of Design Report

☒ ACCEPTED

☐ ACCEPTED AS NOTED

☐ REVISE AND RESUBMIT



Disclaimer: If accepted; the preliminary approval is granted under the condition that a final basis of design report will also be submitted for city review and approval (typically during the DR or PP case). The final report shall incorporate further water or sewer design and analysis requirements as defined in the city design standards and policy manual and address those items noted in the preliminary review comments (both separate and included herein). The final report shall be submitted and approved prior to the plan review submission.

For questions or clarifications contact the Water Resources Planning and Engineering Department at 480-312-5685.

BY jcampo

DATE 3/12/2024

Prepared for:

Headwater Group
5265 S Rio Grande Ste 201
Littleton, CO 80120



Prepared by:

Kimley»Horn

291753000
November 2022
Copyright © 2022, Kimley-Horn and Associates, Inc



Headwaters Scottsdale

WASTEWATER BASIS OF DESIGN REPORT

MARCH 2023

Prepared By:

Kimley»Horn

Contents

1.0 Introduction	1
2.0 Wastewater Analysis	2
2.1 Intent and Scope	2
2.2 General Theory	2
2.3 Wastewater Supply	2
2.4 Wastewater Demands	3
2.5 Wastewater Analysis	3
4.0 Conclusion	4
5.0 References	4

Appendices

Appendix A – Vicinity Map
Appendix B – Site Plan
Appendix C – Scottsdale Quarter Section Map
Appendix D – Sewer Calculations
Appendix E – Utility Plan
Appendix F – Max Sewer Capacity Calculation

1.0 INTRODUCTION

Kimley-Horn and Associates, Inc. has prepared this Wastewater Basis of Design Report for the proposed minimal residential healthcare living development at the southeast corner of 100th Street and Frank Lloyd Wright Boulevard in Scottsdale, Arizona. This report will demonstrate that the proposed project conforms to the City of Scottsdale design requirements.

Headwaters Scottsdale, the “project”, encompasses approximately 6.707 gross acres and contains a 203,929 gross square foot three-story and 5 one-story minimal residential healthcare facility with 217 parking spaces. The total number of units between the three-story and one-story is 172. The complex also includes a swimming pool located in the center of the three-story multifamily complex. The project lies within a portion of the Southwest Quarter of Section 8 and a Portion of the Northeast Quarter of Section 17, Township 3 North, Range 5 East of the Gila and Salt River Base and Meridian in Maricopa County, Arizona. More specifically, the project is bound by East Frank Lloyd Wright Boulevard to the north, Belmont retirement community, 134 units, to the east, single-family to the south, and North 100th Street to the west. See **Appendix A** for the Vicinity Map.

2.0 WASTEWATER ANALYSIS

2.1 INTENT AND SCOPE

The intent of this section is to evaluate the wastewater infrastructure for the proposed development. As a result of this analysis, it will be determined if the wastewater infrastructure can satisfy the projected wastewater demands for the proposed development in accordance with the City of Scottsdale Design Standards & Policies Manual (**Reference 1**).

2.2 GENERAL THEORY

The hydraulic modeling program FlowMaster, a Bentley Systems product developed by Haestad Methods, was used to model the wastewater infrastructure servicing the proposed development. The program uses the Manning equation for flow analysis of non-pressurized closed pipes. This is the typical method used to evaluate wastewater distribution systems.

2.3 WASTEWATER SUPPLY

There is an existing 8-inch VCP sewer main located in 100th Street west of the site. There is an existing public sewer main that runs through the private access road to connect the Belmont Village (134 units) to the sewer located in 100th Street. The existing public sewer main in the private road will be relocated around the proposed building. The water/sewer easement that the sewer is located in will be abandoned.

The existing public sewer main will be cut and tie into a new manholes that will allow the system to be relocated around the proposed development. The proposed 8-inch PVC will extend south, looping around the building and reconnecting to the existing 8-inch sewer main along the private access road near 100th Street entrance. A proposed 20' sewer and sewer/water easement is proposed for the relocation of the public sewer main.

The proposed 8-inch sewer main will have services for the southern buildings and main building. Refer to **Appendix E** for the Preliminary Utility Plan.

The analysis of sewer capacities in this Basis of Design Report will be limited to the 8-inch sewer main extending into the site. This analysis is limited to the use of the proposed development and existing Belmont development.

Per the City of Scottsdale request sewer monitoring was conducted at the manhole located at the intersection of Cactus Road and 100th Street. Based on the monitoring the max flow is 130.93 gallons per minute (gpm) currently. The max capacity of the pipe at maximum depth to diameter ratio (d/D) of 0.65 is 577.30 gpm. See **Appendix F** for the max sewer capacity calculation.

2.4 WASTEWATER DEMANDS

The following calculations and demands are based on Figure 7-1.2 in the City of Scottsdale's 2018 DS&PM. For clarity of building locations, reference **Appendix B** for the Site Plan. See **Appendix C** for the Scottsdale Quarter Section Map.

Table 1: Proposed Sewer Main Demands

Building	Use	DUs	Demand ¹ per unit (GPD)	Average Daily Flow (GPD)	Peak Flow ² (GPD)	Peak Flow (GPM)
Headwaters Minimal Residential Healthcare Facility	Multifamily	172	140	24,080	108,360	75
Belmont Assisted Living	Multifamily	134	140	18,760	84,420	59
Pool Backwash						100
Total For 8" Diameter Pipe						234

Notes:

1. Demands are based on Figure 7-1.2 in City of Scottsdale's 2018 DS&PM
2. The design peak flow factor for multifamily use is 4.5.
3. The pool backwash rate of 100 gpm is based on correspondence with City of Scottsdale staff.

2.5 WASTEWATER ANALYSIS

Sanitary sewer lines will be designed to maintain a maximum depth to diameter ratio (d/D) of 0.65, a minimum full flow velocity of 2.5 ft/sec and a maximum full flow velocity of 10.0 ft/sec in the ultimate peak flow condition. To verify the proposed main has adequate capacity to serve the project, design flows were analyzed with Flow Master using pipe design slopes. Pool backwash shall be connected to the sanitary sewer system through the building service and not discharge to the storm drain system. Backwash pump and pipe sizing will be done by the pool designer under separate permit. Refer to **Table 2** below and **Appendix D** for the Sewer Capacity Calculations.

Table 2: Proposed Sewer Main Capacity

	Peak Flow (GPM)	Manning Roughness (n)	Slope (ft/ft)	d/D	Velocity (ft/s)
8" Diameter Pipe	234	0.010	0.0052	0.475	3.18

The development will add a peak flow of 234 gpm to the existing sewer. The monitoring and the proposed peak flow from the development will total 364.93 gpm. The difference between the calculated flow and the monitored flow is 212.37 gpm. Based on this information the sewer provides enough capacity for the proposed development.


4.0 CONCLUSION

The development proposes to connect one new 8-inch sewer service to the existing 8-inch sewer main in the private access drive via manhole. The proposed sewer main will loop on the south side of the proposed building and reconnect to the existing sewer main near the 100th Street entrance. The proposed and existing sewer infrastructure as outlined by this analysis has adequate capacity for the flows generated by the proposed building located at the southeast corner of 100th Street and Frank Lloyd Wright Boulevard.


5.0 REFERENCES

1. City of Scottsdale, *Design Standards and Policies Manual*. 2018.
2. Sustainability Engineering Group, *Preliminary Basis of Design for Wastewater*, September 2018.

Appendix A – Vicinity Map




VICINITY MAP
CITY OF SCOTTSDALE
N.T.S.




Appendix B – Site Plan

\\V:_Civil\readwaters\Scottsdale\CADD\SP.dwg Layout: SITE PLAN Jun 06, 2023 - 8:11pm dly.fedor



 1001 West Southern Avenue, Suite 131 Mesa, Arizona 85210 (480)207-2666 © 2023	 HEADWATERS GROUP WHERE GREAT THINGS BEGIN	SEC FRANK LLOYD WRIGHT BOULEVARD & 100TH STREET SITE PLAN SCOTTSDALE, ARIZONA	PROJECT No. 291753000
			SCALE (H): 1"=20' SCALE (V): NONE DRAWN BY: AMF DESIGN BY: AMF CHECK BY: STM DATE: 06/06/2023
DESIGN DEVELOPMENT SUBMITTAL		SP.dwg SP	
4 OF 38 SHEETS			

Appendix C – Scottsdale Quarter Section Map




GENERAL NOTES:
• THIS IS A COMPUTER GENERATED DRAWING. FOR ANY REVISIONS PLEASE CONTACT THE CITY OF SCOTTSDALE GIS DEPARTMENT AT (480) 312-7792.

• THE SECTION LINE BEARING AND DISTANCES ARE BASED ON THE CITY OF SCOTTSDALE GPS SURVEY OF SEPTEMBER, 1991. BEARINGS ARE NAD 83 GRID AND DISTANCES ARE FLATTENED TO GROUND. WHERE NO CORNER WAS FOUND THE DIMENSIONS ARE GIVEN TO CALCULATED SECTION CORNERS AND ARE NOTED AS "CALCULATED" ON THE MAP.

LEGEND:


- Water Valve
- Non-potable Water Valve
- Fire Hydrant
- Water Blowoff
- Water Main Reducer
- Water Sample Station
- Water Air Release Valve
- Non-potable Water Air Release Valve
- Water Pressure Reducing Valve
- Water Vault
- Water Manhole
- Non-Potable Water Manhole
- Water Pump
- Water Main
- Non-Potable Water Main
- Fire Line
- Water Service
- Non-Scottsdale Water Main
- Sewer Manhole
- Sewer Cleanout
- Sewer Lift Station
- Sewer Treatment Plant
- Sewer Main - Gravity
- Sewer Main - Force
- Non-Scottsdale Sewer Main
- Sewer Service

VICINITY MAP



NORTH

SCALE: 1" = 100'




The map scale of 1" = 100' is based on a full size print of 30" x 36"

WATER & SEWER

QUARTER SECTION MAP

32-52

NE 1/4 SEC. 17 T3N R5E




GENERAL NOTES:

- THIS IS A COMPUTER GENERATED DRAWING. FOR ANY REVISIONS PLEASE CONTACT THE CITY OF SCOTTSDALE GIS DEPARTMENT AT (480) 312-7792.
- THE SECTION LINE BEARING AND DISTANCES ARE BASED ON THE CITY OF SCOTTSDALE GPS SURVEY OF SEPTEMBER, 1991. BEARINGS ARE NAD 83 GRID AND DISTANCES ARE FLATTENED TO GROUND. WHERE NO CORNER WAS FOUND THE DIMENSIONS ARE GIVEN TO CALCULATED SECTION CORNERS AND ARE NOTED AS CALCULATED ON THE MAP.

LEGEND:

- Cleanout
- Lift Station
- Manhole
- Non-GPS Point
- Plug
- Sewer Service Point
- Sewer Tap Point
- Sewer Valve
- Treatment Plant
- Sewer Main - Gravity
- Sewer Main - Force
- Sewer Main - Private

VICINITY MAP



NORTH

SCALE: 1" = 100'

0 50 100 200
The map scale of 1" = 100' is based on a full size print of 30" x 36"

SEWER QUARTER SECTION MAP

31-52


SE 1/4 SEC. 17 T3N R5E

Appendix D – Sewer Calculations


Sewer Capacity

Project Description	
Friction Method	Manning
Solve For	Formula
	Normal Depth
Input Data	
Roughness Coefficient	0.010
Channel Slope	0.520 %
Diameter	8.0 in
Discharge	234.00 gpm
Results	
Normal Depth	3.8 in
Flow Area	0.2 ft ²
Wetted Perimeter	1.0 ft
Hydraulic Radius	1.9 in
Top Width	0.67 ft
Critical Depth	4.1 in
Percent Full	47.6 %
Critical Slope	0.418 %
Velocity	3.18 ft/s
Velocity Head	0.16 ft
Specific Energy	0.47 ft
Froude Number	1.129
Maximum Discharge	546.91 gpm
Discharge Full	508.42 gpm
Slope Full	0.110 %
Flow Type	Supercritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Average End Depth Over Rise	0.0 %
Normal Depth Over Rise	47.6 %
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	3.8 in
Critical Depth	4.1 in
Channel Slope	0.520 %
Critical Slope	0.418 %


Appendix E – Utility Plan

[illegible]


1. STATION AND OFFSET BASED ON FRANK LLOYD WRIGHT BOULEVARD CENTERLINE.
2. ALL VALVES SHALL BE FLANGED TO TEES, BENDS, AND CROSSES.
3. ADD 1400 TO ALL ELEVATIONS.
4. ALL 8" PIPE SHALL HAVE 3' MINIMUM COVER.



22 OF 38 SHEETS

[illegible]

K:\EAV_Civil\Headwaters Scottsdale\CADD\UT.dwg; Layout:UT-2 Jun 06, 2023 - 8:13pm ally.fedor



LEGEND

	PROPERTY LINE
	RIGHT OF WAY LINE
	STREET CENTERLINE
	EASEMENT
	EXISTING SANITARY SEWER MAIN
	EXISTING PUBLIC WATER MAIN
	EXISTING ELECTRIC LINE
	PROPOSED WATER MAIN
	PROPOSED SEWER MAIN
	PROPOSED FIRE MAIN
	PROPOSED STORM DRAIN
	EXISTING SANITARY SEWER MANHOLE
	EXISTING FIRE HYDRANT
	EXISTING CATCH BASIN
	PROPOSED CLEANOUT
	PROPOSED FDC
	DEMO UTILITY



PUBLIC WATER NOTES

- (3) INSTALL 8" DUCTILE IRON CLASS 350 WATERLINE WITH POLYWRAP WITH BEDDING AND BACKFILL PER EPCOR STD DET. 350-1. LENGTH PER PLAN. 3' MIN COVER.
- (6) INSTALL 6" DUCTILE IRON WITH POLYWRAP PRESSURE CLASS 350 WATERLINE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN.
- (7) INSTALL 8" DUCTILE IRON 90° BEND WITH RESTRAINED JOINTS PER COS STD DET 2342-2 AND MAG STD DET 303.
- (9) INSTALL FIRE HYDRANT ASSEMBLY AND VALVE COMPLETE PER MAG STD DET 360-1. PROVIDE MIN. CLEARANCE PER MAG STD DET 362. INSTALL 6-INCH D.I. FIRE LINE, MORTAR LINED PER MAG SPEC 750 WITH POLYWRAP CORROSION PROTECTION PER MAG SPEC 610.5, BEDDING AND BACKFILL PER MAG SPECS. 4' MINIMUM COVER REQUIRED. LENGTH PER PLAN.
- (12) INSTALL 8"x6" TEE WITH RESTRAINED JOINTS PER COS DET DET 2342-2 AND MAG STD DET 303.
- (19) INSTALL 8" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.
- (20) INSTALL 6" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.
- (21) REMOVE EXISTING FIRE HYDRANT AND INSTALL 6" DUCTILE IRON WITH PLYWRAP PRESIRE CLASS 150 FIRELINE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN.
- (26) INSTALL 8" 11' BEND WITH RESTRAINED JOINTS PER COS STD DET 2342-2. AND MAG STD DET 303.
- (27) INSTALL 8"x6" REDUCER.
- (28) INSTALL 8"x8" TEE WITH RESTRAINED JOINTS PER COS STD DET 2342-2 AND MAG STD DET 303.

APN: 217-26-955
OWNER: BELMONT
VILLAGE
SCOTTSDALE AZ LLC
LOT 3, BK. 1039, PG.
38
NOT A PART

PRIVATE WATER

SEWER CONSTRUCTION NOTES



SECC FRANK LLOYD WRIGHT BOULEVARD & 100TH STREET

UTILITY PLAN

SCOTTSDALE, ARIZONA

PROJECT No
291753000

SCALE (H): 1"=20'

SCALE (V):NONE

DRAWN BY: AMF

DESIGN BY: AMF

CHECK BY: STM

DEVELOPMENT
DESIGN
SUBMITTAL

UT.dwg

UT-2

23 OF 38 SHEETS

Kimley»»Horn

© 2023

1001 West Southern Avenue, Suite 131
Mesa, Arizona 85210 (480)207-2666

K: EAV_Oiv\Headwaters Scottsdale\CADD\UT.dwg, Layout: UT-3 Jun 06, 2023 -- 8:13pm oif/fedor

XREFS: xtb x8m xJT xSD xPUB-**PUBLIC**

NOTES: THIS DOCUMENT AND ITS CONTENTS ARE UNCLASSIFIED AND PUBLIC RELEASE. IT IS THE PROPERTY OF THE U.S. ARMY CORP OF ENGINEERS AND IS LOANED TO YOUR AGENCY. IT IS TO BE REPRODUCED AND TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION FROM THE U.S. ARMY CORP OF ENGINEERS. THIS DOCUMENT IS NOT TO BE USED FOR ANY OTHER PURPOSES. NO WARRANTY IS MADE BY THE U.S. ARMY CORP OF ENGINEERS FOR THE ACCURACY, COMPLETENESS, OR SUITABILITY OF THE INFORMATION CONTAINED HEREIN FOR ANY SPECIFIC PURPOSE. THE U.S. ARMY CORP OF ENGINEERS ASSUMES NO LIABILITY FOR ANY DAMAGES, INCLUDING CONSEQUENTIAL DAMAGES, ARISING OUT OF OR FROM THE USE OF THIS DOCUMENT. FOR MORE INFORMATION, CONTACT THE U.S. ARMY CORP OF ENGINEERS, ATTN: PUBLIC AFFAIRS, 3151 DOWNS AVE, FORT BELVOIR, VA 22060-4397, (703) 696-7222, (703) 696-7223, (703) 696-7224, (703) 696-7225, (703) 696-7226, (703) 696-7227, (703) 696-7228, (703) 696-7229, (703) 696-7230, (703) 696-7231, (703) 696-7232, (703) 696-7233, (703) 696-7234, (703) 696-7235, (703) 696-7236, (703) 696-7237, (703) 696-7238, (703) 696-7239, (703) 696-7240, (703) 696-7241, (703) 696-7242, (703) 696-7243, (703) 696-7244, (703) 696-7245, (703) 696-7246, (703) 696-7247, (703) 696-7248, (703) 696-7249, (703) 696-7250, (703) 696-7251, (703) 696-7252, (703) 696-7253, (703) 696-7254, (703) 696-7255, (703) 696-7256, (703) 696-7257, (703) 696-7258, (703) 696-7259, (703) 696-7260, (703) 696-7261, (703) 696-7262, (703) 696-7263, (703) 696-7264, (703) 696-7265, (703) 696-7266, (703) 696-7267, (703) 696-7268, (703) 696-7269, (703) 696-7270, (703) 696-7271, (703) 696-7272, (703) 696-7273, (703) 696-7274, (703) 696-7275, (703) 696-7276, (703) 696-7277, (703) 696-7278, (703) 696-7279, (703) 696-7280, (703) 696-7281, (703) 696-7282, (703) 696-7283, (703) 696-7284, (703) 696-7285, (703) 696-7286, (703) 696-7287, (703) 696-7288, (703) 696-7289, (703) 696-7290, (703) 696-7291, (703) 696-7292, (703) 696-7293, (703) 696-7294, (703) 696-7295, (703) 696-7296, (703) 696-7297, (703) 696-7298, (703) 696-7299, (703) 696-7300, (703) 696-7301, (703) 696-7302, (703) 696-7303, (703) 696-7304, (703) 696-7305, (703) 696-7306, (703) 696-7307, (703) 696-7308, (703) 696-7309, (703) 696-7310, (703) 696-7311, (703) 696-7312, (703) 696-7313, (703) 696-7314, (703) 696-7315, (703) 696-7316, (703) 696-7317, (703) 696-7318, (703) 696-7319, (703) 696-7320, (703) 696-7321, (703) 696-7322, (703) 696-7323, (703) 696-7324, (703) 696-7325, (703) 696-7326, (703) 696-7327, (703) 696-7328, (703) 696-7329, (703) 696-7330, (703) 696-7331, (703) 696-7332, (703) 696-7333, (703) 696-7334, (703) 696-7335, (703) 696-7336, (703) 696-7337, (703) 696-7338, (703) 696-7339, (703) 696-7340, (703) 696-7341, (703) 696-7342, (703) 696-7343, (703) 696-7344, (703) 696-7345, (703) 696-7346, (703) 696-7347, (703) 696-7348, (703) 696-7349, (703) 696-7350, (703) 696-7351, (703) 696-7352, (703) 696-7353, (703) 696-7354, (703) 696-7355, (703) 696-7356, (703) 696-7357, (703) 696-7358, (703) 696-7359, (703) 696-7360, (703) 696-7361, (703) 696-7362, (703) 696-7363, (703) 696-7364, (703) 696-7365, (703) 696-7366, (703) 696-7367, (703) 696-7368, (703) 696-7369, (703) 696-7370, (703) 696-7371, (703) 696-7372, (703) 696-7373, (703) 696-7374, (703) 696-7375, (703) 696-7376, (703) 696-7377, (703) 696-7378, (703) 696-7379, (703) 696-7380, (703) 696-7381, (703) 696-7382, (703) 696-7383, (703) 696-7384, (703) 696-7385, (703) 696-7386, (703) 696-7387, (703) 696-7388, (703) 696-7389, (703) 696-7390, (703) 696-7391, (703) 696-7392, (703) 696-7393, (703) 696-7394, (703) 696-7395, (703) 696-7396, (703) 696-7397, (703) 696-7398, (703) 696-7399, (703) 696-7400, (703) 696-7401, (703) 696-7402, (703) 696-7403, (703) 696-7404, (703) 696-7405, (703) 696-7406, (703) 696-7407, (703) 696-7408, (703) 696-7409, (703) 696-7410, (703) 696-7411, (703) 696-7412, (703) 696-7413, (703) 696-7414, (703) 696-7415, (703) 696-7416, (703) 696-7417, (703) 696-7418, (703) 696-7419, (703) 696-7420, (703) 696-7421, (703) 696-7422, (703) 696-7423, (703) 696-7424, (703) 696-7425, (703) 696-7426, (703) 696-7427, (703) 696-7428, (703) 696-7429, (703) 696-7430, (703) 696-7431, (703) 696-7432, (703) 696-7433, (703) 696-7434, (703) 696-7435, (703) 696-7436, (703) 696-7437, (703) 696-7438, (703) 696-7439, (703) 696-7440, (703) 696-7441, (703) 696-7442, (703) 696-7443, (703) 696-7444, (703) 696-7445, (703) 696-7446, (703) 696-7447, (703) 696-7448, (703) 696-7449, (703) 696-7450, (703) 696-7451, (703) 696-7452, (703) 696-7453, (703) 696-7454, (703) 696-7455, (703) 696-7456, (703) 696-7457, (703) 696-7458, (703) 696-7459, (703) 696-7460, (703) 696-7461, (703) 696-7462, (703) 696-7463, (703) 696-7464, (703) 696-7465, (703) 696-7466, (703) 696-7467, (703) 696-7468, (703) 696-7469, (703) 696-7470, (703) 696-7471, (703) 696-74





-

- ⑦ INSTALL 8" DUCTILE IRON CLASS 350 WATERLINE WITH BEDDING AND BACKFILL PER EPCOR STD DET. 350-1. LENGTH PER PLAN. 3' MIN COVER.
- ⑥ INSTALL 6" DUCTILE IRON WITH POLYWRAP PRESSURE CLASS 350 WATERLINE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN.
- ⑦ INSTALL 8" DUCTILE IRON 90° BEND WITH RESTRAINED JOINTS PER COS STD DET 2342-2 AND MAG STD DET 303.
- ⑨ INSTALL FIRE HYDRANT ASSEMBLY AND VALVE COMPLETE PER MAG STD DET 360-1. PROVIDE MIN. CLEARANCE PER MAG STD DET 362, INSTALL 6-INCH D.I. FIRE LINE, MORTAR LINED PER MAG SPEC 750 WITH POLYWRAP CORROSION PROTECTION PER MAG SPEC 610.5, BEDDING AND BACKFILL PER MAG SPECS. 4' MINIMUM COVER REQUIRED. LENGTH PER PLAN.
- ⑫ INSTALL 8"x6" TEE WITH RESTRAINED JOINTS PER COS STD DET 2342-2 AND MAG STD DET 303.
- ⑮ INSTALL 8" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.
- ⑮ INSTALL 6" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.
- ⑮ CUT AND INSTALL 8"x8" TEE WITH RESTRAINED JOINTS PER COS STD DET 2342-2 AND MAG STD DET 303.

2. INSTALL 8" P.V.C SDR 35 SANITARY SEWER SERVICE LINE, BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH AND SLOPE PER PLAN.
3. CONNECT TO BUILDING 2-WAY CLEANOUT, INVERT PER PLAN. REF MEP PLANS FOR CONTINUATION.
6. INSTALL INLINE 4"x8" SEWER WYE.
7. INSTALL 6" P.V.C SDR 35 SANITARY SEWER LATERAL, BEDDING AND BACKFILL PER MAG SPEC 601, LENGTH AND SLOPE PER PLAN.
9. INSTALL 60" SANITARY SEWER MANHOLE PER MAG STD DET 420-1. MANHOLE SHALL HAVE 30" FRAME AND COVER PER COS STD DET 2421. RIM AND INVERT PER PLAN.

- ① INSTALL 2" COPPER TYPE 'K' DOMESTIC WATER SERVICE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN. 3' MIN COVER.
- ⑤ DOMESTIC WATER BUILDING CONNECTION, REF MEP PLANS FOR CONTINUATION.
- ⑥ INSTALL 2" GATE VALVE PER COS STD DET 2770 AND PER MAG STD DET 391-1, TYP C
- ①① INSTALL 2"x2" COPPER TEE.


- NOTES:
1. STATION AND OFFSET BASED ON FRANK LLOYD WRIGHT BOULEVARD CENTERLINE.
 2. ALL VALVES SHALL BE FLANGED TO TEES, BENDS, AND CROSSES.
 3. ADD 1400 TO ALL ELEVATIONS.
 4. ALL 8" PIPE SHALL HAVE 3' MINIMUM COVER.



DEVELOPMENT
DESIGN
SUBMITTAL

UT-3
24 OF 38 SHEETS

Kimley»»Horn
1001 West Southern Avenue, Suite 131
Mesa, Arizona 85210 (480)207-2666



- (1) INSTALL 8" DUCTILE IRON CLASS 350 WATERLINE WITH POLYWRAP WITH BEDDING AND BACKFILL PER EPCOR STD DET. 350-1. LENGTH PER PLAN. 3' MIN COVER.
- (4) INSTALL 4" D.I. WATER SERVICE LINE, MIN. CLASS 350. 3' MINIMUM COVER, LENGTH PER PLAN.
- (6) INSTALL 6" DUCTILE IRON WITH POLYWRAP PRESSURE CLASS 350 WATERLINE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN.
- (9) INSTALL FIRE HYDRANT ASSEMBLY AND VALVE COMPLETE PER MAG STD DET 360-1. PROVIDE MIN. CLEARANCE PER MAG STD DET 362. INSTALL 6-INCH D.I. FIRE LINE, MORTAR LINED PER MAG SPEC 750 WITH POLYWRAP CORROSION PROTECTION PER MAG SPEC 610.5, BEDDING AND BACKFILL PER MAG SPECS. 4' MINIMUM COVER REQUIRED. LENGTH PER PLAN.
- (10) INSTALL 3" WATER METER BOX PER MAG STD DET 345-1 AND COS STD DET 2345.
- (12) INSTALL 8"x6" TEE WITH RESTRAINED JOINTS PER COS DET DET 2342-2 AND MAG STD DET 303.
- (19) INSTALL 8" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.
- (20) INSTALL 6" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.
- (23) CUT AND CONNECT TO EXISTING WATER LINE AT 8" 90° BEND WITH RESTRAINED JOINTS PER COS STD DET 2342-2 AND MAG STD DET 303.
- (24) INSTALL 8" 22° BEND WITH RESTRAINED JOINTS PER COS STD DET 2342-2. AND MAG STD DET 303.
- (30) CUT AND INSTALL 8" 45° BEND WITH RESTRAINED JOINTS PER COS STD DET 2342-2. AND MAG STD DET 303.
- (31) INSTALL 2" WATER METER BOX PER MAG STD DET 345-1 AND COS STD DET 2345.
- (32) INSTALL 8"x3" TEE WITH RESTRAINED JOINTS PER COS DET DET 2342-2 AND MAG STD DET 303.
- (34) INSTALL 3" GATE VALVE PER MAG STD DET 391-1 TYPE C AND COS STD DET 2770.

- 1 INSTALL 2" COPPER TYPE 'K' DOMESTIC WATER SERVICE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN. 3' MIN COVER.
- 2 INSTALL 2" BACKFLOW PREVENTOR PER COS STD DET 2353.
- 5 DOMESTIC WATER BUILDING CONNECTION, REF MEP PLANS FOR CONTINUATION.
- 6 INSTALL 2" GATE VALVE PER COS STD DET 2770 AND PER MAG STD DET 391-1, TYP C
- 9 FIRE LINE BUILDING CONNECTION TO WITHIN 5' OF BUILDING. REF MEP PLANS FOR CONTINUATION.
- 10 INSTALL 3" BACKFLOW PREVENTOR PER COS STD DET 2353.
- 11 INSTALL 2"x2" COPPER TEE.
- 12 INSTALL 4" D.I. WATER SERVICE LINE, MIN. CLASS 350. 3' MINIMUM COVER, LENGTH PER PLAN.
- 13 INSTALL 6" DUCTILE IRON WITH POLYWRAP PRESSURE CLASS 150 FIRELINE WITH BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH PER PLAN
- 15 INSTALL 4" 90° BEND WITH THRUST BLOCKS PER MAG STD DET 391 AND NFPA 24.

2. INSTALL 8" P.V.C. SDR 35 SANITARY SEWER SERVICE LINE, BEDDING AND BACKFILL PER MAG SPEC 601. LENGTH AND SLOPE PER PLAN.
3. CONNECT TO BUILDING 2-WAY CLEANOUT, INVERT PER PLAN. REF MEP PLANS FOR CONTINUATION.
6. INSTALL INLINE 4"x8" SEWER WYE.
7. INSTALL 6" P.V.C. SDR 35 SANITARY SEWER LATERAL, BEDDING AND BACKFILL PER MAG SPEC 601, LENGTH AND SLOPE PER PLAN.
9. INSTALL 60" SANITARY SEWER MANHOLE PER MAG STD DET 420-1. MANHOLE SHALL HAVE 30" FRAME AND COVER PER COS STD DET 2421. RIM AND INVERT PER PLAN.

1. STATION AND OFFSET BASED ON FRANK LLOYD WRIGHT BOULEVARD CENTERLINE.
2. ALL VALVES SHALL BE FLANGED TO TEES, BENDS, AND CROSSES.
3. ADD 1400 TO ALL ELEVATIONS.
4. ALL 8" PIPE SHALL HAVE 3' MINIMUM COVER.



1001 West Southern Avenue, Suite 131
Mesa, Arizona 85210 (480)207-2666

SEC FRANK LLOYD WRIGHT BOULEVARD & 100TH STREET

UTILITY PLAN

SCOTTSDALE, ARIZONA

DATE: 06/06/20

UT-4

25 OF 38 SHEETS

Appendix F – Max Sewer Capacity Calculation



SL1526 RDH Flow Study for Kimley Horn

Sterling Margetts

Kimley Horn

7740 N. 16th St., Suite 300, Phoenix, AZ 85020

SL1526 RDH Flow Study, 1 site total in Scottsdale, AZ from Friday 06-23-23 to Monday 07-03-23.

Equipment for Site: Hach 901 Logger with Flo-Dar Sensor (Area Velocity).

The equipment was installed on Friday, 06/23/23 with confined space entry, pipe size confirmed, sensor calibrated, and level depth confirmed to the flow level.

Duration of monitoring: 9-days including 2 weekends

Monitor: Flow (gpm), Level (in), and Velocity (fps)

Data logging: 5-minute intervals (No averaged intervals)

Calibration Performed: Calibration method using 4.00-inch target.

Target Measure: 4.00 in Meter Read: 4.01 in 6/23/2023 07:46 am

Meter Validation: PASSED

Location #1 located on N. 100th St. and E. Cactus Rd.

72" Diameter, Rim to Invert: 115.00 inches

8" PVC pipe, flowing South

No Lateral(s)

The pipe condition is intact and reasonably clean.

Scum line of 2 inches

Flo-Dar installed pointing upstream in the 8" pipe channel.

Flow Data is valid having no missing, erroneous, or anomalies with data.

Attached is a MS Excel summary showing level, velocity, and flow logged at 5-minute intervals during the monitoring period.

RDH Environmental Services

Jeff Schulte

Operations Manager

servicemanager@rdh-env.com

SL1526 RDH Flow Study for Kimley Horn

Pictures:





SL1526 RDH Flow Study for Kimley Horn

Period Summaries:

KH COS MH1 Period Summary: Flow				
Measures	Value	Unit	Date	Time
Max.	130.93	gpm	Sunday, July 2, 2023	10:00 AM
Min.	0.00	gpm	Friday, June 23, 2023	7:15 PM
Avg.	53.84	gpm		
Total	771,041.23	gal		

KH COS MH1 Period Summary: Level				
Measures	Value	Unit	Date	Time
Max.	2.65	in	Sunday, July 2, 2023	10:00 AM
Min.	0.00	in	Friday, June 23, 2023	7:15 PM
Avg.	1.31	in		

KH COS MH1 Period Summary: Velocity				
Measures	Value	Unit	Date	Time
Max.	3.71	fps	Saturday, June 24, 2023	9:00 AM
Min.	0.00	fps	Friday, June 23, 2023	7:15 PM
Avg.	2.72	fps		

*Data begins at 8:30 am on June 23rd and ends at 7:10 am on July 3rd.



SL1526 RDH Flow Study for Kimley Horn

Site Map:



CONFINED SPACE ENTRY PERMIT

ALL COPIES OF PERMIT WILL REMAIN AT JOB SITE UNTIL JOB IS COMPLETED

LOCATION/DESCRIPTION OF CONFINED SPACE

K. H. Cactus Rd.

PURPOSE OF ENTRY

Flow Study Removal

EXPECTED HAZARDOUS

Gases

COMMUNICATIONS

Hand & Verbal

ENTRY SUPERVISOR

Nick Albertson

DATE

7-3-23

TIME

8:25

EXPIRATION

7-3-23

SPECIAL REQUIREMENTS BEFORE ENTRY:

YES

NO

YES

NO

Lockout De-energize - Test and Verify

☒

Escape Harness Required

☒

Lines Broken - Capped or Blanked

☒

Tripod Emergency Escape Unit

☒

Purge - Flush and Vent

☒

Lifelines

☒

Ventilation

☒

Fire Extinguishers

☒

Secure Area (Post and Flag)

☒

Lighting (Explosion proof)

☒

Breathing Apparatus

☒

Protective Clothing

☒

Resuscitator - Inhalator

☒

Respirator

☒

TEST INTERVAL 15 Min

TEST(S) TO BE TAKEN / ACCEPTABLE ENTRY CONDITIONS

DO NOT ENTER IF PERMISSIBLE ENTRY LEVELS ARE EXCEEDED

DATE

7-3

7-3

TESTER

NA

NA

TIME

8:30

8:30

AM/PM

M

M

M

M

M

M

M

M

M

M

% of Oxygen

19.5% to 23.5%

20.7

20.9

^ of L.F.L.* (Gas/Vapor/Mist)

Less than 10%

0

0

Carbon Monoxide

35 ppm (8 hr.)

0

0

Aromatic Hydrocarbon

1 ppm (8 hr.)

0

0

Hydrogen Sulfide

10 ppm (8 hr.)

0

0

Sulfur Dioxide

2 ppm (8 hr.)

0

0

Ammonia

25 ppm (8 hr.)

0

0

NAME OF GAS TESTER(S)

NOTE: Continuous/periodic tests shall be established before beginning the job.

Any questions pertaining to test requirements should be directed to

TESTING INSTRUMENTS USED

Honeywell

NAME

BW Tech

TYPE

GasAlertMax XT II

IDENTIFICATION NUMBER

XT-XWHM-Y-NA MA215-026608

AUTHORIZED ENTRANTS

Zac Schulte

AUTHORIZED ATTENDANTS

Jordan Astemborski

Nick Albertson

PERMIT AUTHORIZATION

I certify that all actions and conditions necessary for safe entry have been performed

Nick Albertson

NAME (Print)

Signature

7-3-23

DATE

8:45

TIME

IN CASE OF AN EMERGENCY CALL 911

100th Street Sewer

Project Description	
Friction Method	Manning
	Formula
Solve For	Discharge
Input Data	
Roughness Coefficient	0.010
Channel Slope	1.172 %
Normal Depth	5.2 in
Diameter	8.0 in
Results	
Discharge	577.30 gpm
Flow Area	0.2 ft ²
Wetted Perimeter	1.3 ft
Hydraulic Radius	2.3 in
Top Width	0.64 ft
Critical Depth	6.4 in
Percent Full	65.0 %
Critical Slope	0.695 %
Velocity	5.36 ft/s
Velocity Head	0.45 ft
Specific Energy	0.88 ft
Froude Number	1.536
Maximum Discharge	820.99 gpm
Discharge Full	763.21 gpm
Slope Full	0.670 %
Flow Type	Supercritical
GVF Input Data	
Downstream Depth	0.0 in
Length	0.0 ft
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 in
Profile Description	N/A
Profile Headloss	0.00 ft
Average End Depth Over Rise	0.0 %
Normal Depth Over Rise	65.0 %
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	5.2 in
Critical Depth	6.4 in
Channel Slope	1.172 %
Critical Slope	0.695 %