



PLANT MATERIALS LEGEND

Sym.	Plant Name	Size	Qty	Remarks
------	------------	------	-----	---------

Trees

<i>Chamaerops humilis</i> Mediterranean Fan Palm	48" box	6	ADWR
<i>Epanopsis ebano</i> Texas Ebony	48" box	3	-
<i>Parkinsonia praecox</i> Palo Brea	48" box	7	ADWR

<i>Phoenix dactylifera</i> 'Medjool' Medjool Date Palm	12'	2	ADWR
<i>Sophora secundiflora</i> Texas Mountain Laurel	36" box	3	-

<i>Washingtonia robusta</i> Mexican Fan Palm	12'	2	-
---	-----	---	---

Shrubs

<i>Asparagus densiflorus</i> 'Myers' Foxtail Fern	5 gal.	6	ADWR
<i>Bouteloua gracilis</i> 'Blonde Ambition' Blonde Ambition Blue Grama	1 gal.	2	ADWR
<i>Callistemon viminalis</i> 'Little John' Bottlebrush	5 gal.	2	ADWR
<i>Convolvulus cneorum</i> Bush Morning Glory	1 gal.	7	ADWR
<i>Dalea capitata</i> Golden Dalea	1 gal.	10	ADWR
<i>Dalea frutescens</i> Black Dalea	5 gal.	15	ADWR
<i>Eremophila hygrophana</i> 'Blue Bells' Blue Bells	5 gal.	11	ADWR
<i>Euphorbia biglandulosa</i> Gopher Plant	5 gal.	26	ADWR
<i>Muhlenbergia rigida</i> 'Nashville' Nashville Muhly	5 gal.	6	ADWR
<i>Tecoma 'Sparky'</i> Sparky Tecoma	1 gal.	2	ADWR
<i>Tecoma stans</i> Yellow Bells	5 gal.	6	ADWR
<i>Vaqueria californica</i> Arizona Rosewood	5 gal.	70	ADWR

Groundcovers

<i>Convolvulus sabatius</i> Ground Morning Glory	1 gal.	3	ADWR
<i>Eremophila glabra</i> 'Mingenew Gold' Outback Sunrise Emu	5 gal.	39	ADWR
<i>Glandularia pulchella</i> Moss Verbena	1 gal.	46	ADWR
<i>Lantana montevidensis</i> Purple Trailing Lantana	1 gal.	46	ADWR
<i>Lantana montevidensis</i> 'White' White Lantana	1 gal.	25	ADWR
<i>Lantana 'New Gold'</i> New Gold Lantana	1 gal.	11	ADWR
<i>Lantana montevidensis</i> 'Yellow Trailing' Yellow Trailing Lantana	1 gal.	10	ADWR
<i>Rosmarinus officinalis</i> 'Prostratus' Dwarf Rosemary	1 gal.	9	ADWR

Cacti

<i>Agave geminiflora</i> Agave	5 gal.	7	ADWR
<i>Hesperaloe parviflora-red</i> Red Hesperaloe	5 gal.	11	ADWR
<i>Hesperaloe parviflora-yellow</i> Yellow Hesperaloe	5 gal.	29	ADWR

MASS PLANTING

SYNTHETIC TURF, 2,000 SQ. FT. (TURF PER SPEC.)
TIGERTURF EVERGLADE FESCUE PRO.
1-800-464-0477. CONTRACTOR TO PROVIDE
SAMPLE ON SITE FOR OWNER APPROVAL
PRIOR TO PURCHASE OR INSTALL.

Sym.	Description
[Symbol]	3/4" SCREENED DECOMPOSED GRANITE, ROCK PROS USA 'MAHOGANY', 2" THICK MINIMUM.

NOTES:

- THE CONTRACTOR SHALL INSTALL NDS ROOT BARRIER PANELS AVAILABLE IN 20' ROLLS (OR APPROVED EQUAL) AT ALL TREES WITHIN 7'-0" FEET OF HARDSCAPE ELEMENTS INCLUDING (BUT NOT LIMITED TO) SIDEWALKS, ASPHALT, CONCRETE SLABS / FOOTINGS AND STRUCTURES. INSTALL PER ROOT BARRIER DETAIL. CONTRACTOR SHALL SUBMIT SPECIFICATION SHEETS OF PROPOSED ROOT BARRIER PANELS TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION.
- CONTRACTOR IS RESPONSIBLE FOR ALL SHIPPING / DELIVERY COSTS ASSOCIATED TO HAVE PLANT MATERIAL SHIPPED TO THE SITE FOR ANY OUT OF STATE MATERIALS. THIS INCLUDES, BUT IS NOT LIMITED TO, SATISFYING ALL DEPT. OF AGRICULTURE REQUIREMENTS ASSOCIATED WITH OBTAINING APPROVAL.
- LANDSCAPE ARCHITECT TO APPROVE FINAL GRADING. PLANTING SHALL NOT OCCUR UNTIL FINAL GRADING IS APPROVED.
- LOCATIONS OF PLANTS SHOWN ON DRAWING ARE APPROXIMATE. LANDSCAPE ARCHITECT TO FIELD APPROVE ALL FINAL LOCATIONS PRIOR TO INSTALLATION. LANDSCAPE CONTRACTOR HAS OPTION TO FLAG LOCATIONS OR PLACE CONTAINER MATERIAL.
- DUE TO SEASONAL AND OR UNFORESEEN CONSTRAINTS SOME PLANT MATERIAL WILL POSSIBLY NOT BE AVAILABLE AT TIME OF INSTALLATION. LANDSCAPE CONTRACTOR TO SUBMIT LIST OF ANY NON-AVAILABLE MATERIAL TO LANDSCAPE ARCHITECT FOR REPLACEMENTS TO BE SELECTED.
- ALL PLANT MATERIAL IS TO BE RETAIL QUALITY.
- LANDSCAPE CONTRACTOR TO PROVIDE PICTURES OR SAMPLES OF ALL PLANT MATERIAL PRIOR TO INSTALLATION FOR APPROVAL.
- ALL PLANT MATERIAL SOURCED FROM OUTSIDE OF ARIZONA TO BE PROPERLY ACCLIMATED TO ARIZONA CLIMATE DEPENDING ON TIME OF YEAR OF INSTALLATION. METHODS: SUN-SCREEN CLOTH/FABRIC TO BE INSTALLED ABOVE PLANT MATERIAL.
- ALL CACTI OR ACCENT MATERIAL WITH SHARP THORNS TO BE PLANTED A MINIMUM OF 3'-0" CLEAR FROM SIDEWALKS
- LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REFUSE OR SEND BACK ANY PLANT MATERIAL THAT DOES NOT MEET QUALITY STANDARDS.