

A PORTION OF THE NORTHEAST QUARTER OF SECTION 27,
TOWNSHIP 2 NORTH, RANGE 4 EAST, OF THE GILA AND SALT RIVER
BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA.

ASAM
2440 W MISSION LN, SUITE 4
PHOENIX, AZ 85021
PHONE: 602 246 9944
CONTACT: LANCE DICKSON, RLS
LANCE@ASAM1.COM

ANY WATER LINE PROJECT THAT INVOLVES CONNECTING TO AN EXISTING ACP OR PVC PIPE, REQUIRES SPECIAL ATTENTION. PER DSDM SECTION 6-1408, FITTINGS MUST BE WELDED INTO ASBESTOS CEMENT PIPE (ACP) OR PVC PIPE WITHIN 6-FEET OF ANOTHER FITTING OR JOINT WILL REQUIRE THAT SECTION OF PIPE TO BE REMOVED AND REPLACED WITH DUCTILE IRON PIPE (DIP). EXISTING TEES, TAPPING SLEEVES AND RELATED APPURTENANCES THAT ARE NOT UTILIZED BY THE DEVELOPMENT SHALL BE REMOVED BY THE CONTRACTOR. A MINIMUM 3-FOOT SECTION OF PIPE SHALL BE REMOVED, WITH NO LESS THAN 6-FEET REMAINING TO THE NEAREST JOINT. THE REMOVED PIPE SHALL BE REPLACED WITH DIP. WHEN MORE THAN 3- FEET OF EXISTING ACP OR PVC WATER LINES ARE EXPOSED DURING CONSTRUCTION AND THE BEDDING IS DISRUPTED, THE WATER LINE MUST BE REPLACED WITH DIP (MINIMUM CLASS 350) WITH MECHANICAL JOINTS AND FLAGGED JOINTS TO 3- FEET FROM THE SIDES OF THE EXPOSED CROSSING TRENCH. REFER TO AAS STANDARD DETAIL AN 401. NO TAPPING SLEEVE AND VALVE SHALL BE USED ON ACP PIPE. VALVES WILL NEED TO BE CUT INTO ACP PIPE. DISPOSAL OF MATERIALS CONTAINING ASBESTOS AND/OR LEAD SHALL BE IN CONFORMANCE WITH ALL REGULATIONS, LAWS AND ORDINANCES.



1 OF 1