



Wastewater Study

FINAL Basis of Design Report

- APPROVED
- APPROVED AS NOTED
- REVISE AND RESUBMIT



Disclaimer: If approved; the approval is granted under the condition that the final construction documents submitted for city review will match the information herein. Any subsequent changes in the water or sewer design that materially impact design criteria or standards will require re-analysis, re-submittal, and approval of a revised basis of design report prior to the plan review submission.; this approval is not a guarantee of construction document acceptance. For questions or clarifications contact the Water Resources Planning and Engineering Department at 480-312-5685.

BY Idillon DATE 10/31/2019

Address comments below and throughout in final BODs and apply relevant items to stipulations:

- 1) Phase 1 sewer pipes to Hayden can remain 8" if max flow is 439gpm in a single 8" pipe at 1% slope shown. d/D=0.68. Perform surveying of inverts to confirm slope for final BOD and provide results in final BOD. If slopes are significantly different upsizing may still be required.
- 2) Phase 2 will require upsizing of existing 8" pipe in Parkway Ave. to 12" south to Glenrosa and then 15" from Glenrosa to Miller and Indian School intersection.
- 3.) Inconsistencies throughout report on line sizes existng and proposed. Check.
- 4) Min pool backwash on any separate public sewer is 100gpm min. Revise analysis in final BOD.
- 5) Any existing lines will be fully removed to accommodate new larger required lines.

Gentry on the Green Master Wastewater Basis of Design Report

Job No. 19001704

Prepared for:
ColRich
444 West Beach Street Ste. 300
San Diego, CA 92101

Prepared by:
Atwell, LLC
4700 E Southern Ave
Mesa, AZ 85206



October 2019

**GENTRY ON THE GREEN
PRELIMINARY WASTEWATER
TABLE OF CONTENTS**

1.0	INTRODUCTION.....	1
2.0	EXISTING WASTEWATER COLLECTION SYSTEM.....	1
3.0	PROPOSED WASTEWATER SYSTEM.....	2
4.0	HYDRAULIC MODEL.....	2
4.1	BOUNDARY CONDITIONS.....	2
4.2	PHYSICAL PARAMETERS.....	3
4.3	WASTEWATER GENERATION SCENARIOS.....	3
4.4	MODELING RESULTS.....	4
5.0	CONCLUSION.....	4

APPENDICES

- A. Exhibits
- B. Wastewater Generation Calculations
- C. Wastewater System Hydraulic Analysis
- D. Wastewater Flow Test Results



1.0 INTRODUCTION

The Gentry on the Green development (the “Project”), is a proposed multi-use development that includes residential and commercial uses. The Project’s site is currently developed as three apartment complexes. The Project is located in the southeast quarter of Section 23, Township 2 North, Range 4 East of the Gila and Salt River Base and Meridian, Scottsdale, Arizona (See Vicinity Map in Appendix A). The multiple sewer mains surrounding the project site will support the proposed development. See Appendix A Quarter Section map for the existing sewer lines. The Project is approximately 42 acres and is phased into two phases (See Phasing Exhibit in Appendix A). Phase 1 is approximately 27 acres and includes 1,214 dwelling units, 31,000 square feet of commercial/retail development, and 10,000 square feet of restaurant. Phase 2 is approximately 15 acres and includes 270 dwelling units, 250 healthcare beds, and 150 hotel rooms. Phase 2 is based on a conceptual land use scenario for the purpose of determining conceptual infrastructure/traffic generation for Phase 2 and is subject to change. Refer to Appendix B for the proposed and existing wastewater generation calculations.

2.0 EXISTING WASTEWATER COLLECTION SYSTEM

The Project is located within the service area boundary of the City of Scottsdale. Sewer mains in operation exist within the Project boundary. There is an existing 8-inch VCP sewer main and manhole located on the Phase 1A and Phase 1B portion of the site that flows east into an existing 39-inch sewer main along the Hayden Road alignment. There is another 8-inch VCP line on the Phase 1D portion of the site that also flows to the 39-inch sewer main in Hayden Road. This has a slope of 1.03% based on topo information. An 8-inch VCP sewer main exists on Parkway Avenue that serves the existing Phase 2 site and flows south to Indian School Road. This has a slope of 1.92% based on topo information.

A manhole flow test was performed for the manhole at the intersection of Parkway Avenue and Indian School Road, which connects to the 8-inch sewer main on Parkway Avenue. This flow test was performed by Western Environmental Equipment Company from December 8, 2018 to December 19, 2019. The manhole flow test results were used to determine available capacity in the 8-inch sewer main that would primarily serve Phase 2 of this project and found that this line has a d/D ratio of 0.46 and a peak flow rate of 127.45 gpm. The existing Phase 2 units account for 57% of the monitored peak flow. This is based on 354 existing dwelling units in Phase 2 and the 266 dwelling units making up the remainder of dwelling units that contribute to this peak wastewater generation. The 266 units that will remain active on the Parkway Avenue sewer main derive from discussions with the City of Scottsdale staff. The existing 354 units that are being removed by developing Phase 2 account for 73 gpm ($57\% \times 127.45$ gpm). The remaining 266 units

account for 54 gpm ($43\% \times 127.45$ gpm). The 54 gpm from the remaining units will be applied to the wastewater model with the proposed demands from the Phase 2 development. The flow test results are available in Appendix D. The existing wastewater generation for the site are calculated in Appendix C.

3.0 PROPOSED WASTEWATER SYSTEM

The design of the proposed wastewater collection system is based on Bulletin 11 (ADEQ) and the City of Scottsdale Design Standards & Policies Manual and sound engineering principles. The proposed wastewater collection system is designed in accordance with the City of Scottsdale's design standards:

- High Density Residential average day generation is 140 gallons per capita per day with a peaking factor of 4.5. Residential density is assumed as 2.2 persons per unit.
- Commercial and Retail average day generation is 0.5 gallons per day per sq. ft. with a peaking factor of 3.
- Office average day generation is 0.4 gallons per day per sq. ft. with a peaking factor of 3.
- Restaurant average day generation is 1.2 gallons per day per sq. ft with a peaking factor of 6.
- Hotel average day generation is 380 gallons per day per room with a peaking factor of 4.5.

4.0 HYDRAULIC MODEL

An Excel spreadsheet was used to analyze the new wastewater collection system for the average day and the peak day wastewater generation for the project site. See Appendix C for results. The City of Scottsdale Design Standards & Policies Manual requires that wastewater pipes less than 15" or less in diameter must have a d/D ratio that does not exceed 0.65. Sewer pipes must also have a minimum velocity of 2.5 ft/s and less than 10 ft/s in the peak flow scenario.

4.1 BOUNDARY CONDITIONS

The wastewater outfall for the Phase 1 project site is an existing 39-inch wastewater main in the Hayden Road alignment. Two existing 8-inch wastewater mains that connect to the 39-inch wastewater main in Hayden Road remain in place and will be utilized to service Phase 1 of the project.

can remain 8" with
max flow of 439gm
@ d/D=0.68

The outfall for a portion of the Phase 2 site is the existing 8-inch sewer main in Parkway Avenue that outfalls to a 15-inch sewer main at the intersection of Indian School Road and Miller Road. This 8-inch sewer main was evaluated using a flow test performed by Western Environmental Equipment Company from December 8, 2018 to December 19, 2019. The highest peak flow is used for analysis when sizing the proposed sewer system. Based on the analysis, the existing 8-inch pipe in Parkway and Indian does not have sufficient capacity for the proposed flows. It is anticipated that the sewer main will need to be upsized to 15-inch to serve phase 2. It is anticipated that these improvements will occur with the Phase 2 development. Assuming worst case scenario for Phase 2 development site plans, a more detailed analysis will need to be performed with the final site plan to determine more accurate future flows and pipe capacity. Refer to Appendix D for the flow test results and Appendix C for the analysis of the pipes.

4.2 PHYSICAL PARAMETERS

Physical parameters used in the hydraulic analysis are summarized in Appendix B. Proposed pipe sizes used in this model are 8-inch for Phase 1 and 15-inch for Phase 2. Nodes defined in the schematic (see Appendix A) are placed at anticipated extents of service line locations. Each proposed building for Phase 1 has been assigned a node (see Appendix B). The wastewater generations for proposed commercial, retail, and restaurant square footage are equally distributed across the proposed buildings. A site plan does not exist for Phase 2. The wastewater generations are projected based on the anticipated density and land use for Phase 2. For the analysis, Phase 1 included two pools and Phase 2 included 1 pool. Refer to Appendix A for the layout of the sewer system for both phases.

4.3 WASTEWATER GENERATION SCENARIOS

The peak day wastewater generation was used to determine the required wastewater main sizes to serve this project.

The existing wastewater generation from the portions of Phase 2 that will be removed when Phase 2 is developed are calculated from a unit fraction and removed from the existing flow test results. 266 units will remain that utilize this Parkway Avenue sewer main. 354 existing units are being removed from the existing Phase 2 site. For the analysis of the proposed main in Parkway Avenue, the proposed supply is combined with the remaining unit flows as measured in the flow test.

The Excel spreadsheet in Appendix C shows the results of the hydraulic analysis for Phase 1 and Phase 2 of the site.

4.4 ANALYSIS RESULTS

The results of the wastewater analysis show that the Phase 1 portion of the site will discharge into two existing 8-inch sewer mains connected to the 39-inch wastewater main in Hayden Road.

The existing 8" in Phase 2 has a maximum full flow capacity of 306.8 gpm, while the proposed wastewater generation along with the existing peak flow totals to 510.5 gpm. For this reason, Phase 2 will be served by a 15-inch main that will replace an existing 8 inch main in Parkway Avenue extending down to Indian School to Miller Road. This 15" line will run at the same slopes as the existing 8" pipes. Refer to Appendix C for analysis and results.

The analyses show that the d/D ratio remains under the City of Scottsdale recommended 0.65 for all pipes while maintaining a velocity lower than 10 ft/s.

5.0 CONCLUSION


The Phase 1 portion of the site will utilize the two existing 8-inch sewer connections that cross Indian Bend Wash low flow channel and enter a 39-inch sewer main in Hayden Road.

Phase 2 will require upsizing an existing 8-inch sewer main to a 15-inch main in Parkway Avenue to the Indian School Road and Miller Road intersection. This will need to be verified with more testing during the development of Phase 2 that could be in 10 years or longer. The Phase 2 proposed generation is based on the highest generation scenario for the land use matrix currently available and will be updated at Final BOD.

incorrect, 692gpm is
proposed plus
existing

Upsize to 12" south to
Monterosa then 15"
south to Miller

APPENDIX A
EXHIBITS



LEGEND

GENTRY ON THE GREEN



ATWELL


866.850.4200 www.atwell-group.com

4700 E. SOUTHERN AVENUE
MESA, AZ 85206
480.218.8851

EXHIBIT 1 - VICINITY MAP

GENTRY ON THE GREEN

SCOTTSDALE, AZ




Phase Two
 Site Area: 14.97 gross acres

Phase One
 Site Area: 26.53 gross acres
 Residential Unit Total: 1,214 units
 Total Non-Residential Area: 21,000sf
 Total Retail Area: 20,000sf
 Total Retail Patio Area: 2,800sf
 Total Non-Residential / Retail Area: 43,800sf
 Total Parking Required: 1,950 spaces [per zoning ordinance]
 Total Parking Provided: 2,471 spaces [includes 78th street parking]

Site Plan



18160- 8/9/19



GENTRY ON THE GREEN- Scottsdale, Arizona

Notice of IP Rights: 2016 DAVIS. THESE DESIGNS ARE THE EXCLUSIVE PROPERTY OF DAVIS. NO USE OR REPRODUCTION IS PERMITTED WITHOUT THE EXPRESS WRITTEN PERMISSION OF DAVIS.





Phase Two

Phase One


- Phase 1A
- Phase 1B
- Phase 1C
- Phase 1D
- Phase 1E
- The Paseo

Phasing Exhibit



GENTRY ON THE GREEN- Scottsdale, Arizona

Notice of IP Rights: 2016 DAVIS. THESE DESIGNS ARE THE EXCLUSIVE PROPERTY OF DAVIS. NO USE OR REPRODUCTION IS PERMITTED WITHOUT THE EXPRESS WRITTEN PERMISSION OF DAVIS.




GENERAL NOTES:
 THIS IS A COMPUTER GENERATED DRAWING. FOR ANY REVISIONS PLEASE CONTACT THE CITY OF SCOTTSDALE GIS DEPARTMENT AT (480) 312-7792.

THE SECTION LINE BEARING AND DISTANCES ARE BASED ON THE CITY OF SCOTTSDALE GRID SURVEY OF SEPTEMBER, 1991. BEARINGS ARE NAD 83 GRID AND DISTANCES ARE FLATTENED TO GROUND. WHERE NO CORNER WAS FOUND THE DIMENSIONS ARE GIVEN TO CALCULATED SECTION CORNERS AND ARE NOTED AS "CALCULATED" ON THE MAP.


LEGEND:

- Water Valve
- Non-potable Water Valve
- Fire Hydrant
- Water Blowoff
- Water Main Reducer
- Water Sample Station
- Water Air Release Valve
- Non-potable Water Air Release Valve
- Water Pressure Reducing Valve
- Water Vault
- Water Manhole
- Non-Potable Water Manhole
- Water Pump
- Water Main
- Non-Potable Water Main
- Fire Line
- Water Service
- Non-Scottsdale Water Main
- Sewer Manhole
- Sewer Cleanout
- Sewer Lift Station
- Sewer Treatment Plant
- Sewer Main - Gravity
- Sewer Main - Force
- Non-Scottsdale Sewer Main
- Sewer Service

VICINITY MAP



NORTH



WATER & SEWER
 QUARTER SECTION MAP
17-46
 SE 1/4 SEC. 23 T2N R4E

11-ZN-2019

SCOTTSDALE GEOGRAPHIC INFORMATION SYSTEMS
 3629 North Drinkwater Boulevard
 Scottsdale, Arizona 85251

NOT TO SCALE
 THIS DOCUMENT IS PROVIDED FOR GENERAL INFORMATION PURPOSES ONLY. THE CITY OF SCOTTSDALE DOES NOT WARRANT ITS ACCURACY, COMPLETENESS OR SUITABILITY FOR ANY PARTICULAR PURPOSE. IT SHOULD NOT BE RELIED UPON WITHOUT FIELD VERIFICATION.
 THE CITY OF SCOTTSDALE
 09-SEP-18


COPYRIGHT © 2019 ATWELL LLC NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC

6119001704 - vicente-glen-conceptualwsgplan_sewer19001704-01.cad1.dwg Plotdate: 10/1/2019

LEGEND


- | | | | |
|--|---------------------------------|----------------------------|-------------------------|
| | MATCHLINE | EX. | EXISTING |
| | BOUNDARY LINE | ELEC | ELECTRIC |
| | LOT LINE | BFP | BACKFLOW PREVENTION |
| | CENTER LINE | G | GAS |
| | EASEMENT | WTR | WATER |
| | RIGHT-OF-WAY | SWR | SEWER |
| | EXISTING CONTOUR | P | PAVEMENT |
| | PROPOSED CONTOUR | R/W | RIGHT-OF-WAY |
| | RETAINING WALL | CL | CENTER LINE |
| | WATER LINE | B/C | BACK OF CURB |
| | FIRE HYDRANT | S/W | SIDEWALK |
| | WATER VALVE | C&G | CURB & GUTTER |
| | AIR RELEASE VALVE | E/P | EDGE OF PAVEMENT |
| | WATER METER BOX | PUE | PUBLIC UTILITY EASEMENT |
| | REDUCER | CB | CATCH BASIN |
| | SEWER LINE | MH | SEWER MANHOLE |
| | SEWER MANHOLE | SD | STORM DRAIN |
| | FLOW DIRECTION | SD MH | STORM DRAIN MANHOLE |
| | GRADE BREAK | | |
| | STREET SIGN POST | | |
| | STREET LIGHTS | | |
| | DRYWELL | | |
| | STORM DRAIN | | |
| | EXISTING GAS MANHOLE | | |
| | EXISTING SANITARY SEWER MANHOLE | | |
| | EXISTING ELECTRICAL PULL BOX | | |
| | EXISTING TELEPHONE PEDISTAL | | |
| | EXISTING GUY WIRE | | |
| | EXISTING POWER POLE | | |
| | EX. W | EXISTING WATER | |
| | EX. S | EXISTING SEWER | |
| | EX. G | EXISTING GAS | |
| | OHE | EXISTING OVERHEAD ELECTRIC | |

CONCEPTUAL WATER & SEWER PLAN FOR PHASE I OF GENTRY ON THE GREEN SCOTTSDALE, ARIZONA



THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE: CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSURE ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.



OWNER/DEVELOPER
COLRICH
444 WEST BEACH STREET, STE. 300
SAN DIEGO, CA 92101
PHONE: 858-490-2300
CONTACT: MATTHEW BATEMAN
EMAIL:

ENGINEER
ATWELL
4700 E. SOUTHERN AVENUE
MESA, AZ 85206
PHONE: 602-690-7527
CONTACT: RAMZI GEORGES
EMAIL: rgeorges@atwell-group.com

SHEET INDEX

SHEET No.	DESCRIPTION
01	COVER SHEET
02	WATER & SEWER PLAN
03	WATER & SEWER PLAN
04	WATER & SEWER PLAN
05	WATER & SEWER PLAN
06	WATER & SEWER PLAN
07	WATER & SEWER PLAN
08	WATER & SEWER PLAN
09	WATER & SEWER PLAN


KEY MAP
SCALE: 1" = 100'



COVER SHEET
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA



REVISIONS:




PM. R. GEORGES
DR. A. CABALLERO
JOB NO.
19001704
FILE NO.
19001704-01-CS01
01

SHEET NO.
01 OF 09

PROJECT NUMBER

COPYRIGHT © 2019 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.

6119001704 - vicente.ghe.comentarios@atwell.com & sewer19001704.dwg: uti.dwg PlotDate: 10/1/2019



NOTE:
ON-SITE UTILITIES TO BE REMOVED
BEFORE CONSTRUCTION.
UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING
UNDERGROUND UTILITIES ARE SHOWN
IN AN APPROXIMATE WAY ONLY AND
HAVE NOT BEEN INDEPENDENTLY
VERIFIED BY THE OWNER OR ITS
REPRESENTATIVE. THE CONTRACTOR
SHALL DETERMINE THE EXACT
LOCATION OF ALL EXISTING UTILITIES
BEFORE COMMENCING WORK AND
AGREES TO BE FULLY RESPONSIBLE
FOR ANY AND ALL DAMAGES WHICH
MIGHT BE OCCASIONED BY THE
CONTRACTOR'S FAILURE TO EXACTLY
LOCATE AND PRESERVE ANY AND ALL
UNDERGROUND UTILITIES.


NOTE:
CONSTRUCTION SITE SAFETY IS THE
SOLE RESPONSIBILITY OF THE
CONTRACTOR. NEITHER THE OWNER
NOR THE ENGINEER SHALL BE
EXPECTED TO ASSUME ANY
RESPONSIBILITY FOR SAFETY OF THE
WORK OF PERSONS ENGAGED IN THE
WORK OF ANY NEARBY STRUCTURES,
OR OF ANY OTHER PERSONS.



WATER & SEWER PLAN
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA




REVISIONS:




PM. R. GEORGES
DR. A. CABALLERO
JOB NO.
19001704
FILE NO.
19001704-02-UT01
02

SHEET NO.
02 OF 09

PROJECT NUMBER



COPYRIGHT © 2019 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.
6119001704 - visconte-green-center-wp-plan-wat-sv-concept-plan.dwg & sewer19001704-03-102.dwg PlotDate: 10/1/2019



NOTE:
ONSITE UTILITIES TO BE REMOVED BEFORE CONSTRUCTION. UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTE:
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.




WATER & SEWER PLAN
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA



REVISIONS:

NO.	DESCRIPTION




PM. R. GEORGES
DR. A. CABALLERO
JOB NO. 19001704
FILE NO. 19001704-03-UT02
03

SHEET NO.
03 OF 09

PROJECT NUMBER

COPYRIGHT © 2019 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.



NOTE:
 ONSITE UTILITIES TO BE REMOVED
 BEFORE CONSTRUCTION.
 UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING
 UNDERGROUND UTILITIES ARE SHOWN
 IN AN APPROXIMATE WAY ONLY AND
 HAVE NOT BEEN INDEPENDENTLY
 VERIFIED BY THE OWNER OR ITS
 REPRESENTATIVE. THE CONTRACTOR
 SHALL DETERMINE THE EXACT
 LOCATION OF ALL EXISTING UTILITIES
 BEFORE COMMENCING WORK, AND
 AGREES TO BE FULLY RESPONSIBLE
 FOR ANY AND ALL DAMAGES WHICH
 MIGHT BE OCCASIONED BY THE
 CONTRACTOR'S FAILURE TO EXACTLY
 LOCATE AND PRESERVE ANY AND ALL
 UNDERGROUND UTILITIES.

NOTICE:
 CONSTRUCTION SITE SAFETY IS THE
 SOLE RESPONSIBILITY OF THE
 CONTRACTOR. NEITHER THE OWNER
 NOR THE ENGINEER SHALL BE
 EXPECTED TO ASSUME ANY
 RESPONSIBILITY FOR SAFETY OF THE
 WORK OF PERSONS ENGAGED IN THE
 WORK OF ANY NEARBY STRUCTURES,
 OR OF ANY OTHER PERSONS.



WATER & SEWER PLAN
 CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
 SCOTTSDALE, ARIZONA




REVISIONS:

NO.	DATE	DESCRIPTION




PM. R. GEORGES
 DR. A. CABALLERO
 JOB NO.
 19001704
 FILE NO.
 19001704-04-UT03
04



SHEET NO.
04 OF 09

PROJECT NUMBER



NOTE:
ON-SITE UTILITIES TO BE REMOVED BEFORE CONSTRUCTION. UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.


NOTICE:
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.



WATER & SEWER PLAN
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA





REVISIONS:



PM. R. GEORGES
DR. A. CABALLERO
JOB NO. 19001704
FILE NO. 19001704-05-UT04
05

SHEET NO.
05 OF 09





NOTE:
ON-SITE UTILITIES TO BE REMOVED BEFORE CONSTRUCTION. UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK, OF PERSONS ENGAGED IN THE WORK, OR OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.




WATER & SEWER PLAN
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA



REVISIONS:


NO.	DESCRIPTION



PM. R. GEORGES
DR. A. CABALLERO
JOB NO. 19001704
FILE NO. 19001704-06-UT05
06

SHEET NO.
06 OF 09

PROJECT NUMBER



MATCHLINE SEE SHT 04

MATCHLINE SEE SHT #

NOTE:
ON-SITE UTILITIES TO BE REMOVED
BEFORE CONSTRUCTION.
UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING
UNDERGROUND UTILITIES ARE SHOWN
IN AN APPROXIMATE WAY ONLY AND
HAVE NOT BEEN INDEPENDENTLY
VERIFIED BY THE OWNER OR ITS
REPRESENTATIVE. THE CONTRACTOR
SHALL DETERMINE THE EXACT
LOCATION OF ALL EXISTING UTILITIES
BEFORE COMMENCING WORK AND
AGREES TO BE FULLY RESPONSIBLE
FOR ANY AND ALL DAMAGES WHICH
MIGHT BE OCCASIONED BY THE
CONTRACTOR'S FAILURE TO EXACTLY
LOCATE AND PRESERVE ANY AND ALL
UNDERGROUND UTILITIES.


NOTICE:
CONSTRUCTION SITE SAFETY IS THE
SOLE RESPONSIBILITY OF THE
CONTRACTOR. NEITHER THE OWNER
NOR THE ENGINEER SHALL BE
EXPECTED TO ASSUME ANY
RESPONSIBILITY FOR SAFETY OF THE
WORK OF PERSONS ENGAGED IN THE
WORK OF ANY NEARBY STRUCTURES,
OR OF ANY OTHER PERSONS.



WATER & SEWER PLAN
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA




REVISIONS:




PM. R. GEORGES
DR. A. CABALLERO
JOB NO.
19001704
FILE NO.
19001704-07-UT06
07

SHEET NO.
07 OF 09



COPYRIGHT © 2019 ATWELL LLC NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC

8119001704 - vicente-george-consulting-engineers-and-architects-llc-19001704-08-ud7.dwg Plot Date: 10/1/2019



NOTE:
ON-SITE UTILITIES TO BE REMOVED BEFORE CONSTRUCTION. UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE:
CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSURE ANY RESPONSIBILITY FOR SAFETY OF THE WORK OF PERSONS ENGAGED IN THE WORK OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.



WATER & SEWER PLAN
CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
SCOTTSDALE, ARIZONA




REVISIONS:

NO.	DATE	DESCRIPTION




PM. R. GEORGES
DR. A. CABALLERO
JOB NO. 19001704
FILE NO. 19001704-08-UT07
08

SHEET NO.
08 OF 09



PROJECT NUMBER

COPYRIGHT © 2019 ATWELL LLC. NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC.



NOTE:
 ONSITE UTILITIES TO BE REMOVED
 BEFORE CONSTRUCTION.
 UNLESS OTHERWISE NOTED.

THE LOCATIONS OF EXISTING
 UNDERGROUND UTILITIES ARE SHOWN
 IN AN APPROXIMATE WAY ONLY AND
 HAVE NOT BEEN INDEPENDENTLY
 VERIFIED BY THE OWNER OR ITS
 REPRESENTATIVE. THE CONTRACTOR
 SHALL DETERMINE THE EXACT
 LOCATION OF ALL EXISTING UTILITIES
 BEFORE COMMENCING WORK, AND
 AGREES TO BE FULLY RESPONSIBLE
 FOR ANY AND ALL DAMAGES WHICH
 MIGHT BE OCCASIONED BY THE
 CONTRACTOR'S FAILURE TO EXACTLY
 LOCATE AND PRESERVE ANY AND ALL
 UNDERGROUND UTILITIES.

ATWELL
 866.850.4200 www.atwell-group.com
 4700 E. SOUTHERN AVENUE
 MESA, AZ 85206
 480.276.8851

WATER & SEWER PLAN
 CONCEPTUAL WATER & SEWER PLAN
PHASE I OF GENTRY ON THE GREEN
 SCOTTSDALE, ARIZONA


811
 Know what's below.
 Call before you dig.

REVISIONS:

REGISTERED PROFESSIONAL ENGINEER
 37287
 RAMON
 GEORGES
 SCOTTSDALE, ARIZONA

PM. R. GEORGES
 DR. A. CABALLERO
 JOB NO.
 19001704
 FILE NO.
 19001704-09-UT08

SHEET NO.
09 OF 09



PROJECT NUMBER

APPENDIX B
WASTEWATER DEMAND CALCULATIONS

100gpm minimum of each separate sewer system with a pool must be applied.

should be 100gpm

NODE #	Land Use	Unit (Area or Dwelling Units)	Demand (gpd per unit)	Demand (gpm)	Peak Flow (gpm)	Peak Flow (MGD)
1	HDR (BLDG A)	302 DUs	140.0	29.4	132.1	0.19026
	Restaurant (BLDG A)	5,000 sq. ft.	1.2	4.2	25.0	0.036
	Pool (BLDG A)	1 ea (50%)	50 (gpm)	50.0	50.0	0.072
	Retail (BLDG A)	5,000 sq. ft.	0.5	1.7	5.2	0.0075
2	HDR (BLDG B)	380 DUs	140.0	36.9	166.3	0.2394
	Club Room / Gym (BLDG B)	10,500 sq. ft.	0.5	3.6	10.9	0.01575
6	HDR (BLDG C)	299 DUs	140.0	29.1	130.8	0.18837
	Restaurant (BLDG C)	5,000 sq. ft.	1.2	4.2	25.0	0.036
	Pool (BLDG C)	1 ea (50%)	50 (gpm)	50.0	50.0	0.072
	Retail (BLDG C)	5,000 sq. ft.	0.5	1.7	5.2	0.0075
7	HDR (BLDG D)	233 DUs	140.0	22.7	101.9	0.14679
	Club Room / Gym (BLDG D)	10,500 sq. ft.	0.8	5.8	17.5	0.0252
Phase 1 Wastewater Generation				239.3	720.0	1.03677

TABLE NOTE: the two pools flow into the same Hayden sewer system. They combine for a total 100 gpm into the Hayden sewer system, as required.

Land Use	Unit (Area or Dwelling Units)	Demand (gpd per unit)	Demand (gpm)	Peak Flow (gpm)	Peak Flow (MGD)	
HDR	9	270 DUs	140.0	26.3	118.1	0.1701
Healthcare ⁽⁴⁾	9	250 beds	250.0	43.4	195.3	0.28125
Hotel	9	150 rooms	380.0	39.6	225.0	0.324
Pool	9	1 ea	100 (gpm)	100.0	100.0	0.144
Phase 2 Wastewater Generation			209.2	638.4	0.91935	
Phase 1 & 2 Total Wastewater Generation			448.5	1,358.4	1.95612	

Monitored Peak Flow Rate (gpm)	Flow Removed for Phase 2 Development (gpm)	Remaining Flow After Ex. Phase 2 Unit Removal (gpm)	Proposed Peak Flow in Indian School Road and Parkway Avenue (gpm)	Proposed Peak Flow in Indian School Road and Parkway Avenue (gpm)
127.45	72.4992	54.9508	693.4	1.0

TABLE NOTE: Phase 2 wastewater generation based on flow monitoring of 12" main in Parkway Avenue. 266 DU remain after the removal of existing 354 DU from Phase 2.
127 gpm / (266+354) DU = 0.2048 gpm/DU

Notes:

- 1) Average Day Demand (ADD) based on City of Scottsdale Design Standards & Policies Manual.
- 2) Peaking Factors:

Land Use	Peaking Factor
HDR/ Healthcare	4.5
Commercial/ Retail/ Office	3.0
Restaurant	6.0
Hotel	4.5

- 3) Demand based on Arizona Administrative Code Title 18 Chapter 9 Unit Design Flows for wastewater.

existing 8" main



TABLE 2					
Existing Wastewater Generation - Phase 1					
Land Use	Unit (Area or Dwelling Units)	Wastewater Generation (gpd per unit)	Average Day Demand (gpm)	Peak Flow (gpm)	Peak Flow (MGD)
HDR (PHASE 1A+1B)	303 DUs	140.0000	29.5	132.6	0.19089
HDR (PHASE 1D)	172 DUs	140.0000	16.7	75.3	0.10836
Commercial	17,100 sq. ft.	0.0003	5.9	17.8	0.02565
Total Phase I Wastewater Generation			52.1	225.6	0.3249

Existing Wastewater Generation - Phase 2				
Land Use	Unit (Area or Dwelling Units)	Wastewater* Generation (gpm per unit)	Peak Flow (gpm)	Peak Flow (MGD)
HDR	354 DUs	0.2048	72.5	0.104398848
Total Phase II Wastewater Generation			72.5	0.104398848

*Phase 2 wastewater generation based on flow monitoring of 12" main in Parkway Avenue. 266 DU remain after the removal of existing 354 DU from Phase 2.
 $127 \text{ gpm} / (266+354) \text{ DU} = 0.2048 \text{ gpm/DU}$

Notes:

1) Average Day Demand (ADD) based on City of Scottsdale Design Standards & Policies Manual.

2) Peaking Factors:

Land Use	Peaking Factor
HDR/ Healthcare	4.5
Commercial/ Retail/ Office	3.0
Restaurant	6.0
Hotel	4.5

3) Demand based on Arizona Administrative Code Title 18 Chapter 9 Unit Design Flows for wastewater.



with 100gpm min
from pool max
d/D=0.68, this would
still be acceptable
over a short reach
and small basin such
as this. ✓

Phase I Peak Flow Wastewater System Hydraulic Analysis																
Pipes			Estimated Flow		Pipe Sizing								Performance			
Pipe Segment	Upstream Node	Downstream Node	Peak Flow (mgd)	Flow (cfs)	Pipe Dia. (in.)	Mannings "n"	Design Slope (ft/ft)	K	Central Angle θ (degrees)	Depth to Diameter h/D	Flow Area (ft ²)	Flow Velocity (ft/s)	Pipe Capacity (mgd)	Depth to Dia. ⁽²⁾ Check	Max Velocity ⁽¹⁾ Check	Capacity Check
1	1	2	0.306	0.47	8	0.013	0.01040	0.120	2.8972	0.439	0.148	3.21	0.778	OK	OK	OK
2	2	3	0.561	0.87	8	0.013	0.01040	0.219	3.6140	0.617	0.226	3.84	0.778	OK	OK	OK
3	3	4	0.561	0.87	8	0.013	0.01040	0.219	3.6140	0.617	0.226	3.84	0.778	OK	OK	OK
4	4	5	0.561	0.87	8	0.013	0.01030	0.221	3.6215	0.619	0.227	3.83	0.775	OK	OK	OK
5	6	7	0.304	0.47	8	0.013	0.01920	0.088	2.6251	0.372	0.118	3.97	1.050	OK	OK	OK
6	7	8	0.476	0.74	8	0.013	0.01040	0.186	3.3820	0.560	0.201	3.66	0.778	OK	OK	OK
7	8	9	0.476	0.74	8	0.013	0.01040	0.186	3.3820	0.560	0.201	3.66	0.778	OK	OK	OK
8	9	10	0.476	0.74	8	0.013	0.01040	0.186	3.3820	0.560	0.201	3.66	0.778	OK	OK	OK

1. Maximum velocity allowed = 10 ft/s
2. Maximum depth over diameter ratio = "OK" if ratio less than 0.65.


$$Q = \frac{1.486 \cdot A \cdot R^{\frac{2}{3}} \cdot S^{\frac{1}{2}}}{n}$$

Pipe flow parameters were estimated by Saatçi equations for partially filled circular pipes (Debo and Reese, 1995):

$$K = 0.673Q \cdot n \cdot D^{-\frac{8}{3}} \cdot S^{-\frac{1}{2}}$$

$$\theta = \frac{3\pi}{2} \left[1 - \left[1 - [\pi K]^{\frac{1}{2}} \right]^{\frac{1}{2}} \right]^{\frac{1}{2}}$$

$$\frac{h}{D} = \frac{1}{2} \left[1 - \cos\left(\frac{\theta}{2}\right) \right]$$



w/ 100gpm max d/D would be higher but still acceptable

Minimum Slopes		
Pipe Size (in)	Slope (ft/ft)	Full flow Velocity (ft/s)
8	0.0052	2.5
12	0.0030	2.5

Debo, Thomas N and Reese, Andrew J (1995). *Municipal Stormwater Management - 2nd edition*. Lewis Publishers - CRC Press LLC. Boca Raton, Florida

Notes:

- 1) BLDG 1 and BLDG 3 each account for the demands for a pool. The third pool is to be part of Phase 2.
- 2) Demands from the proposed restaurant, commercial, and retail are evenly distributed across the four building nodes.
- 3) Slopes for pipe segments 1 and 5 are determined from obtained survey data. All other pipe slopes are running at 1/8" per foot.

Phase 2 Peak Flow Wastewater System Hydraulic Analysis																
Pipes			Estimated Flow		Pipe Sizing									Performance		
Pipe Segment	Upstream Node	Downstream Node	Peak Flow (mgd)	Flow (cfs)	Pipe Dia. (in.)	Mannings "n"	Design Slope (ft/ft)	K	Central Angle θ (degrees)	Depth to Diameter h/D	Flow Area (ft ²)	Flow Velocity (ft/s)	Pipe Capacity (mgd)	Depth to Dia. ⁽²⁾ Check	Max Velocity ⁽¹⁾ Check	Capacity Check
9	11	12	0.998	1.54	15	0.013	0.00320	0.132	2.9909	0.462	0.555	2.78	2.159	OK	OK	OK
10	12	13	0.998	1.54	15	0.013	0.00280	0.141	3.0591	0.479	0.581	2.66	2.308	OK	OK	OK

1. Maximum velocity allowed = 10 ft/s
2. Maximum depth over diameter ratio = "OK" if ratio less than 0.65.

Minimum Slopes		
Pipe Size (in)	Slope (ft/ft)	Full flow Velocity (ft/s)
8	0.0052	2.5
12	0.0030	2.5


$$Q = \frac{1.486 \cdot A \cdot R^{\frac{2}{3}} \cdot S^{\frac{1}{2}}}{n}$$

Pipe flow parameters were estimated by Saatçi equations for partially filled circular pipes (Debo and Reese, 1995):

$$K = 0.673Q \cdot n \cdot D^{-\frac{8}{3}} \cdot S^{-\frac{1}{2}}$$

$$\theta = \frac{3\pi}{2} \left[1 - \left[1 - [\pi K]^{\frac{1}{2}} \right]^{\frac{1}{2}} \right]^{\frac{1}{2}}$$

$$\frac{h}{D} = \frac{1}{2} \left[1 - \cos\left(\frac{\theta}{2}\right) \right]$$



Debo, Thomas N and Reese, Andrew J (1995). *Municipal Stormwater Management - 2nd edition*. Lewis Publishers - CRC Press LLC. Boca Raton, Florida


Notes:

- 1) Phase 2 accounts for the demands of a pool.
- 2) Existing demands are subtracted from the proposed demands because the existing structures are being replaced.
- 3) The existing peak flow rate from the flow test at Indian School Road and Parkway Avenue is added to the proposed demands for phase 2.
- 3) Slopes for pipe segments 6 and 7 are determined from obtained survey data and quartersection invert data. Only Node 9 has an invert that is verified by survey data.
- 4) The existing 8" line in Parkway Ave and Indian School Road is analyzed as being upsized to a 12" pipe.

12" and 15" pipe,
Exhibit 5 shows all
15"

APPENDIX C
WASTEWATER SYSTEM HYDRAULIC ANALYSIS

19001704 - vicante-glen-cortesia\project_documents\engineering-planning-power and energy\reports\wastewater\exhibit\stwer_exhibit.dwg Sowdate: 9/30/2019 3:44 PM Plotdate: 9/30/2019 4:21 PM COPYRIGHT 2017 ATWELL LLC NO REPRODUCTION SHALL BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF ATWELL LLC



THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTICE: CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. NEITHER THE OWNER NOR THE ENGINEER SHALL BE EXPECTED TO ASSUME ANY RESPONSIBILITY FOR SAFETY OF THE WORK, OF PERSONS ENGAGED IN THE WORK, OF ANY NEARBY STRUCTURES, OR OF ANY OTHER PERSONS.

866.850.4200 www.atwell-group.com
4700 E. SOUTHERN AVENUE
MESA, AZ 85206

EXHIBIT 5: FULL BUILD OUT SEWER
PROJECT: GENTRY ON THE GREEN
CITY OF SCOTTSDALE, ARIZONA

811
Know what's below.
Call before you dig.

REVISIONS:

PM. R. GEORGES
DR. M. MENDEZ
JOB NO. 19001704
FILE NO.

GRAPHIC SCALE
1" = 120'


Worksheet for INDIAN SCHOOL ROAD - PROP. 15" DEPTH

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.0028
Diameter	15.0
Discharge	693.39
Results	
Normal Depth	7.1
Flow Area	0.6
Wetted Perimeter	1.9
Hydraulic Radius	3.6
Top Width	1.25
Critical Depth	5.9
Percent Full	47.1
Critical Slope	0.0053
Velocity	2.72
Velocity Head	0.11
Specific Energy	0.70
Froude Number	0.709
Maximum Discharge	1,650.25
Discharge Full	1,534.11
Slope Full	0.0006
Flow Type	Subcritical
GVF Input Data	
Downstream Depth	0.0
Length	0.0
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0
Profile Description	
Profile Headloss	0.00
Average End Depth Over Rise	0.0
Normal Depth Over Rise	75.0
Downstream Velocity	Infinity
Upstream Velocity	Infinity
Normal Depth	7.1
Critical Depth	5.9
Channel Slope	0.0028
Critical Slope	0.0053

Cross Section for INDIAN SCHOOL ROAD - PROP. 15" DEPTH

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth

Input Data	
Roughness Coefficient	0.013
Channel Slope	0.0028
Normal Depth	7.1
Diameter	15.0
Discharge	693.39



V: 1
H: 1

Worksheet for EX SS INDIAN SCHOOL RD MAX CAPACITY

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.0028
Diameter	8.0
Discharge	217.00
Results	
Normal Depth	5.2
Flow Area	0.2
Wetted Perimeter	1.3
Hydraulic Radius	2.3
Top Width	0.64
Critical Depth	3.9
Percent Full	65.0
Critical Slope	0.0070
Velocity	2.01
Velocity Head	0.06
Specific Energy	0.50
Froude Number	0.578
Maximum Discharge	308.71
Discharge Full	286.98
Slope Full	0.0016
Flow Type	Subcritical
GVF Input Data	
Downstream Depth	0.0
Length	0.0
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0
Profile Description	
Profile Headloss	0.00
Average End Depth Over Rise	0.0
Normal Depth Over Rise	75.0
Downstream Velocity	Infinity
Upstream Velocity	Infinity
Normal Depth	5.2
Critical Depth	3.9
Channel Slope	0.0028
Critical Slope	0.0070


Worksheet for PARKWAY AVENUE - PROP. 15" DEPTH

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.0032
Diameter	15.0
Discharge	693.39
Results	
Normal Depth	6.8
Flow Area	0.5
Wetted Perimeter	1.8
Hydraulic Radius	3.5
Top Width	1.24
Critical Depth	5.9
Percent Full	45.4
Critical Slope	0.0053
Velocity	2.85
Velocity Head	0.13
Specific Energy	0.69
Froude Number	0.762
Maximum Discharge	1,764.19
Discharge Full	1,640.03
Slope Full	0.0006
Flow Type	Subcritical
GVF Input Data	
Downstream Depth	0.0
Length	0.0
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0
Profile Description	
Profile Headloss	0.00
Average End Depth Over Rise	0.0
Normal Depth Over Rise	75.0
Downstream Velocity	Infinity
Upstream Velocity	Infinity
Normal Depth	6.8
Critical Depth	5.9
Channel Slope	0.0032
Critical Slope	0.0053

Cross Section for PARKWAY AVENUE - PROP. 15" DEPTH

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth

Input Data	
Roughness Coefficient	0.013
Channel Slope	0.0032
Normal Depth	6.8
Diameter	15.0
Discharge	693.39




V: 1
H: 1

Worksheet for Ex SS PARKWAY AVE MAX CAPACITY

Project Description	
Friction Method	Manning Formula
Solve For	Normal Depth
Input Data	
Roughness Coefficient	0.013
Channel Slope	0.0032
Diameter	8.0
Discharge	232.00
Results	
Normal Depth	5.2
Flow Area	0.2
Wetted Perimeter	1.3
Hydraulic Radius	2.3
Top Width	0.64
Critical Depth	4.0
Percent Full	65.0
Critical Slope	0.0071
Velocity	2.15
Velocity Head	0.07
Specific Energy	0.51
Froude Number	0.617
Maximum Discharge	330.02
Discharge Full	306.80
Slope Full	0.0018
Flow Type	Subcritical
GVF Input Data	
Downstream Depth	0.0
Length	0.0
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0
Profile Description	
Profile Headloss	0.00
Average End Depth Over Rise	0.0
Normal Depth Over Rise	75.0
Downstream Velocity	Infinity
Upstream Velocity	Infinity
Normal Depth	5.2
Critical Depth	4.0
Channel Slope	0.0032
Critical Slope	0.0071

APPENDIX D
FLOW TEST RESULTS



LOCATION OF
MANHOLE FLOW TEST


Indian School and Parkway

Flowlink 5

Level (2.571 in):2.45

Velocity (1.223 ft/s):1.35

Flow Rate (899259 gal):55.06



WATEWATER FLOW TEST RESULTS - PEAK FLOW

Site Name	Indian School and Parkway								
Label	Min Velocity	Time	Max Velocity	Time	Min Flow Rate	Time	Peak Flow Rate	Time	Total Flow
Units	ft/s	Date/Time	ft/s	Date/Time	gpm	Date/Time	gpm	Date/Time	gal
Resolution	0.1	N/A	0.1	N/A	0.1	N/A	0.1	N/A	0.1
Significant Digits	0	N/A	0	N/A	0	N/A	0	N/A	0
12/8/2018 0:00	0.759	5:34:00 AM	2.552	3:50:00 PM	13.229	5:34:00 AM	118.726	11:46:00 AM	77719
12/9/2018 0:00	0.996	3:22:00 AM	2.524	11:50:00 PM	0	4:40:00 AM	123.401	11:40:00 AM	80251.2
12/10/2018 0:00	0.925	9:00:00 PM	2.482	8:44:00 AM	0	5:12:00 AM	127.45	8:44:00 AM	77839.6
12/11/2018 0:00	0.75	7:04:00 PM	2.26	4:52:00 AM	14.011	4:08:00 AM	96.859	8:14:00 AM	74313
12/12/2018 0:00	0.86	12:02:00 AM	2.367	11:44:00 PM	15.171	2:20:00 AM	98.889	9:32:00 PM	77594.4
12/13/2018 0:00	0.794	11:00:00 PM	2.111	2:02:00 AM	12.32	4:18:00 AM	94.213	7:38:00 AM	70086.7
12/14/2018 0:00	0.737	12:40:00 PM	2.115	2:00:00 AM	10.978	3:02:00 AM	100.848	6:54:00 AM	70285.1
12/15/2018 0:00	0.703	9:04:00 PM	1.285	12:18:00 AM	14.031	4:50:00 AM	90.339	11:12:00 AM	74713.5
12/16/2018 0:00	0.553	1:22:00 AM	1.461	2:30:00 PM	15.467	1:22:00 AM	97.769	11:28:00 AM	75418.6
12/17/2018 0:00	0.722	10:24:00 AM	1.707	10:40:00 PM	15.907	3:04:00 AM	102.804	10:40:00 PM	71911.2
12/18/2018 0:00	0.528	4:22:00 PM	1.592	1:02:00 AM	0	4:32:00 PM	94.766	7:10:00 PM	71707.7

PEAK FLOW