

Abbreviated Water and Sewer Needs

Basis of Design Report

Sewer

Deer Valley Townhomes

NWC of Miller Road & Deer Valley Road

City of Scottsdale

Maricopa County, Arizona

TSC Project No. 0800

July 2019

Prepared for:

Beardsley 22, Inc 222 W Linger Lane, Phoenix, AZ 85021 FINAL Basis of Design Report

■ APPROVED

☑ APPROVED AS NOTED

☐ REVISE AND RESUBMIT



Disclaimer: If approved; the approval is granted under the condition that the final construction documents submitted for city review will match the information herein. Any subsequent changes in the water or sewer design that materially impact design criteria or standards will require re-analysis, re-submittal, and approval of a revised basis of design report prior to the plan review submission.; this approval is not a guarantee of construction document acceptance. For questions or clarifications contact the Water Resources Planning and Engineering Department at 480-312-5685.

BY scan

DATE 9/10/2019

Note: 6-inch sewer will be designated as private and will not be maintained by City of Scottsdale





<u>Tab</u>	<u>le of Contents</u>	
1.0	Introduction	1
2.0	Sewer System	2
3.0	Sewer Analysis	2
	3.1 Jurisdictional Design Criteria	2
	3.2 Proposed Wastewater Flows	2
	3.3 Sewer Calculations	3
4.0	Conclusion	3
	of Figures ure 1: Location Map	1
<u>List (</u>	of Appendices	
App	pendix A: Grading & Drainage Plan	



1.0 Introduction

The proposed Deer Valley Townhomes development (Project) consists of attached townhomes split between three (3) buildings on a one acre parcel. The Site is defined by the parcel boundary for APN# 212-02-010E and is located at the northwest corner of Miller Road and Deer Valley Road in Scottsdale (see figure 1 below). The current project zoning is PCOC and proposed project zoning is R-3. The site is currently undeveloped and the proposed development will be constructed all at once and will not be phased.

The purpose of this report is to evaluate the existing infrastructure and to determine if the proposed design will adequately support the calculated demands for the proposed developed Site. The Project will be designed and developed in accordance with the 2018 City of Scottsdale Design Standards & Policies Manual (DSPM), County, and State requirements.



Figure 1: Location Map

2.0 Sewer System

The site is a vacant lot with a channel along the east side. There are several existing sewer lines surrounding the property, according to City quarter section maps. Deer Valley Road has an existing 8" VCP sanitary sewer line that flows east to west. An 8" PVC sewer line exists in Miller Road that flows south. An existing sewer line exists in Calistoga Circle with a service stub extends into the Site at the northwest corner. **Appendix A** shows the exact connection location. The proposed sewer system will utilize the existing sewer stub to the property and tie into the main within Calistoga Circle. A 6" PVC sewer line will service the site with 4" laterals to each home.

Based on discussions with the City of Scottsdale, the downstream sewer main and wastewater treatment plant has sufficient capacity to support the Project's sewer proposed flows. The sewer flow from the Project will be conveyed to the City of Scottsdale Wastewater Treatment Plant, 4.2 miles downstream.

3.0 Sewer Analysis

3.1 Jurisdictional Design Criteria

Based on the DSPM all sewer lines shall be designed to provide a minimum peak flow velocity of 2.5 feet per second when flowing completely full and a maximum velocity of 10.0 feet per second. A Manning's roughness coefficient, "n", of 0.013 will be used for all pipe materials. Per MAG Standard Detail 404, the minimum slope requirement for six (6) inch diameter sewer service is 2.08%. Upon completion of the plumbing design in the construction document phase, the service lines to each home or structure will be sized. Cleanouts are located at any direction change greater than 45° or at the end of the line. All buildings are required to have a two-way cleanout at the building per 2015 International Plumbing Code (IPC). Cleanout spacing is equal to or less than 100'.

3.2 Proposed Wastewater Flows

This report supplements preliminary plans proposing 9 residential units. As a result, the final total projected wastewater flow is calculated as follows:

Average Daily Demand =

100 gpcpd

Average Daily Flow (ADF) = 9 DU x 100 gpcpd x 2.5 p/DU = 2,250 gpd

Peak Daily Flow (PDF) = ADF \times 4.0 =

9,000 gpd

^{*}ADF based on DSPM section 7-1.403.A

^{*}PDF based on DSPM figure 7-1.2

3.3 Sewer Calculations

Flow capacity per Manning's formula for uniform pipe flow:

$$Q = \frac{1.49}{n} (A) (R_h)^{\frac{2}{3}} (S)^{\frac{1}{2}}$$

Where:

Q = Pipe capacity (cfs)

n = Manning's roughness coefficient

A = Cross sectional area (ft²)
R = Hydraulic radius (ft.)
S = Minimum slope (ft/ft)

Capacity for a full flowing 6" diameter pipe with a minimum slope of 0.0208 ft/ft:

$$\frac{1.49}{0.013}(\pi 0.25^2)(0.13)^{\frac{2}{3}}(0.0208)^{\frac{1}{2}} = 0.81\ cfs = 523{,}517\ gpd$$

9,000 gpd << 523,517 gpd pipe capacity

Flow velocity per Manning's formula for uniform pipe flow:

$$V = \frac{1.49}{n} (R_h)^{\frac{2}{3}} (S)^{\frac{1}{2}}$$

Where:

V = Pipe velocity (ft/s)

n = Manning's roughness coefficient

R_h = Hydraulic radius (ft.) S = Minimum slope (ft/ft)

The full-flow velocity computed for a 6" sewer line:

$$\frac{1.49}{0.013}(0.13)^{\frac{2}{3}}(0.0208)^{\frac{1}{2}} = 4.12 \, ft/s$$


4.12 fps > 2.5 fps


4.0 Conclusion


As demonstrated, the proposed sewer system for Deer Valley Townhomes will be in accordance with the 2018 City of Scottsdale Design Standards & Policies Manual and have the capacity to service 9 townhomes on a one acre site. The proposed demand is well under the proposed capacity and an acceptable velocity is obtained.


APPENDIX A

PRELIMINARY GRADING & DRAINAGE PLAN









- 1. MC-3500 CHAMBERS SHALL CONFORM TO THE REQUIREMENTS OF ASTM F2418 "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 2. MC-3500 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 3. "ACCEPTABLE FILL MATERIALS" TABLE ABOVE PROVIDES MATERIAL LOCATIONS, DESCRIPTIONS, GRADATIONS, AND COMPACTION REQUIREMENTS FOR FOUNDATION, EMBEDMENT, AND FILL MATERIALS.
- 4. THE "SITE DESIGN ENGINEER" REFERS TO THE ENGINEER RESPONSIBLE FOR THE DESIGN AND LAYOUT OF THE STORMTECH CHAMBERS FOR THIS PROJECT.
- 5. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 6. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 7. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.

Volume Provided									
Number of chambers		6 (4 DIDE)	Volume Per Chamber	110 cf					
Number of End Caps		2 (1 PIPE)	Volume Per End Cap	16 cf					
Area		440 sf	Excavation Length	52 lf					
Perimeter		121 ft	Excavation Width	8 If					
Stone above		12 in	Excavation Depth (Including cover)	6 If					
Stone below		9 in	NOTE: TOTAL LENGTH OF STORAGE TANK = CHAMBERS PLUS END CAPS, EACH						
Voids in stone		40 %							
Length of Isolator Row		47 ft	CHAMBER IS 7.17 FT IN LENGTH AND						
			END CAP IS 1.88 FT IN LENGTH.						
Volume in chambers	# of Chambers * 109.9	659 cf							
Volume in End Caps	# of caps * 15.6	31 cf							
Volume of excavation	LXWXD	2422 cf							
Amount of stone	Vexc - Vchmb	1731 cf							
Volume in stone	Void % * Amount _{stone}	693 cf							
Amount of Filter Fabric	2*Area + Perimeter *(6 +Cover)	1822 sf							
Volume Provided	$V_{chmb} + V_{stone}$	1352 cf							

PAVING, GRADING AND DRAINAGE NOTES

1 GRADE TO DRAIN

8" SOLID WHITE LINE

4" DOUBLE YELLOW LINE

2 GRADE 4' WIDE DRAINAGE SWALE TO DRAIN; LINE WITH 4" DIA. LANDSCAPE ROCK.

3 2' WIDE CURB OPENING.

RETAINING WALL WITH SAFETY RAIL. WALL HEIGHT VARIES, PER PLAN. WALL FOOTING 4 SHALL EXTEND BELOW TOP OF BANK TURN DOWN FOR RIP RAP, WHERE APPLICABLE ALONG EX. CHANNEL.

5 EXPOSED STEM WALL; REFER TO ARCHITECTURAL PLANS.

6 MIN. 2' SAWCUT AND CONCRETE TO REMAIN. MIN. 2' SAWCUT AND REMOVE EX. A.C.C.P. ROADWAY. PROTECT EXISTING ASPHALT

7 DRIVEWAY PER C.O.S. STD. DTL. 2255; SIDEWALK MODIFIED PER PLAN.

8 WIDEN A.C.C.P. ROADWAY TO LIMITS SHOWN.

9 OBLITERATE PAVEMENT MARKINGS 10 MATCH EXISTING.

| 11 | 2' DEEP RIP RAP D50 = 6" TO BE INSTALLED AGAINST RETAINING; MATCH EXISTING

41715 LISA NELSON 03/25/1/9 EXPIRES 12/31/2019

DEER VALLEY TOWNHOMES

PRELIMINARY GRADING & DRAINAGE

Contact Arizona 311 at least two full working days before you begin excavatio BLUI STAKE, INC. Call 811 or eliek Arizona811.com DESCRIPTION

08/27/18 CITY SUBMITTA CITY SUBMITTAI 02/06/19 03/25/19 CITY SUBMITTAI

CHECKED BY: LMN DRAWN BY: CMA

TITLE: PRELIMINARY **GRADING & DRAINAGE**

2 of 2

SHEET No.

PROJECT No.



Basis of Design Report for

Sewer



☐ APPROVED AS NOTED☐ REVISE AND RESUBMIT

Report

✓ APPROVED

FINAL Basis of Design

Disclaimer: If approved; the approval is granted under the condition that the final construction documents submitted for city review will match the information herein. Any subsequent changes in the water or sewer design that materially impact design criteria or standards will require re-analysis, re-submittal, and approval of a revised basis of design report prior to the plan review submission.; this approval is not a guarantee of construction document acceptance. For questions or clarifications contact the Water Resources Planning and Engineering Department at 480-312-5685.

BY scan

DATE 7/13/2020

Deer Valley Townhomes

NWC of Miller Road & Deer Valley Road

City of Scottsdale

Maricopa County, Arizona

City of Scottsdale Case Number: 43-DR-2019

TSC Project No. 0800


June 9th, 2020

Prepared for:

Beardsley 22, Inc 222 W Linger Lane, Phoenix, AZ 85021 480-899-4330

Prepared by:

Lisa Nelson, P.E.
645 E. Missouri Avenue, Suite 160
Phoenix, AZ 85014
480-454-1807
Inelson@terrascape.us





<u>Table</u>	e of Contents	
1.0	Introduction	1
2.0	Sewer System	1
3.0	Sewer Analysis	2
	3.1 Jurisdictional Design Criteria	2
	3.2 Proposed Wastewater Flows	2
	3.3 Sewer Calculations	3
4.0	Conclusion	4
<u>List o</u>	<u>f Figures</u>	
Figure	e 1: Vicinity Map	1
List o	f Appendices	

REFERENCES:

- 2018 City of Scottsdale Design Standards and Policies Manual Chapter 7 (Wastewater)
- ADEQ Engineering Bulletin No.1 Chapter 4 (Sewerage collection Systems)
- International Plumbing Code 2015

Appendix A: Grading & Drainage Plan



1.0 Introduction

The proposed Deer Valley Townhomes development (Project) consists of attached townhomes split between three (3) buildings, 9 units on a one acre parcel. The proposed total disturbed area is 0.68 acres which include approx. 12,332 SF of building area. The lowest finished floor elevation of the site is 1779. The Site is defined by the parcel boundary for APN# 212-02-010E and is located at the northwest corner of Miller Road and Deer Valley Road in Scottsdale (see figure 1 below). The project zoning is R-3. The Site is currently undeveloped and the proposed development will be constructed all at once and will not be phased.




Figure 1 Vicinity Map

The purpose of this report is to evaluate the existing infrastructure and to determine if the proposed design will adequately support the calculated demands for the proposed developed Site. The Project will be designed and developed in accordance with the 2018 City of Scottsdale Design Standards & Policies Manual (DSPM), County, and State requirements.

2.0 <u>Sewer System</u>

The Site is a vacant lot with a channel along the east side. There are several existing sewer lines surrounding the property, according to City quarter section maps. An existing sewer line exists in Calistoga Circle with a service stub extends into the Site at the northwest corner. An 8" PVC sewer line exists in Miller Road that flows south. Deer Valley Road has an existing 8" VCP sanitary sewer line that flows east to west.

The proposed sewer system will tie into the existing sewer line in Dear Valley Road with a proposed sanitary sewer manhole. **Appendix A** shows the connection

location. An 8" PVC sewer line will service the Site with 6" laterals in the east and west direction and 4" building connections to each unit. The building connections are proposed 3.4' below finished floor elevation. Refer to Preliminary G&D Plan in **Appendix A** for proposed sewer system layout. The onsite sewer system will be privately owned and maintained.

Based on discussions with the City of Scottsdale, the downstream sewer main and wastewater treatment plant has sufficient capacity to support the Project's sewer proposed flows. The sewer flow from the Project will be conveyed to the City of Scottsdale Wastewater Treatment Plant, 4.2 miles downstream.

3.0 <u>Sewer Analysis</u>

3.1 Jurisdictional Design Criteria

Based on the DSPM all sewer lines shall be designed to provide a minimum peak flow velocity of 2.5 feet per second and a maximum velocity of 10.0 feet per second. The depth to diameter ratio (d/D) for gravity sewer shall not exceed 0.65. A Manning's roughness coefficient, "n", of 0.013 will be used for all pipe materials. Per ADEQ Engineering Bulletin No.11, Chapter 4, Table IV-1, in order to maintain a minimum velocity of 2.5 fps, the minimum slope requirement for eight (8) inch diameter sewer is 0.52%. 4" and 6" pipes will be utilized as laterals or building connections and shall have a minimum slope of 2.08% per International Plumbing Code (2015 IPC). Cleanouts are located at any direction change greater than 45° or at the end of the line. All buildings are required to have a two-way cleanout at the building per IPC. Cleanout spacing is equal to or less than 100'.

3.2 Proposed Wastewater Flows

This report supplements preliminary plans proposing 9 residential units. As a result, the final total projected wastewater flow is calculated as follows:

Average Daily Demand =

100 gpcpd

Average Daily Flow (ADF) = 9 DU x 100 gpcpd x 2.5 p/DU = 2,250 gpd

Peak Daily Flow (PDF) = ADF \times 4.0 =

9,000 gpd

^{*}ADF based on DSPM section 7-1.403.A

^{*}PDF based on DSPM figure 7-1.2

3.3 Sewer Calculations

• Flow capacity per Manning's formula for uniform pipe flow:

$$Q = \frac{1.49}{n} (A) (R_h)^{\frac{2}{3}} (S)^{\frac{1}{2}}$$

Where:

Q = Pipe capacity (cfs)

n = Manning's roughness coefficient

A = Cross sectional area (ft²)
R = Hydraulic radius (ft.)
S = Minimum slope (ft/ft)

The flowing full (d/D=0.65) capacity for the proposed 8" sewer line into the Site with a minimum slope of 0.52%:

$$\frac{1.49}{0.013}(\pi 0.33^2)(0.19)^{\frac{2}{3}}(0.0052)^{\frac{1}{2}} = 0.93 \ cfs = 601,074 \ gpd$$

9,000 gpd << 601,074 gpd pipe capacity

The flowing full (d/D=0.65) capacity for 6" lateral to serve the 4" building services at a minimum slope of 2.08%:

$$\frac{1.49}{0.013}(\pi 0.25^2)(0.14)^{\frac{2}{3}}(0.0208)^{\frac{1}{2}} = 0.88\ cfs = 568,759\ gpd$$

9,000 gpd << 568,759 gpd pipe capacity

The capacity for the existing 8" sewer main in E. Deer Valley Road (1.24% slope, generated from As-Built plan), d/D=0.65:

$$\frac{1.49}{0.013}(\pi 0.33^2)(0.19)^{\frac{2}{3}}(0.0124)^{\frac{1}{2}} = 1.44 \ cfs = 930,696 \ gpd$$

9,000 gpd << 930,696 gpd pipe capacity

• Flow velocity per Manning's formula for uniform pipe flow:

$$V = \frac{1.49}{n} (R_h)^{\frac{2}{3}} (S)^{\frac{1}{2}}$$

Where:

V = Pipe velocity (ft/s)

n = Manning's roughness coefficient

R_h = Hydraulic radius (ft.) S = Minimum slope (ft/ft) The velocity computed for an 8" sewer line flowing full capacity d/D=0.65 and a 0.52% slope:

$$\frac{1.49}{0.013}(0.19)^{\frac{2}{3}}(0.0052)^{\frac{1}{2}} = 2.73 \, ft/s$$


$$2.5 \, \text{fps} < \underline{2.73 \, \text{fps}} < 10 \, \text{fps}$$


4.0 Conclusion


As demonstrated, the proposed sewer system for Deer Valley Townhomes will be in accordance with the 2018 City of Scottsdale Design Standards & Policies Manual and have the capacity to service 9 townhomes on a one acre site. The project demand is less than the 8" sewer line capacity and an acceptable velocity is achieved. The Site flow is insignificant compared to contributing flows from the surrounding development and therefore the impact on the City main is negligible.

APPENDIX A

PRELIMINARY GRADING & DRAINAGE PLAN








SEE PLAN

UNDERDRAIN DETAIL



- 1. MC-3500 CHAMBERS SHALL CONFORM TO THE REQUIREMENTS OF ASTM F2418 "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 2. MC-3500 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 3. "ACCEPTABLE FILL MATERIALS" TABLE ABOVE PROVIDES MATERIAL LOCATIONS, DESCRIPTIONS, GRADATIONS, AND COMPACTION REQUIREMENTS FOR FOUNDATION, EMBEDMENT, AND FILL MATERIALS.
- 4. THE "SITE DESIGN ENGINEER" REFERS TO THE ENGINEER RESPONSIBLE FOR THE DESIGN AND LAYOUT OF THE STORMTECH CHAMBERS FOR THIS PROJECT.
- 5. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 6. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 7. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.

		Volume Provided		
Number of chambers		6 (4 DIDE)	Volume Per Chamber	110 cf
Number of End Caps		2 (1 PIPE)	Volume Per End Cap	16 cf
Area		440 sf	Excavation Length	52 lf
Perimeter		121 ft	Excavation Width	8 If
Stone above		12 in	Excavation Depth (Including cover)	6 If
Stone below		9 in	NOTE, TOTAL LENGTH OF STORAGE I	- A N II / -
Voids in stone		40 %	NOTE: TOTAL LENGTH OF STORAGE TANK = CHAMBERS PLUS END CAPS. EACH CHAMBER IS 7.17 FT IN LENGTH AND EAC	
Length of Isolator Row		47 ft		
			END CAP IS 1.88 FT IN LENGTH.	
Volume in chambers	# of Chambers * 109.9	659 cf		
Volume in End Caps	# of caps * 15.6	31 cf		
Volume of excavation	LXWXD	2422 cf		
Amount of stone	Vexc - Vchmb	1731 cf		
Volume in stone	Void % * Amount _{stone}	693 cf		
Amount of Filter Fabric	2*Area + Perimeter *(6 +Cover)	1822 sf		
Volume Provided	$V_{chmb} + V_{stone}$	1352 cf		

PAVING, GRADING AND DRAINAGE NOTES

1 GRADE TO DRAIN

8" SOLID WHITE LINE

4" DOUBLE YELLOW LINE

2 GRADE 4' WIDE DRAINAGE SWALE TO DRAIN; LINE WITH 4" DIA. LANDSCAPE ROCK.

3 2' WIDE CURB OPENING.

RETAINING WALL WITH SAFETY RAIL. WALL HEIGHT VARIES, PER PLAN. WALL FOOTING SHALL EXTEND BELOW TOP OF BANK TURN DOWN FOR RIP RAP, WHERE APPLICABLE ALONG EX. CHANNEL.

5 EXPOSED STEM WALL; REFER TO ARCHITECTURAL PLANS.

6 MIN. 2' SAWCUT AND CONCRETE TO REMAIN. MIN. 2' SAWCUT AND REMOVE EX. A.C.C.P. ROADWAY. PROTECT EXISTING ASPHALT

7 INSTALL CL-1 DRIVEWAY PER C.O.S. STD. DTL. 2256; SIDEWALK MODIFIED PER PLAN.

8 SAWCUT, CLEAN EDGE, AND WIDEN A.C.C.P. ROADWAY TO LIMITS SHOWN.

9 OBLITERATE PAVEMENT MARKINGS

10 MATCH EXISTING.

| 11 | 2' DEEP RIP RAP D50 = 6" TO BE INSTALLED AGAINST RETAINING; MATCH EXISTING

41715 LISA NELSON

DEER VALLEY TOWNHOMES

PRELIMINARY GRADING & DRAINAGE

Contact Arizona 311 at least two full BLAND STRAND, 1892. Call 811 or eliek Arizona811.com

DESCRIPTION 08/27/18 CITY SUBMITTA CITY SUBMITTA 02/06/19

2ND DRB SUBMITTA

CITY SUBMITTAI

03/25/19

06/08/20 3RD DRB SUBMITTA

CHECKED BY: LMN

DRAWN BY: CMA TITLE: PRELIMINARY

GRADING & DRAINAGE

2 of 2

SHEET No.

PROJECT No.